

SECTION 02719 - MAILBOXES

PART 1- GENERAL

1.1 DESCRIPTION

- A. The WORK under this Section includes providing all labor, materials, tools and equipment necessary to remove, relocate, or reconstruct existing mailboxes; and/or construct new cantilever single, or cantilever gang-type mailboxes, as shown on the Drawings and CBJ Standard Details 116 - Cantilever Single Mailbox and 117 - Cantilever Gang Mailbox, or as directed by the ENGINEER.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Materials shall conform to the requirements of CBJ Standard Details 116 - Cantilever Single Mailbox and 117 - Cantilever Gang Mailbox.
- B. The existing mailbox receptacle may be reused, if found to be in suitable condition, as determined by the ENGINEER. If the mailbox receptacle is determined by the ENGINEER to be unsuitable for reuse, or if the existing receptacle is damaged by the CONTRACTOR, a new receptacle of similar size and new lettering and/or numbers shall be provided at the CONTRACTORS's expense.
- C. The length of the cantilever arm from the edge of the post to the end of the support arm may be reduced to 36 inches for those mailboxes located behind the sidewalk.
- D. The face of the mailbox receptacle shall align with the traveled edge of shoulder, back edge of paved sidewalk, or back edge of curb if no sidewalk is present.

PART 3 - EXECUTION

3.1 GENERAL

- A. Existing mailboxes in conflict with construction shall be reconstructed and relocated to satisfy the requirements of the CBJ Standard Details. The CONTRACTOR shall ensure that daily mail service will remain uninterrupted to all residents affected by the construction.
- B. Only those mailboxes actually reconstructed will be considered for measurement for payment under this item. Mailboxes that conform to the CBJ Standard Details, but require only relocation, will not be measured for payment and will be considered incidental to other WORK.
- C. Where two mailboxes are shown together on the Drawings, a single post assembly with two mail receptacles shall be constructed to conform to CBJ Standard Detail 117 - Cantilever Gang Mailbox.

END OF SECTION