



**NOTES:**

1. SLAB SHALL BE REINFORCED WITH #6 @5" BOTTOM AND #4 @7" TOP. PROVIDE A MINIMUM OF #4 @12" TOP AND BOTTOM PERPENDICULAR TO MAIN REINFORCEMENT.
2. REINFORCING COVER SHALL BE 2-INCHES CLEAR AT TOP AND BOTTOM SURFACES.
3. LID TO BE H-20 LOADING PER MANHOLE MANUFACTURER.

<b>SCALE:</b> NTS	<b>DATE:</b> 1/18/00	<b>CITY AND BOROUGH OF JUNEAU, ALASKA</b>	
<b>DRAWN BY:</b> STAFF	<b>CHECKED BY:</b> JB/STAFF	<b>PUMP STATION DETAILS</b>	
<b>APPROVED BY:</b> 		<b>REVISED:</b> 8/14/2011	<b>STANDARD 220-4</b>