

SECTION 02806 - REMOVE EXISTING ASPHALT SURFACING

PART 1 - GENERAL

1.1 DESCRIPTION

- A. The WORK under this Section includes providing all labor, materials, tools and equipment necessary to remove existing asphalt surfacing as shown on the Drawings and Standard Details or as directed by the ENGINEER.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. All materials shall conform to the requirements of the Specifications or to the requirements of the agency having jurisdiction over the pavement being replaced.

PART 3 – EXECUTION

3.1 GENERAL

- A. Asphalt Pavement to be removed shall be neatly saw cut full depth along straight lines, with a tolerance of 0.1 feet in 50 feet and 0.2 feet in 100 feet. Only such pavement shall be removed as is necessary to excavate for the appurtenances, but the pavement shall be cut a sufficient distance outside the excavation to prevent damage to adjacent pavement by lifting or tearing the mat. All removed pavement shall be disposed off of the Project at an approved disposal site.
- B. The CONTRACTOR shall deliver the removed asphalt surfacing material to the asphalt disposal stockpile in the CBJ/State Lemon Creek Gravel Pit. The CONTRACTOR shall stack the material with a loader if required by the ENGINEER.
- C. If the CONTRACTOR fails to comply with the provisions of any CBJ ordinance or permit pertaining to waste disposal or disposal sites; the CBJ shall have the right, after giving 30 days written notice, to bring the disposal sites into compliance and collect the cost of the WORK from the CONTRACTOR, either directly or by withholding monies otherwise due under the contract.

END OF SECTION