

**SECTION 03304 - REMOVE EXISTING SIDEWALK, CONCRETE SLAB,  
OR CURB AND GUTTER**

**PART 1 – GENERAL**

1.1 DESCRIPTION

- A. The WORK under this section includes providing all labor, materials, tools, and equipment necessary for removing and disposing of existing concrete sidewalks, concrete slabs, concrete curb and gutter, or concrete valley gutter as indicated on the Drawings or as directed by the ENGINEER

**PART 2 - PRODUCTS (Not Used)**

**PART 3 - EXECUTION**

3.1 CONSTRUCTION

- A. Sidewalks, concrete slabs, curb and gutter, or valley gutter to be removed shall be separated from the remaining portion by saw cutting. Saw cuts shall be at right angles to the curb, sidewalk, or slab edge. Broken edges shall be trimmed to eliminate jagged or irregular surfaces. The CONTRACTOR shall dispose of the material at an approved disposal area.
- B. The CONTRACTOR is responsible to secure disposal sites, including obtaining written permission from the owner and any required permits, if none are indicated on the Drawings. The cost of securing such sites shall be borne by the CONTRACTOR.

**END OF SECTION**