



ADDENDUM TO THE CONTRACT

for the

Glacier Fire Station Siding Replacement Contract No. BE20-182

ADDENDUM NO.: ONE

CURRENT DEADLINE FOR BIDS:

May 14, 2020

PREVIOUS ADDENDA: NONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED:

April 24, 2020

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php

Information Item:

Item No. 1. Sheet A302 DETAIL 2 – Text 'LADDER PROTECTION' and Sheet A801 DETAILS 1, 2 & 4 text including "LADDER" refers to CCFR's wood sheathed wall assembly for ladder training purposes. All metal roof access ladders are to be reinstalled in existing locations.

Supplemental Information Item: (See Bid Website)

- Reference Photos of existing exterior conditions at Glacier Fire Station- 2 pages
- Existing Access Ladder Information- 3 pages
- All Asbestos Containing Materials- Sampling & Lab Test Results. All exterior ACM was abated in 2008.

No Asbestos Containing Materials are expected to be found during the Glacier Fire Station- Exterior Siding Replacement Project. If any concealed areas are suspected, the Owner will arrange for and pay for sampling and testing on a case by case basis.

PROJECT MANUAL:

Item No. 1. SECTION 00310 BID SCHEDULE **Delete** in its entirety and replace with attached Bid Schedule labeled ADDENDUM 1.

DRAWINGS:

Item No. 1. SHEET A302, **Add** Note 1 to detail 2: Aluminum letters and number to meet the following specifications:

0.090" Alum face thickness, Min
0.063" Alum return thickness, Min
Brushed Alum finish
Lexan Back (for back lit letter)
White LED Color (for back lit letter)

By: Paula Osborn for
Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 3

SECTION 00310 - BID SCHEDULE

Bid Schedule for construction of **E20-182 Glacier Fire Station Siding Replacement**, in accordance with the Contract Documents.

BASE BID - Furnish all labor, equipment and materials for demolition of existing metal siding and flashings, exterior windows, exterior metal doors, site, exterior light fixtures and installation of metal wall panel assemblies, metal flashing and accessories and exterior metal doors. and perform all WORK as described in these Contract Documents.

TOTAL BASE BID \$ _____
(Price in Figures)

ADDITIVE ALTERNATE NO. 1 - Metal Signage Letter With Backlighting

Installation of the metal signage letters as shown and all associated electrical for the letter backlighting

TOTAL ADDITIVE ALTERNATE NO. 1 \$ _____
(Price in Figures)

ADDITIVE ALTERNATE NO. 2 - Metal Signage Letter Without Backlighting

Installation of the metal signage letters as shown with no back lighting or associated electrical work for the backlighting.

TOTAL ADDITIVE ALTERNATE NO. 2 \$ _____
(Price in Figures)

Date: _____ **Bidder:** _____
(Company Name)

END OF SECTION