**ADDENDUM TO THE CONTRACT**

**for the**

**UNIVERSITY DRIVE LIGHTING UPGRADES**

**Contract No. BE21-092**

| | |
|---|---|
| **ADDENDUM NO.:**     **THREE** | **CURRENT DEADLINE FOR BIDS:** |
| | **March 2, 2021** |

**PREVIOUS ADDENDA: TWO**

**ISSUED BY:**  City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED:**                            **February 26, 2021**

The following items of the contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering-public-works

**PROJECT MANUAL:**

Item No. 1     SECTION 00852 – Permits
*Delete* Section 00852 *in its entirety.*

Item No. 2     SPECIAL PROVISIONS, Section 16521 – Exterior Lighting, Subsection 2.4 – Finishes, Paragraph C.
*Delete and replace* Paragraph C *with* the following:

"C.     Factory-Painted Finish: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

       1.     Interior Surfaces of Pole: One coat of bituminous paint, or otherwise treat for equal corrosion protection.
       2.     Exterior Surfaces: Per manufacturer's standard for corrosion protection.
           a.     Color: As indicated by the specifications in the drawings."

**DRAWINGS:**

Item No. 1    SHEET E-04 – One Line
*Add* the following Sheet Note #4:

"4. The contractor shall install No. 1/0 conductors as shown. No. 10 awg tap conductors are acceptable for connecting the individual light fixtures.  Conductors shall be free of splicing, except at each light location, slicing is allowed in the hand hole only."

Item No. 2    SHEET E-07 – Footing & Junction Box
*Delete and replace* the label that reads "Galvanized light pole"
*with* "Non-tapered steel pole."


By: _____
              Greg Smith,
         Contract Administrator


Total number of pages contained within this Addendum: 2