



## ADDENDUM TO THE CONTRACT

for the

### TONGASS BOULEVARD RECONSTRUCTION, PHASE 1 Contract No. BE21-150

**ADDENDUM NO.:** ONE

**CURRENT DEADLINE FOR BIDS:**

May 11, 2021

**PREVIOUS ADDENDA:** NONE

**ISSUED BY:**

City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED:**

**April 29, 2021**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

**PROJECT MANUAL:**

Item No. 1 SECTION 00310 – BID SCHEDULE **delete** in its entirety and **replace** with the attached Bid Schedule labeled Addendum 1.

By: \_\_\_\_\_

*Greg Smith*

Greg Smith  
Contract Administrator

Total number of pages contained within this Addendum: 3

## SECTION 00310 - BID SCHEDULE

ADDENDUM 1

PAY ITEM NO.	PAY ITEM DESCRIPTION	PAY UNIT	APPROX. QUANTITY	UNIT PRICE		AMOUNT	
				DOLLARS	CENTS	DOLLARS	CENTS
1505.1	Mobilization	Lump Sum	All Req'd	LUMP	SUM		
1570.1	Erosion and Sediment Control	Lump Sum	All Req'd	LUMP	SUM		
2201.1	Clearing and Grubbing	Lump Sum	All Req'd	LUMP	SUM		
2202.1	Excavation	CY	1,960				
2202.2	Sideslopes and Ditch Grading	Lump Sum	All Req'd	LUMP	SUM		
2202.3	Mining Area Restoration and Road Cleaning Guarantee	Contingent Sum	All Req'd	Contingent	Sum	\$ 5,000	00
2204.1	2-Inch Minus Shot Rock w/ Base Course	CY	1,470				
2204.2	Base Course, Grading D-1 for Driveways	Ton	20				
2401.1	Sanitary Sewer Pipe, 8-Inch PVC	LF	1,037				
2401.2	Sanitary Sewer Pipe, 12-Inch PVC	LF	41				
2401.3	Service Connections and Laterals	Each	7				
2401.4	Locate Sanitary Sewer Services	Lump Sum	All Req'd	LUMP	SUM		
2401.5	Connect to Existing Sanitary Sewer Pipe	Each	7				
2402.1	Sanitary Sewer Manhole, Type I With Fiberglass Base Liner	Each	6				
2501.1	4 & 6-Inch Pipe Culvert	LF	100				
2501.2	12-Inch Pipe Culvert	LF	287				
2501.3	18-Inch Pipe Culvert	LF	164				
2501.4	24-Inch Pipe Culvert	LF	972				
2501.5	6-Inch Underdrain	LF	244				
2501.6	CPP Saddle Tee	Each	2				
2502.1	Storm Drain Manhole, Type I	Each	8				
2502.2	Storm Drain Manhole, Type II	Each	1				
2502.3	Catch Basin, Type IV	Each	2				
2502.4	Catch Basin, Type III	Each	3				
2502.5	24-Inch CPP Inlet	Each	5				
2502.6	Connect to Dissimilar Storm Drain Pipe	Each	1				
2601.1	10-Inch HDPE Water Pipe	LF	219				
2601.2	24-Inch HDPE Water Pipe	LF	945				
2601.3	Connect to Existing Water Pipe	Each	7				
2601.4	Temporary Water System	Lump Sum	All Req'd	LUMP	SUM		
2601.5	Corrosion Protection	Each	11				
2602.1	10-Inch Gate Valve	Each	5				
2602.2	24-Inch Butterfly Valve	Each	4				
2603.1	Fire Hydrant Assembly with Access Pad	Each	3				
2604.1	Air Release Valve	Each	1				
2605.1	1-Inch Poly Water Services	Each	6				
2605.2	4-Inch HDPE Water Services	Each	1				
2605.3	Locate Water Services	Lump Sum	All Req'd	LUMP	SUM		
2607.1	Pipe Insulation	Board	120				
2702.1	Construction Surveying	Lump Sum	All Req'd	LUMP	SUM		
2707.1	Remove and Reset Chain Link Fence	LF	93				
2707.2	Remove and Reset Wood Fence	LF	90				
2709.1	Topsoil	CY	60				
2709.2	Topsoil Finish Grading	MH	30				
2710.1	Seeding, Hydraulic Method, Type III	SU	1				
2716.1	Remove and Dispose of Storm and Sanitary Sewer Pipe	Lump Sum	All Req'd	LUMP	SUM		
2716.2	Fill Water Pipe with Slurry	Lump Sum	All Req'd	LUMP	SUM		

**SECTION 00310 - BID SCHEDULE**

ADDENDUM 1

PAY ITEM NO.	PAY ITEM DESCRIPTION	PAY UNIT	APPROX. QUANTITY	UNIT PRICE		AMOUNT	
				DOLLARS	CENTS	DOLLARS	CENTS
2717.1	Remove and Dispose of Storm and Sanitary Sewer Structures	Lump Sum	All Req'd	LUMP	SUM		
2718.1	Sign Assembly	Each	12				
2719.1	Reconstruct Mailbox	Each	10				
2720.1	Painted Traffic Markings	Lump Sum	All Req'd	LUMP	SUM		
2722.1	Relocate Electrical Conductor	Each	18				
2723.1	Remove and Relocate Landscaping	Lump Sum	All Req'd	LUMP	SUM		
2801.1	A.C. Pavement, Type II-A, Class B	Ton	656				
2801.2	A.C. Pavement for Sidewalks, Driveways and Hydrant Pads	SY	1,122				
2806.1	Remove Existing Asphalt Surfacing	SY	4,700				
3302.1	Concrete Area Drains	Each	7				
3302.2	Concrete Headwall with Hinged Trash Rack	Each	2				
3303.1	Concrete Access Pad, 6-Inches Thick with Detectable Tiles	SY	110				
3303.2	Concrete Sidewalk, 6-Inches Thick	SY	112				
3303.3	Concrete Curb and Gutter, Type I	LF	1,835				
3304.1	Removal of Concrete Sidewalks	SY	128				
3304.2	Removal of Curb and Gutter	LF	1,554				
260000.1	Lighting	Lump Sum	All Req'd	LUMP	SUM		

**TOTAL BASE BID \$** \_\_\_\_\_

**COMPANY NAME:** \_\_\_\_\_