



ADDENDUM TO THE CONTRACT

for the

**DOUGLAS 4TH STREET UTILITIES AND DRAINAGE
Contract No. BE21-215**

ADDENDUM NO.: TWO

CURRENT DEADLINE FOR BIDS:

April 13, 2021

PREVIOUS ADDENDA: ONE

ISSUED BY:

City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward St
Juneau, Alaska 99801

DATE ADDENDUM ISSUED:

April 5, 2021

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering-public-works>

CLARIFICATIONS:

PROJECT MANUAL:

Item No. 1 **Delete** SECTION 00310- BID SCHEDULE in its entirety and **replace** with the attached Bid Scheduled labeled Addendum 2

By: 

Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 3

SECTION 00310 - BID SCHEDULE

PAY ITEM NO.	PAY ITEM DESCRIPTION	PAY UNIT	APPROX. QUANTITY	UNIT PRICE		AMOUNT	
				DOLLARS	CENTS	DOLLARS	CENTS
1505.1	Mobilization	Lump Sum	All Req'd	LUMP	SUM		
1550.1	Traffic Maintenance	Lump Sum	All Req'd	LUMP	SUM		
1570.1	Erosion and Sediment Control	Lump Sum	All Req'd	LUMP	SUM		
2202.1	Excavation	CY	2,277				
2202.2	Mining Area Restoration & Road Cleaning Guarantee	Contingent Sum	All Req'd	CONTINGENT	SUM	\$5,000	00
2205.1	Riprap, Class I & II	CY	233				
2206.1	Recycled Asphalt Pavement	CY	1,441				
2401.1	Sanitary Sewer Pipe, 8-Inch PVC	LF	1,614				
2401.2	6-Inch PVC Service Connections and Laterals	EA	23				
2401.3	Locate Sanitary Sewer Services	Lump Sum	All Req'd	LUMP	SUM		
2401.4	Connect to Existing Sanitary Sewer Pipe	EA	4				
2402.1	Sanitary Sewer Manhole, Type I	EA	7				
2402.2	Sanitary Sewer Manhole, Type I with Fiberglass Base Liner	EA	3				
2402.3	Connect to Existing Sanitary Sewer Manhole	EA	1				
2501.1	6-Inch PVC Pipe Culvert	LF	27				
2501.2	12-Inch CPP Pipe Culvert	LF	507				
2501.3	18-Inch CPP Pipe Culvert	LF	535				
2501.4	24-Inch CPP Pipe Culvert	LF	72				
2502.1	Storm Drain Manhole, Type I	EA	3				
2502.2	Storm Drain Manhole, Type II with Oil-Water Separator	EA	1				
2502.3	Catch Basin, Type III	EA	6				
2502.4	Catch Basin, Type IV	EA	5				
2503.1	84-Inch SRPE Culvert with Headwall	Lump Sum	All Req'd	LUMP	SUM		
2601.1	10-Inch HDPE Water Pipe	LF	2,472				
2601.2	14-Inch HDPE Water Pipe	LF	1,233				
2601.3	Connect to Existing Water Pipe	EA	6				
2601.4	Connect to Existing Water Pipe at PRV	EA	2				
2601.5	Temporary Water System	Lump Sum	All Req'd	LUMP	SUM		
2601.6	Corrosion Protection	EA	8				
2602.1	8-Inch Gate Valve	EA	2				
2602.2	10-Inch Gate Valve	EA	6				
2602.3	14-Inch Butterfly Valve	EA	2				
2603.1	Fire Hydrant Assembly With RAP Access Pad	EA	2				
2603.2	Connect to Existing Fire Hydrant	EA	1				
2605.1	1-Inch Poly Water Service	EA	24				
2605.2	2-Inch Poly Water Service	EA	2				
2605.3	8-Inch HDPE Water Service	EA	2				
2605.4	Locate Water Services	Lump Sum	All Req'd	LUMP	SUM		
2607.1	Pipe Insulation	Board	163				
2702.1	Construction Surveying	Lump Sum	All Req'd	LUMP	SUM		
2707.1	6-Foot Chain Link Fence with Slats	LF	148				
2710.1	Seeding, Hydraulic Method, Type III	SLURRY UNIT	3				
2716.1	Remove Existing Storm Drainage System	Lump Sum	All Req'd	LUMP	SUM		
2717.1	Remove and Abandon Existing Sanitary Sewer System	Lump Sum	All Req'd	LUMP	SUM		

SECTION 00310 - BID SCHEDULE

PAY ITEM NO.	PAY ITEM DESCRIPTION	PAY UNIT	APPROX. QUANTITY	UNIT PRICE		AMOUNT	
				DOLLARS	CENTS	DOLLARS	CENTS
2717.2	Remove and Abandon Existing Water System	Lump Sum	All Req'd	LUMP	SUM		
2719.1	Reconstruct Mailbox, Single	EA	2				
2719.2	Reconstruct Mailbox, Gang	EA	10				
2801.1	A.C. Pavement, Type II-A, Class B	SY	341				
2806.1	Remove Existing Asphalt Surfacing	SY	299				
3302.1	Concrete Area Drain	EA	17				
3302.2	Concrete Headwall Without Trash Rack	EA	3				
3303.1	Curb and Gutter, Type I	LF	42				
3304.1	Removal of Curb and Gutter	LF	42				

TOTAL BID: _____

COMPANY NAME: _____