



ADDENDUM TO THE CONTRACT

for the

BRH FUEL SYSTEM UPGRADES Contract No. BE22-233

ADDENDUM NO.: ONE

CURRENT DEADLINE FOR BIDS:

June 7, 2022

PREVIOUS ADDENDA: NONE

ISSUED BY:

City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED:

May 26, 2022

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Public Purchase webpage at: <https://www.publicpurchase.com/gems/juneau.ak/buyer/public/home>

PROJECT MANUAL:

Item No. 1 SECTION 00030 – NOTICE INVITING BIDS. COMPLETION OF WORK.

Replace the Completion of Work table **with** the following:

All WORK	December 15, 2022
----------	-------------------

Item No. 2 SECTION 00030 – NOTICE INVITING BIDS. DESCRIPTION OF WORK.

Add the following paragraphs to the end of the Description of Work:

“Final pavement patches shall be done with either asphalt or concrete patches. Asphalt pavement placement can occur provided it is completed prior to asphalt plant shutdown. Concrete patches shall be black concrete with Fiber mesh 300 or approved equal per CBJ Standard Specification 03303. Concrete patches shall have a minimum thickness of 5”.

The CONTRACTOR will be responsible for snow removal in and around the work zone until pavement patching is completed, including fully cured concrete if applicable, and ready for use.”

Item No. 3 SECTION 00500 – AGREEMENT, ARTICLE 2 – CONTRACT COMPLETION TIME.

Replace the completion of work table **with** the following:

All WORK	December 15, 2022
----------	-------------------

DRAWINGS:

Item No. 1 SHEET C7.03 – CIVIL DETAILS, DETAIL 4 – Fuel Oil Piping Trenching Detail.

Replace “New 4” asphalt patch paved in two lifts”
with “New 3” asphalt patch paved in one lift”

Item No. 2 SHEET C7.03 – CIVIL DETAILS, SHEET NOTES 7 through 11.

Replace notes 7-11 **with** the following:

- “7. Final pavement patches shall be done with either asphalt or concrete patches. Asphalt pavement placement can occur provided it is completed prior to asphalt plant shutdown.
8. Concrete patches shall be black concrete with Fiber mesh 300 or approved equal per CBJ Standard Specification 03303. Concrete patches shall have a minimum thickness of 5”.
9. The CONTRACTOR will be responsible for snow removal in and around the work zone until pavement patching is completed, including fully cured concrete if applicable, and ready for use.”

By: Caleb Comas
Caleb Comas,
Contract Administrator

Total number of pages contained within this Addendum: 2