



ADDENDUM TO THE CONTRACT

for the

JNU REHABILITATE ACCESS ROAD Contract No. BE22-127

ADDENDUM NO.: FOUR

CURRENT DEADLINE FOR BIDS:
August 17, 2022

PREVIOUS ADDENDA: THREE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: August 16, 2022

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Public Purchase webpage at: <https://www.publicpurchase.com/gems/juneau,ak/buyer/public/home>

CLARIFICATIONS:

Question: *"The documents pages 259 – 260 list spec section Item P-670 Hazardous Area Barriers and it refers us to section 01 5200 and per the plans. I don't find any shown on the plans or relative info in section 01 5200. Please let us know if this is needed."*

Response: Section P-670 advises that plastic barriers, with flasher unit and flag, are to be used as needed for safety purposes. Our intent was for the Contractor to use these barriers to identify the limits of construction – particularly at night. This would require the placement of barriers at each end of the construction limits (across the width of the access road) to warn of construction activity.

This section identifies that JNU has plastic barriers for use by the Contractor and that the Contractor shall provide the barrier lights, batteries as required for the barrier lights and flags. JNU does not anticipate a need for the use of a lot of these barricades.

PROJECT MANUAL:

Item No. 1. SECTION 004114 – BID SCHEDULE

Replace Section 004114 **with** the attached Section 004114, Labeled ADDENDUM 4. This adds Pay Item No. P-610c to Additive Alternate B.

By: 
Caleb Comas,
Contract Administrator

Total number of pages contained within this Addendum: 3

SECTION 004114 BID SCHEDULE

**JNU REHABILITATE ACCESS ROAD
BASE BID – RAP ROADWAY AND ARMOR SLOPES**

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
D-701a	Corrugated Plastic Pipe, 12-inch	LF	12			\$	
D-701b	Extend Corrugated Plastic Pipe through Armor Rock	EA	3			\$	
D-701c	Extend HDPE Pipe through Armor Rock	EA	3			\$	
D-751a	Storm Drain Catch Basin w/ Area Drain	EA	1			\$	
D-751b	Raise Existing Cover to Finish Grade	EA	2			\$	
G-105a	Mobilization and Demobilization	LS	All Req'd	LUMP	SUM	\$	
G-105b	Furnish and Install Water Level Board	LS	All Req'd	LUMP	SUM	\$	
G-135a	Construction Surveying by the Contractor	LS	All Req'd	LUMP	SUM	\$	
G-300a	CPM Scheduling	LS	All Req'd	LUMP	SUM	\$	
G-700a	Airport Flagger	CS	All Req'd	CONT	SUM	\$4000	00
G-700b	Temporary Traffic Control Signage	LS	All Req'd	LUMP	SUM	\$	
P-101a	Pavement Removal	SY	350			\$	
P-152a	Unclassified Excavation and Disposal	CY	3400			\$	
P-152b	Remove and Dispose Existing Concrete Gangway Abutment	EA	11			\$	
P-156a	Erosion, Sediment and Pollution Control Administration	LS	All Req'd	LUMP	SUM	\$	
P-156b	Temporary Erosion, Sediment and Pollution Control	LS	All Req'd	LUMP	SUM	\$	
P-180a	Armor Rock	CY	4000			\$	
P-180b	Rip Rap	CY	300			\$	
P-180c	Geotextile Fabric	SY	6000			\$	
P-207a	Recycled Asphalt Pavement	CY	5300			\$	
P-209a	Crushed Aggregate Base Course	CY	20			\$	
P-610a	Concrete Gangway Abutment	EA	12			\$	
P-610b	Concrete Cleanup Slab	LS	All Req'd	LUMP	SUM	\$	
T-901a	Seeding	LS	All Req'd	LUMP	SUM	\$	

TOTAL BASE BID AMOUNT IN FIGURES: \$ _____

BIDDER NAME: _____

SECTION 004114 BID SCHEDULE

JNU REHABILITATE ACCESS ROAD, ADDITIVE ALTERNATE A – PAVE ROADWAY

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
G-105a	Mobilization/Demobilization	LS	All Req'd	LUMP	SUM	\$	
G-135a	Construction Surveying by the Contractor	LS	All Req'd	LUMP	SUM	\$	
G-300a	CPM Scheduling	LS	All Req'd	LUMP	SUM	\$	
P-156a	Erosion, Sediment and Pollution Control Administration	LS	All Req'd	LUMP	SUM	\$	
P-156b	Temporary Erosion, Sediment and Pollution Control	LS	All Req'd	LUMP	SUM	\$	
P-207a	Recycled Asphalt Pavement	CY	1400			\$	
P-207b	Recycled Asphalt Pavement (deduct from base bid)	CY	-1300			\$	
P-209a	Crushed Aggregate Base Course	CY	750			\$	
P-403a	Hot Mix Asphalt, 4" Thick	SY	6200			\$	

TOTAL ADDITIVE ALTERNATE A AMOUNT IN FIGURES: \$ _____

JNU REHABILITATE ACCESS ROAD, ADDITIVE ALTERNATE B – WEST FINGER ROAD

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
G-105a	Mobilization/Demobilization	LS	All Req'd	LUMP	SUM	\$	
G-135a	Construction Surveying by the Contractor	LS	All Req'd	LUMP	SUM	\$	
G-300a	CPM Scheduling	LS	All Req'd	LUMP	SUM	\$	
P-101a	Pavement Removal	SY	15			\$	
P-152a	Unclassified Excavation and Disposal	CY	18			\$	
P-156a	Erosion, Sediment and Pollution Control Administration	LS	All Req'd	LUMP	SUM	\$	
P-156b	Temporary Erosion, Sediment and Pollution Control	LS	All Req'd	LUMP	SUM	\$	
P-180b	Rip Rap	CY	150			\$	
P-180c	Geotextile Fabric	SY	550			\$	
P-209a	Crushed Aggregate Base Course	CY	900			\$	
P-403a	Hot Mix Asphalt, 4" Thick	SY	5000			\$	
P-610c	Raise and Reset Existing Concrete Gangway Abutment	EA	7			\$	

TOTAL ADDITIVE ALTERNATE B AMOUNT IN FIGURES: \$ _____