

## ATTACHMENT #3

**Option A:** 18" cast aluminum letters mounted to steel tube at canopy edge.



### ATTACHMENT #3

**Option B.1:** 8" cast aluminum letters mounted to siding at building entry.

**Option B.2:** 8" hollow stainless letters mounted to siding at building entry, back lit.



### ATTACHMENT #3

**Option B.1:** Existing lighting at night, 8" cast aluminum letters mounted to siding at building entry.



View from curb



**ATTACHMENT #3**

**Option B.2**  
illuminated signage  
over entry door.



Individual 8" tall letters are back lit with LEDs; pegged mounted to siding.

### ATTACHMENT #3

<b>JNUTerminal Entry Sign</b>			
Preliminary Project Cost Estimate			
	OPTION A (canopy edge)	OPTION B.1 (thru siding)	OPTION B.2 (thru siding, backlit)
Component	Est. Cost	Est. Cost	Est. Cost
Lettering	\$ 5,000	\$ 1,500	\$ 3,500
Fabrication of lettering mounting system	\$ 8,500	\$ -	\$ -
Mount letters & support to canopy	\$ 6,000	\$ 8,500	\$ 10,000
<b>Subtotal Construction</b>	<b>\$ 19,500</b>	<b>\$ 10,000</b>	<b>\$ 13,500</b>
Engineering Design	\$ 3,000		\$ 2,000
Procurement, coordination	\$ 3,000	\$ 2,000	\$ 2,500
Construction administration / inspection	\$ 5,000	\$ 5,000	\$ 5,000
Project contingency	\$ 1,950	\$ 1,000	\$ 1,350
<b>Subtotal Indirect Costs</b>	<b>\$ 12,950</b>	<b>\$ 8,000</b>	<b>\$ 10,850</b>
<b>Total Project Cost</b>	<b>\$ 32,450</b>	<b>\$ 18,000</b>	<b>\$ 24,350</b>