



ADDENDUM TO THE CONTRACT

for the

Glacier Valley Elementary School Playground Upgrades

Contract No. E10-209

ADDENDUM NO.: ONE

BID OPENING DATE:

April 8, 2010

2:00 p.m. Local Time

PREVIOUS ADDENDA: NONE

ISSUED BY:

City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED:

April 1, 2010

The following items of the contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. If this fax is incomplete, please call (907) 586-0490, and we will re-send it. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at:

<http://www.juneau.org/engineering ftp/contracts/Contracts.php>

PROJECT MANUAL:

- Item No. 1 Section 00310 BID SCHEDULE – **Delete** in its entirety and **replace** with the attached Bid Schedule labeled Addendum No. 1
- Item No. 2 Section 00500 – AGREEMENT – Article 1. Work. **Add** the following:
- Additive Alternate No. 3 – Covered Play Area Fencing Enclosure. Furnish all labor, equipment and materials to furnish and install the covered play area fencing enclosure as shown on Sheet A03 of the construction drawings.
- Item No. 3 Section 01230 ALTERNATES, Part 3.2.A – **Add** the following:
- Additive Alternate No. 3 – Covered Play Area Fencing Enclosure. The intent of this Additive Alternate is to furnish and install the covered play area fencing enclosure as shown on Sheet A03 of the construction drawings.

DRAWINGS:

- Item No. 4 L01 – Layout Plan. **Add** the following sheet note:
- “Paint two (2) hopscotch courts and two (2) four-square courts atop existing asphalt surface beneath the existing steel structure. Paint four (4) four-square courts atop new asphalt at basketball court. Paint two (2) hopscotch courts atop new asphalt at

jump rope area. Four-square courts to be 16'x16'. Hopscotch courts to be comprised of nine (9) 18"x18" squares with an 18" radius semicircular "Home" square at top."

Item No. 5 L02 – Enlarged Tot Lot Plan. **Add** the following sheet note:

"Compact subgrade under Tot Lot Play Surface area prior to installation of filter cloth and fall protection material."

Item No. 6 L03 – Enlarged Main Play Area Plan. **Add** the following sheet note:

"Compact subgrade under Main Play Area Play Surface area prior to installation of filter cloth and fall protection material."

Item No. 7 A03 – Play Area Fencing Enclosure. **Delete** the following Drawing 1 note:

"Vinyl Mesh, Black"

And **Replace** with the following:

"9 gauge galvanized chain link fabric with knuckled ends all edges. Chain link fabric joints and seams shall be minimized and occur at support structure where required."

Item No. 8 A03 – Play Area Fencing Enclosure. **Add** the following to the end of Drawing 1 title:

"- Additive Alternate 3"

Item No. 9 E01 – Covered Play Areas Electrical. **Add** the following sheet note:

"6. Rewire to switch group h."

And **Add** sheet note 6 to the two (2) southwest corner floodlights.



By: _____
Jennifer Mannix,
Contract Administrator

Date: 4-1-10

Total number of pages contained within this Addendum: 3

SECTION 00310 - BID SCHEDULE

Bid Schedule for construction of **E10-209, named Glacier Valley Elementary School Playground Upgrades**, in accordance with the Contract Documents.

BASE BID - Furnish all labor, equipment and materials for replacing play structures and performing other site improvements including drainage, asphalt, site furnishing, painting and lighting replacement at covered play area and perform all WORK as described in these Contract Documents.

TOTAL BASE BID \$ _____
(Price in Figures)

ADDITIVE ALTERNATE NO. 1 - PICNIC TABLES, BENCHES & PLANTERS. Furnish all labor, equipment and materials and perform all WORK for installation of picnic tables and benches as shown on the construction drawings and the manufacturer's installation instructions. Picnic tables and benches will be furnished by the Juneau School District. This Additive Alternate also includes furnish and install of corrugated plastic pipe planters.

TOTAL ADDITIVE ALTERNATE NO. 1 \$ _____
(Price in Figures)

ADDITIVE ALTERNATE NO. 2 – BOLLARDS. Furnish all labor, equipment and materials and perform all WORK to furnish and install bollards at the main entry plaza as shown on the construction drawings.

TOTAL ADDITIVE ALTERNATE NO. 2 \$ _____
(Price in Figures)

ADDITIVE ALTERNATE NO. 3 - COVERED PLAY AREA FENCING ENCLOSURE. Furnish and install the covered play area fencing enclosure as shown on Sheet A03 of the construction drawings.

TOTAL ADDITIVE ALTERNATE NO. 3 \$ _____
(Price in Figures)

Date: _____ **Bidder:** _____
(Company Name)

END OF SECTION