



## ADDENDUM TO THE CONTRACT

for

### DIXON and MAIN STREETS RECONSTRUCTION Contract No. E11-146

**ADDENDUM NO.:** ONE

**CURRENT BID OPENING DATE:**

February 16, 2011  
2:00 p.m. Local Time

**PREVIOUS ADDENDA:** NONE

**ISSUED BY:**

City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED:**

**February 8, 2011**

The following items of the Contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. If this fax is incomplete, please call (907) 586-0490, and we will re-send it. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at:  
<http://www.juneau.org/engineering ftp/contracts/Contracts.php>

### **PROJECT MANUAL**

- Item No. 1      SECTION 00030 – NOTICE INVITING BIDS, Deadline for Bids. **Delete** the last sentence and **replace** with the following:
- “Bids will be opened immediately thereafter in the Engineering Third Floor Conference Room in the Marine View Center, 230 So. Franklin Street, unless otherwise specified.”
- Item No. 2      SECTION 01025 – MEASUREMENT AND PAYMENT, Article 2.23, 1-INCH WATER SERVICE, **add the following paragraph:**
- F.      WORK under this item includes the 2-inch water services located at Station “D” 14+83, and at Station “M” 12+40.
- Item No. 3      SECTION 02716 – WATER, STORM AND SANITARY PIPE REMOVAL, PART 1 – GENERAL, Article 1.1, DESCRIPTION, **add the following:**
- The WORK under this Section also includes the filling of the pipes, 6-inches and larger, that are shown on the Drawings to be taken out of service, with a flowable backfill as an alternative to removal and disposal.
- Item No. 4      SECTION 02716 – WATER, STORM AND SANITARY PIPE REMOVAL, PART 2 – PRODUCTS, **delete** (Not Used) and **add the following paragraph:**
- A.      Flowable backfill is a mixture of Portland cement, fly ash, fine aggregate, water, and may contain other cementations materials or concrete admixtures to improve flowability or other performance characteristics. The flowable backfill shall contain not less than 141 pounds of cement per cubic yard, and shall contain only enough water that will result in a flowable self-leveling product at the time of

placement. The mixture shall have sufficient cement and sand content to set up into a solid mass within 24 hours of placement.

- Item No. 5 SECTION 02716 – WATER, STORM AND SANITARY PIPE REMOVAL, PART 3 – EXECUTION, **add the following to paragraph A:**

The CONTRACTOR may fill any of the pipes, 6-inches and larger, that are shown on the Drawings to be taken out of service, with a flowable backfill as an alternative to removal and disposal of the pipe. All segments of these pipes remaining buried within the street or sidewalk embankment shall be completely filled with the flowable backfill mixture. The CONTRACTOR shall conduct these operations in a manner that the ENGINEER can verify that the pipe segments have been completely filled with the flowable mixture.

- Item No. 6 SECTION 02724 – WOOD FENCE, PART 2 – PRODUCTS, Article 2.1, MATERIALS, paragraph A, **replace sentence No. 1 with the following:**

1. The wood pickets shall be cedar, 38 inches to 42 inches in length, with the standard width and thickness available without special milling. The paint shall be exterior grade white.

- Item No. 7 SECTION 02724 – WOOD FENCE, PART 3 – EXECUTION, Article 3.1, CONSTRUCTION, **add the following paragraph:**

- D. Spacing between pickets shall not exceed the width of the picket. The bottom of the pickets shall be set approximately one-inch above the concrete sidewalk level.

## **DRAWINGS**

- Item No. 8 SHEET NO. 12, titled "PLAN – DIXON STREET CALHOUN AVENUE TO STA "D" 13+10." **Replace Note 6 with the following:**

6. REMOVE/REPLACE WALL END SECTION. SEE DETAILS ON SHEET 6.

- Item No. 9 SHEET NO. 18, titled "WOOD HANDRAIL DETAILS" **Replace the note in the handrail detail that reads "2 X 6" W/ROUTED HANDRAIL (SUNWOOD OR EQUAL)" with the following:**

"2 X 6 W/ROUTED CEDAR HANDRAIL."

- Item No. 10 SHEET NO. 21, titled "PLAN – MAIN STREET WEST FIFTH STREET TO STA "M" 12+65." **Add the following note to the survey monument located at Sta "M" 10+10.2, 17.2 LT, and the survey monument located at Sta "M" 12+19.1, 14.5 LT: "REMOVE/RESET SURVEY MONUMENT."**



By: \_\_\_\_\_  
Jennifer Mannix, CBJ Contract Administrator

Total number of pages contained within this Addendum: 2.