# HAMAS CAPITA OFF

# ADDENDUM TO THE CONTRACT

for

# CONSOLIDATED PUBLIC WORKS FACILITY PHASE III

### Contract No. E12-011

ADDENDUM NO.: ONE

**CURRENT BID OPENING DATE:** 

July 22, 2011

2:00 p.m. Local Time

PREVIOUS ADDENDA: NONE

ISSUED BY:

City and Borough of Juneau ENGINEERING DEPARTMENT

155 South Seward Street Juneau, Alaska 99801

## DATE ADDENDUM ISSUED:

July 18, 2011

The following items of the Contract are modified as herein indicated. All other items remain the same.

# PROJECT MANUAL

Item No. 1 SECTION 01025 – MEASUREMENT AND PAYMENT, Article 2.6 – MODIFIED C-1 BASE COURSE (Pay Item No. 2202.5) PRICE BASED ON QUANTITY, CUBIC YARD, Replace paragraph D with the following:

D. Payment for Modified C-1 Base Course, will be made at the Unit Price named in the Bid Schedule under Pay Item No. 2202.5, which payment will constitute full compensation for all WORK described in Section 02202 – Excavation and Embankment, Section 02204 – Base Course, as shown on the Drawings and as directed by the ENGINEER.

### DRAWINGS

- Item No. 2 SHEET NO. 8, titled "SITE PLAN." Replace PROTECT MONUMENT with PROTECT MONUMENT N:10659.30 E:10469.27 as labeled on the plan.
- Item No. 3 SHEET NO. 8, titled "SITE PLAN." **Add** the following note on monument in slope near pipe S-5:

REMOVE AND RESET MONUMENT. DEFLECT S-5 TO AVOID CONFLICT WITH MONUMENT. N:10659.59 E:10304.13

Item No. 4 SHEET NO. 8, titled "SITE PLAN." Replace STA "P" 17+06.4, 91.0 RT, DITCH INV EL=60.50 with STA "P" 17+06.4, 91.0 RT, DITCH INV EL=60.85 as labeled on the plan.

Item No. 5 SHEET NO. 8, titled "SITE PLAN." Add the following note:

ALL TREES WITHIN THE CLEARING LIMITS SHALL BE FELLED PRIOR TO OCTOBER 15, 2011. THE PATHWAY SHALL BE KEPT CLEAR OF FALLEN TREES AT ALL TIMES. ALL TREES FALLEN AS PART OF THIS PROJECT SHALL BE REMOVED FROM THIS SITE, INCLUDING THOSE THAT HAVE FALLEN BEYOND THE CLEARING LIMITS.

Item No. 6 SHEET NO. 9, titled "TEMPORARY DRIVEWAY RAMP PLAN & PROFILE VIEW AND USEABLE EXCAVATION FILL LIMITS." Replace INSTALL 4"X4"X8' PRESSURE TREATED POST (3' BURRIED) ON PROPERTY LINE with INSTALL 4"X4"X8' PRESSURE TREATED POST (3' BURIED) ON PROPERTY LINE N:10195.86 E:10469.18 as labeled on the plan.

Total number of pages contained within this Addendum: 2