



Permit Number: Per 11-118

Receipt Number: N/A

Check Number: N/A

Permit Fee: \$ N/A Account Number: 110-00-3-00-00-204
Inspection Amount: \$ 1 Account Number: 110-00-3-00-00-204
Inspection Deposit Amount: \$ 1 Account Number:
Bond Amount: \$ Account Number: 110-00-1-33-00-000

CIP PROJECT
RFA E12-072

Applicant Name: Paul Beck, CBJ Mailing Address: 155 S. Seward St. City: Juneau, AK Zip: 99801 Phone: 586 0882

Location of Project: 5400 Glacier Highway US 668 fr.

* Two sets of plans must be submitted showing the proposed project or parking reservation area, drawn to scale as noted on the plans, and include:

- All property lines (if applicable)
- Location of all structures, existing or proposed
- Existing and proposed utilities
- North arrow
- Any proposed grading changes
- All other relevant measurements

I. STREET AND SIDEWALK USE PERMIT (Ord. 62.10)

1. STREET CLOSED: ☐ Yes ☒ No SIDEWALK BLOCKED: ☐ Yes ☒ No
(* If either is "Yes" attach a detour diagram and plot plan)
2. PARKING LANE CLOSED: ☐ Yes ☒ No If "Yes", number of spaces eliminated:
3. TYPES OF VEHICLES/EQUIPMENT PARKING:
4. DATES NEEDED: From To TIMES OF DAY: From To
5. ON-SITE REPRESENTATIVE: PHONE:
6. SPECIAL CONDITIONS OF APPROVAL:
7. CONDITIONS/REVERSE SIDE: 1 2 3 4 5 6 7 8 9 10 11 : APPROVED DATE:

II. PUBLIC FACILITY TRANSMISSION & EXCAVATION PERMIT (Ord. 62.05 and 62.40)

1. ESTIMATED COST OF WORK IN THE PUBLIC RIGHT-OF-WAY: \$ N/A X %
2. TYPE OF STREET SURFACE TO BE CUT: ☐ Asphalt ☐ Concrete ☐ Gravel ☐ Dirt
3. SCOPE OF WORK: ☐ Sanitary Sewer (Spec. #40) ☐ Water Line (Spec. #60) ☐ Grading (Spec. #20) ☐ Asphalt Roads (Spec. #80)
☐ Storm Drain (Spec. #50) ☒ Other (Spec. # New fire hydrant)
4. PROJECT TIME FRAME: From 7/13/11 To 9/1/11
5. ON-SITE REPRESENTATIVE: Paul Beck CBJ PHONE: 586 0882
6. SPECIAL CONDITIONS OF APPROVAL:
7. CONDITIONS/REVERSE SIDE: 1 2 3 4 5 6 7 8 9 10 11 : APPROVED DATE: 7/25/11

III. DRIVEWAY CONSTRUCTION PERMIT (Ord. 62.36)

1. WORK: ☐ New Driveway ☐ Driveway Repair MATERIAL: ☐ Asphalt ☐ Concrete
2. DIMENSIONS: Width Culvert Size (Invert elevation)
3. SPECIAL CONDITIONS OF APPROVAL:
4. CONDITIONS/REVERSE SIDE: 1 2 3 4 5 6 7 8 9 10 11 : APPROVED DATE:

The undersigned owner/applicant hereby agrees to hold and save harmless the City and Borough of Juneau from any and all claims for damages, costs, expense or causes of action that may arise because of installation and maintenance of the improvement other right-of-way use hereto applied for and further agree to remove same upon notice from the City and to replace public property damage thereby. All construction shall be in accordance with City and Borough of Juneau Construction Standards and Specifications. The applicant/permittee is responsible to call 586-1333 for underground utility location prior to excavation.

This permit may be cancelled by the City upon any stoppage of work on this project over a seven (7) day duration.

Applicant Signature:

Date: 7/13/11

OFFICE INFORMATION: Permit Expires On: Final Inspection:

Bond/Deposit Returned On: To: By:

Received By: Date: Issued by: Date:

CONDITIONS OF APPROVAL


1. **INSPECTIONS:** Inspections can be requested by calling 586-1703, indicating the location of the project, permit number, type of inspection, and your name. Inspection requests must be received 24 hours prior to the time you need the inspection. An inspection is required prior to backfill over any and all utility lines and road surfaces. Construction reports must be filed with the Department of Engineering or the Deposit/Bond will be retained by the City for one year.
2. **SPECIAL INSEPTION:** Television and Air Test inspections of all sewer main line installations must be performed and approved by the City.
3. **ROADWAY SURFACES:** When excavating within public streets, all paved surfaces must be "saw cut" per Standard Detail No. 1010 and returned to the original condition within 24 hours of the conclusion of construction activity as determined by inspection.
4. **BACKFILL:** When backfilling utility lines fill material must be compacted in a maximum of 12 inch layers and consist of nonfrost susceptible granular material. "Muck", frozen or organic materials is not allowed. In lieu on compaction tests the City and Borough can be directed by the permittee to hold the bond for a period of one year after the project has received final inspection approval.
5. **AS-BUILT PLANS:** Permit holders for all projects involving the installation of underground utilities must submit as-built plans to the CBJ Department of Engineering per City specifications. Projects involving public utilities, i.e. Sewer and Water mains and effected laterals, streets, and storm drains, must submit as-built plans on 22 inch by 34 inch (22" X34") mylar sheets and be stamped by a State of Alaska licensed Professional Civil Engineer. Deposits/Bonds will not be released prior to the submission and approval of as-built plans.
6. **OTHER APPROVALS:** Permit applications for projects involving sewer and water line development, and sometimes other types of projects, must first obtain and submit to CBJ Department of Engineering evidence of project approval often involving but not limited to the State of Alaska Department of Environmental Conservation, Department of Transportation, Department of Fish and Game, and U.S. Corp of Engineers, etc.
7. **BLOCKING LANE(S) OF TRAFFIC:** Orange traffic cones must be placed in such a manner to shift oncoming traffic from closed lanes to open lanes. Cones must be set a minimum of 50 feet from the point where traffic is closed spaced no more than 15 feet apart. Signs with yellow flashing warning lights must be placed behind the cone barricade and indicate "Lane Closed". If lane closure occurs on a two-way street a flagman directing traffic must be present during peak travel hours of 7:30 a.m. to 9:00 a.m. and 4:00 p.m. to 5:00 p.m.
8. **SIDEWALK BARRICADING:** When protects involve the use of equipment or work over a sidewalk, a six foot high fence of "Hurricane" type or other approved fencing method must be installed in such a manner so as to restrict pedestrian traffic from the work area.
9. **POSTING OF PARKING PERMITS:** Parking permits must be prominently displayed on the dashboard of each authorized vehicle located in the restricted parking zone. If the parking authorization involves a construction project, then each individual vehicle displaying a parking permit must also have the company name or symbol on the side of the vehicle.
10. **SECURING PARKING PLACES:** It is the responsibility of the parking permit holder to properly block or barricade authorized parking spaces. If a problem should arise after an area has been properly posted, the CBJ Police Department should be notified at 586-5210.

11. **OTHER SPECIAL CONDITIONS:**

LANE SHIFT, TRAFFIC CONTROL PLAN TO BE
SUBMITTED TO ADOT FOR APPROVAL. COPY OF
APPROVED TCP TO BE SUB ATTACHE TO THIS
PERMIT

Permit Center
230 S. Franklin, 4th Floor
Marine View Center
PHONE 586-0770

INSPECTIONS
586-1703



POSTING NOTICE OF BUILDING PERMIT

ROW20110118

Permit No.

New fire hydrant CIP - RFQ E12-072

For

5370 GLACIER HWY

Address

7/25/2011

MUST BE POSTED IN A CONSPICUOUS PLACE THROUGHOUT CONSTRUCTION