



**ADDENDUM TO THE CONTRACT  
for the  
Auke Bay Elementary  
School Renovation Re-Bid  
Contract No. E12-216**

**ADDENDUM NO.: FOUR**

**CURRENT DEADLINE FOR BIDS:  
March 8, 2012**

**PREVIOUS ADDENDA: THREE**

**ISSUED BY:** City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED: March 5, 2012**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

**INFORMATION ITEM:** All addenda previously issued with cancelled bid E12-042 are incorporated by reference and should *not* be acknowledged with the re-bidding of this project. Please only acknowledge addenda issued under Re-Bid No. E12-216 on the Bid form, Section 00300.

**PROJECT MANUAL RE-BID PACKET:**

Item No. 1: SECTION 097200 - WALL COVERINGS: **Add** Section 2.3 as follows:

- "A. At contractors options in lieu of field installed fabric wall covering over cork, provide:  
Factory Fabricated Tackable Textile Wall Covering.
1. Basis of Design: Provide Claridge edge wrapped tack wall panels with designer fabric as selected by Architect from full range of colors. Provide wrapped edge butt joints to align with plastic laminate panel joints – typical. 100% polyester fabric with Class A rating. Soil and stain resistant.
  2. Substitutions: Or approved equal."

**DRAWINGS:**

Item No. 2: Sheet A004 - Partition Type M: **Add** the following note:

- "8. At gym 106 provide sound isolation system (Not 6) to face of wall opposite gymnasium."

Item No. 3: Sheet A015 – Finish Schedule, Abbreviations PLAM/TACK: **Add** "See Detail 2/A906.

Item No. 4: Sheets A403 and A411: **Provide** Type M walls on all walls of Gymnasium 106.

Item No. 5: Sheet A500 – Keynotes, Note 539: **Add** "See Detail 2/A906".

Item No. 6: Sheet A500 – Keynotes, Note 540: **Add** "See Detail 1 & 2/A906".

**DRAWINGS, Cont'd.**

- Item No. 7. Sheets A501-A523 – TYPICAL INTERIOR DETAILS – INTERIOR ELEVATIONS: **Add** general note: "All counters with sinks, are solid surface, note 503 unless otherwise noted."
- Item No. 8. Sheet A520 – INTERIOR ELEVATIONS, Details 6-9: **Change** Note "502" to read "503".
- Item No. 9. Sheet A803 – EXTERIOR DETAILS, Detail 6: **Change** Note "8148" to read "8156".
- Item No. 10. Sheet A906 – INTERIOR ELEVATIONS, Detail 2: **Change** 2'-6" to read 3'-2 ½". The change is intended to accommodate a 4' width of tack surface vertically between the 2x2 trim.
- Item No. 11. Sheet A906 – INTERIOR ELEVATIONS, Detail 3: **Add** the following note: "Where prefabricated fabric wrapped cork panels are used, delete aluminum trim and provide fabric wrapped butt joints to align with joints of plam wall panel as indicated."
- Item No. 12. Sheet A906 – INTERIOR ELEVATIONS: **Add** Detail Number "3" to top right detail and **add** Detail Number 6 and "plam wall panel typical joint" to bottom right detail.
- Item No. 13. Sheet A909 – INTERIOR DETAILS: **Add** general note to Details 1, 2, 3,m 4, and 5:  
"Apply to all second floor construction where occupied space occurs below." **Add** general note to Detail 6: "Occurs at both mechanical penthouses."

By: \_\_\_\_\_

Jennifer Mannix,  
Contract Administrator

Date: March 5, 2012

Total number of pages contained within this Addendum: 2