



## ADDENDUM TO THE CONTRACT

for the

### AUKE BAY ELEMENTARY SCHOOL RENOVATION RE-BID

Contract No. E12-216

**ADDENDUM NO.:** FIVE

**CURRENT DEADLINE FOR BIDS:**  
March 8, 2012

**PREVIOUS ADDENDA:** FOUR

**ISSUED BY:** City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED:** March 6, 2012

The following items of the contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: [http://www.juneau.org/engineering\\_ftp/contracts/Contracts.php](http://www.juneau.org/engineering_ftp/contracts/Contracts.php)

#### **CORRECTION:**

Addendum No. 4, Item No. 2 – In parentheses, it should read “Note 6”.

Addendum No. 4, Item No. 13 – delete the “m” within the Details listed (1, 2, 3, 4 and 5).

#### **PROJECT MANUAL:**

Item No. 1 Section 123661 Simulated Stone Countertops: **Change** Sub Section 2.2.C.2. to “Type: Provide Standard Type of middle-grade, unless Special Purpose Type is indicated.”

#### **DRAWINGS:**

- Item No. 1 Addendum #4, Item #4, Sheet A403 and A411: **Provide** type M walls at all North, East and South walls of Gymnasium 106. **Provide** walls similar to type B6 at all West walls of Gymnasium 106 – Gymnasium side of walls to be ½” pwd paneling, opposite side of walls to be sound isolation system.
- Item No. 2 Sheet A400 Note 446: **Change** note to “Mfr’d wood veneer casework, provide power and data from book display wall.”

Item No. 3 Add the following notes to sheets C400 and C401

- The 36" deep section of '12"-minus shot rock borrow' (sheets C400,C401) under the asphalt pavement(as identified on sheets C200 – C205) may be reduced to an 18" minimum\* in areas of existing pavement(identified on C100,C101), and
- The 36" deep section of '12"-minus shot rock borrow' (sheets C400,C401) under exterior concrete paving / flatwork may be reduced to a 12" minimum\* in areas of existing development.

\*depth may be greater in fill areas, and useable excavation meeting requirements of borrow, compacted to minimum of 95% modified proctor maximum density, may be used to fill to the shot rock borrow limits.

- Geotextile separation fabric, Type - C shall only be required under development areas that are currently not developed and covered with asphalt pavement or concrete (as identified on C100, C101).

Add the following note to Sheets C200:

- Utility piping (sheets C200 – C205) elevations may be raised to the following minimum cover requirements. Contractor shall be responsible for avoiding all conflicts:
  - Storm Drain Piping: 2' minimum from top of pipe to finish grade
  - Water and Sewer Piping: 5' minimum from top of pipe to finish grade

By: \_\_\_\_\_

Jennifer Mannix,  
Contract Administrator

Date: 3/6/12

Total number of pages contained within this Addendum: 2