



## ADDENDUM TO THE CONTRACT

for the

### ADAIR-KENNEDY FOOTBALL/SOCCER FIELD SYNTHETIC TURF REPLACEMENT

Contract No. E12-189

**ADDENDUM NO.:** ONE

**CURRENT DEADLINE FOR BIDS:**  
March 16, 2012

**PREVIOUS ADDENDA:** NONE

**ISSUED BY:** City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED:** March 7, 2012

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at:  
<http://www.juneau.org/engineering ftp/contracts/Contracts.php>

#### **INFORMATIONAL ITEMS:**

- Turf manufacturers may submit product specifications in advance of the Deadline for Bids to obtain pre-approval. Email information to [jennifer\\_mannix@ci.juneau.ak.us](mailto:jennifer_mannix@ci.juneau.ak.us). A list of pre-approved manufacturers/products will be posted on the website listed above and will be updated as approvals occur.
- Photos of the existing field and recent repairs that have been made are posted at the website listed above.
- The advertised construction estimate did not include the Additive Alternate work. The estimate for the Additive Alternate is \$80,000.

#### **SPECIAL PROVISIONS:**

Item No. 1: Section 00800 – Supplementary General Conditions

- Article 13.6, One Year Correction Period, Paragraph E, Definitions, Number 3. **Delete** the following sentence:

"The term "Serviceable" in the context of this warranty, shall mean that the synthetic turf system shall have an average dynamic cushioning G value according to ASTM F355A no greater than 125 G's."

And **replace** with the following sentence:

"The term "Serviceable" in the context of this warranty, shall mean that the synthetic turf system shall have an average dynamic cushioning G value according to ASTM F355A no greater than 125 G's upon installation and shall not exceed 175 G's maximum during the warranty of the product."

Item No. 2: Section 01025 - Measurement and Payment, Article 2.3, Remove and Dispose of Existing Turf System, Paragraph B. **Add** the following:

"The WORK will also include removal and disposal of the existing geotextile fabric under-pad that is located on the bottom of the existing turf surfacing material".

Item No. 3: Section 02240 – Synthetic Turf Surfacing

➤ Article 1.2, Minimum Synthetic Turf Contractor's Qualifications. **Delete** subparagraph 1 and **replace** with the following:

"1. Have installed a minimum of six (6) successful full-size outdoor football or soccer synthetic turf fields (minimum 70,000 sq. ft.) in the United States within the past three (3) years of tufted polyethylene grass-like fabrics that are filled with either all rubber or a mixture of SBR rubber and sand. "

➤ Article 2.3, Requirements of Turf Surfacing System, Paragraph F. **Delete** paragraph and **replace** with the following:

"Fiber Type and Density: The turf surface shall use slit film polyethylene low-friction fibers with a minimum fiber density of 40 ounces per square yard."

➤ Article 3.2, Removal of Existing Turf System, Paragraph A, **delete** the first sentence and **replace** with the following:

"The existing turf surfacing material, rubber infill, and geotextile fabric under-pad that is located on the bottom of the existing turf surfacing material shall be removed in an orderly manner to avoid excessive disturbance to the underlying turf base material."

By: 

Jennifer Mannix,  
Contract Administrator

Date: 3/8/12

Total number of pages contained within this Addendum: 2