



ENGINEERING DEPARTMENT

ADDENDUM TO THE CONTRACT

for the

MAIN STREET, SECOND TO FIFTH STREET IMPROVEMENTS

Contract No. E12-167

ADDENDUM NO.: THREE

CURRENT DEADLINE FOR BIDS:
May 30, 2012

PREVIOUS ADDENDA: TWO

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: May 25, 2012

The following items of the Contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. If this fax is incomplete, please call (907) 586-0490, and we will re-send it. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

PROJECT MANUAL

Item No. 1: SECTION 01025 – MEASUREMENT AND PAYMENT, PART 1 – GENERAL, ARTICLE 5.2A - ALASKA OFFICE BUILDING ENTRANCE CANOPY. *Delete* paragraph B in its entirety and replace with the following paragraph. *The only change is the addition of canopy circuits and lighting.*

“B. The WORK under this Item includes the construction of a new canopy at the entrance to the Alaska Office Building at approximate Station “M” 13+50 LT, all inclusive of concrete footings and base plates for columns, steel posts and structure, glazing system, gutters, downspouts, and underground storm conduit to a point of connection to the storm sewer line at approximate Station 13+42, 34.0 LT. The WORK also includes the underground circuits from the handhole at STA “M” 12+72, 30’LT and the extension of conduits and circuits into the canopy structure and the installation of lighting as shown on the Drawings.”

Item No. 2: SECTION 01025 – MEASUREMENT AND PAYMENT, PART 1 – GENERAL, ARTICLE 16.2 LIGHTING. *Delete* paragraphs B and C in their entirety and *replace* with the following:

“B. This WORK includes the provision of all of the underground circuits; ductwork and handholes; junction boxes; luminaires, poles, and foundations; and controls with the following exception:

1. The underground conductors and cables supplying power to the Alaska Office Building Canopies from the handhole at STA "M" 12+72, 30'LT, and all other above grade WORK required for the Alaska Office Building Canopy lighting and the Alaska Office Building Entrance Canopy. This WORK will be measured for payment under Pay Item 16000.3A Alaska Office Building Canopy Lighting, and Pay Item No. 5120.2A Alaska Office Building Entrance Canopy.
- C. The underground conduit from the handhole at STA "M" 12+72, 30'LT, through the footings for both the Alaska Office Building Canopy and the Alaska Office Building Entrance Canopy, to a termination point at the top of the footings as shown on the Drawings, shall be measured for payment under this Pay Item."

DRAWINGS

Item No. 3: SHEET 12 of 44, C.109 – PROJECT PHASING AND TRAFFIC CONTROL PLAN, NOTES. *Add* the following NOTE 9.

"9. THE EXISTING MAIN STREET SIDEWALK, PROJECT RIGHT, BETWEEN SECOND STREET AND FOURTH STREET SHALL REMAIN IN PLACE, UNDISTURBED AND UNOBSTRUCTED TO PEDESTRIAN ACCESS UNTIL MAY 1, 2013."

Item No. 4: SHEET 34 of 44, E.302 - LIGHTING PLAN – MAINT STREET STA "M" 12+75 TO STA "M" 15+26." *Delete* the drawing in its entirety and *replace* with the attached.

By: _____

Jennifer Mannix, CBJ Contract Administrator

Total number of pages contained within this Addendum: 3