



**PLAN
NEW ROOF**

New Work Notes:

1. Install new roofing assembly on existing wood deck.
2. Modify approximately 284 LF of parapet. For bidding purposes, assume 71 LF of parapet to be modified per detail B/G. Assume remaining 211 LF of parapet to be modified per detail A/G.
3. Install new prefinished metal coping at modified parapet.
4. Modify existing roof framing and ceiling framing for new roof hatch and access panel. Install new roof hatch and access panel. Coordinate w/ existing framing, mechanical, and electrical systems.
5. Install new retrofit roof drain, overflow drain & new covers.
6. Install new plumbing vent covers.
7. Modify metal boiler flue bracing as required and resattach to roof parapet.
8. Tapered expanded polystyrene insulation.
9. Reroute EMS wiring through attic & connect w/ existing wiring @ building interior. Patch existing thru-wall penetration.
10. Extend parapet @ returns as required to maintain 3 1/4" gap between existing E.I.F.S. an inside face of new treated 2x12 fascia
11. Infill roof framing & sheathing @ old roof hatch opening.



Do not scale from this drawing, use dimensions

Yaakoosge' Daakahidi Alternative High School Roofing Replacement
 Contract No. E06-138
New Roof Plan
 Architecture Division
 CITY/BOROUGH OF JUNEAU
 Alaska's Capital City



Yaakoosge' Daakahidi Alternative High School Roofing Replacement
 Contract No. E06-138

New Roof Plan



March 8, 2006

Project Manager: N. Coffey
 Designed By: R. Ritter, N. Coffey
 Drafted By: T. Mores

Sheet number:
4 of 6