ENGINEERING DEPARTMENT

ADDENDUM TO THE CONTRACT

for the

PIONEER AVENUE RECONSTRUCTION, PHASE III

Contract No. E14-022

ADDENDUM NO.: **ONE**

CURRENT BID OPENING DATE:
November 7, 2013
2:00 p.m. Local Time

PREVIOUS ADDENDA: **NONE**

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: **November 1, 2013**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php

SPECIAL PROVISIONS

Item No. 1 SECTION 02202 – EXCAVATION AND EMBANKMENT, PART 3 – EXECUTION, Article 3.1, EXCAVATION. ***Add*** *the following paragraph:*

"P. Observations from the original construction of Pioneer Avenue reveal that stumps, logs, overburden, brush and other debris were placed into the deep fill areas along the left side of the roadway. The CONTRACTOR is advised that most of the excavated materials to be measured for payment under Pay Item 2202.2, Additional Excavation, are likely to not meet the requirements of useable material from excavation for use in the deep fill areas. All unsuitable materials shall be disposed of as described in these specifications.

1. Backfill for the areas of additional excavation which are below a plane 24" below finish roadway elevations shall be obtained only from usable excavation and no measurement for payment will be made for imported materials.
2. The CONTRACTOR shall conduct its' operations as required to maintain traffic as described in the Drawings under "NOTES FOR TRAFFIC CONTROL" and in the specifications, and to obtain all necessary usable material from excavation, including that available from the right side of the roadway, to backfill to the bottom of the shot rock borrow section."

DRAWINGS

Item No. 1 Sheet No. 4 of 18, titled "TYPICAL SECTIONS". ***Replace*** the reference to 12" MINUS SHOT ROCK BORROW" in SECTION A ***to read*** "USABLE MATERIAL FROM EXCAVATION". ***Replace*** the references to 8" MINUS SHOT ROCK BORROW in the TYPICAL SECTION and SECTION A ***to read*** "SHOT ROCK BORROW".

Item No. 2 Sheet No. 5 of 18, titled "TYPICAL SECTIONS". ***Replace*** the reference to "12" MINUS SHOT ROCK BORROW" in SECTION B ***to read*** "USABLE MATERIAL FROM EXCAVATION". ***Replace*** the reference to 8" MINUS SHOT ROCK BORROW in SECTION B ***to read*** "SHOT ROCK BORROW"

By:_____
Rich Ritter, AIA
Acting Contracts Officer

Total number of pages contained within this Addendum: 2