ENGINEERING DEPARTMENT

ADDENDUM TO THE CONTRACT

for the

Mendenhall Valley Public Library
Contract No. E14-051

ADDENDUM NO.: **NINE**

CURRENT DEADLINE FOR BIDS: **April 9, 2014**

PREVIOUS ADDENDA: **EIGHT**

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: **April 8, 2014**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php

PROJECT MANUAL:

Item No. 1 SECTION 095426 – LINEAR WOOD CEILINGS AND WALLS, PART 2 -- PRODUCTS, 2.1 LINEAR WOOD CEILING, B and C, 1.,e:

Delete: "Reference 092100 for support system components" and ***Replace*** with "Reference 092116 for support system components"

Item No. 2 SECTION 113100 – RESIDENTIAL APPLIANCES, PART 2 – PRODUCTS, 2.1.D:

Delete: "Coffee Machine: Countertop" and ***Replace*** with "Owner Furnished Contractor Installed Coffee Machine: Countertop"

Item No. 3 SECTION 124813 – ENTRANCE FLOOR MATS AND FRAMES:

Delete specification section in its entirety.

Item No. 4 SECTION 129300 – SITE FURNISHINGS, PART 2 - PRODUCTS, 2.6 BIKE RACKS:

Delete: Article A in its entirety and ***Replace*** with:

A. Bike Rack: Cora Expo 7510.

SPECIAL PROVISIONS:

No Changes

DRAWINGS:

Item No. 5 DRAWING SHEET A8.25 TYPICAL CEILING DETAILS

Delete detail "1B TYPICAL CEILING DETAIL" in its entirety.

Item No. 6 ADDENDUM NO. 7, DRAWING SHEET A6.7, INTERIOR ELEVATIONS CHILDREN 116 SOUTH:

Change note: "GBD W/ APPLIED WALL GRAPHIC" ***to read***, "GBD".

Item No. 7 DRAWING SHEETS A9.1 – A9.10, EXT. ROOF, SOFFIT AND WALL ASSEMBLIES (legend), SOFFIT ASSEMBLY 4S, 4Si:

Change "3/4" S.S. Z MTL 16" O.C." ***to read***: "3/4" Z, CHANNEL, 20 GAUGE, GALVANIZED WITH G60 COATING"

Item No. 8 DRAWING SHEET E4.6 DETAILS, Detail 1:

Delete the fiber patch panel.

Change the two unmarked 24-port switches ***to read*** "future, space only for 24-port switch"

By: _____
Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 2