



## ADDENDUM TO THE CONTRACT

for the

**Statter Harbor Improvements  
Contract No. DH14-014**

**ADDENDUM NO.: THREE**

**CURRENT DEADLINE FOR BIDS:  
October 8, 2014**

**PREVIOUS ADDENDA: TWO**

**ISSUED BY:** City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**DATE ADDENDUM ISSUED: October 3, 2014**

The following items of the contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

### **PROJECT MANUAL:**

- Item No. 1 SECTION 01025 – MEASUREMENT AND PAYMENT, PART 2 – PAY ITEMS, DIVISION 1 GENERAL REQUIREMENTS, Article 2.15, SURCHARGE PERIMETER ROCKS, **Replace** Paragraph C with the following:
- C. Boulders existing on site used as Surcharge Perimeter Rocks shall be included in measurements for payment for Surcharge Perimeter Rocks.
- Item No. 2 SECTION 02301 – WICK DRAINS, PART 3 – EXECUTION, Article 3.1 CONSTRUCTION, **Replace** Paragraph K with the following:
- K. The CONTRACTOR shall install the wick drains prior to the instrumentation devices. The CONTRACTOR shall take all necessary precautions to protect instrumentation and other surveying devices while conducting the WORK. The CONTRACTOR shall replace, at no cost to the OWNER, instrumentation that is damaged or becomes unreliable as a result of the CONTRACTOR's operations.
- Item No. 3 SECTION 02402 – SANITARY SEWER MANHOLES AND CLEANOUTS, PART 2 – PRODUCTS, Article 2.1 MANHOLES, **Delete** Paragraph B in its entirety.
- Item No. 4 SECTION 02502 - STORM SEWER MANHOLES, INLETS AND CATCH BASINS, Article 2.5 PRECAST CONCRETE UNITS, **Delete** Paragraph C in its entirety.
- Item No. 5 SECTION 02707 – FENCING, PART 2 – PRODUCTS, Article 2.2 TIMBER FENCE, Paragraph D, PRESERVATIVE TREATMENT, Item 1, **Add** the following sentence:
- All timber materials shall be pressure treated to the standards of AWP A U1, use Category UC4A.
- Item No. 6 SECTION 11100 – INSTRUMENTATION, **Add** the following Article to the end of PART 3 – EXECUTION:

### 3.5 PROTECTION AND MAINTENANCE OF INSTRUMENTATION

- A. In addition to other protection and maintenance requirements as specified herein, the CONTRACTOR shall take all necessary precautions to protect instrumentation and other surveying devices while conducting the WORK. The CONTRACTOR shall maintain, in serviceable condition, all instrumentation for the duration required to complete the WORK. The CONTRACTOR shall replace, at no cost to the OWNER, instrumentation that is damaged or becomes unreliable as a result of the CONTRACTOR's operations.

Item No. 7 SECTION 13121 – COVERED SHELTER, PART 2 – MATERIALS, Article 2.1 MATERIALS, **Add** the following sentence to the end of Paragraph A:

All sawn lumber shall be pressure treated per AWP A C2 for use Category UC3B per AWP A U1.

#### **PLANS:**

Item No. 8 DRAWING SHEET L3.01, PLANTING PLAN, Planting Legend, Deciduous Trees, **Replace** the entire table row referencing AA, Amelanchier arborea, with T-M Transplant Maple.

Item No. 9 DRAWING SHEET L3.02, PLANTING PLAN, **Delete** the entire table row referencing AA, Amelanchier arborea, from the Planting Legend, Deciduous Trees.

**Delete** the entire table row referencing GP, Geranium Patricia, from the Planting Legend, Perennials.

From the Planting Legend, Perennials **Replace** HM: Heuchera micrantha 'Palace Purple' with IS: Iris Setosa.

By:   
Greg Smith  
Contract Administrator

Total number of pages contained within this Addendum: 2