



ADDENDUM TO THE CONTRACT

for

DOWNTOWN SEAWALK – BRIDGE TO GOLD CREEK, PHASE III

Contract No. E16-128

ADDENDUM NO.: ONE

CURRENT BID OPENING DATE:
October 11, 2016
2:00 p.m. Local Time

PREVIOUS ADDENDA: NONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: **Sept 30, 2015**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

SPECIAL PROVISIONS:

Item No. 1: SECTION 01025 - MEASUREMENT AND PAYMENT, PART 2 – DIVISION TWO PAY ITEMS, Article 2.31 – HABITAT (PAY ITEM NO. 2711.5) PRICE BASED ON LUMP SUM PAY UNIT, Paragraph B. **Add** the following:

“The bid price for Pay Item No. 2711.5 shall be based on the following items and quantities: (12) Habitat Snags, (17) Habitat Logs, and (5) Habitat Root Wads.”

Item No. 2: SECTION 01700 – PROJECT CLOSE-OUT, COMPLIANCE CERTIFICATE AND RELEASE FORM. **Delete** in its entirety, and **replace** with the attached COMPLIANCE CERTIFICATE AND RELEASE FORM, labeled Addendum No. 1.

Item No. 3: SECTION 02870 - SITE FURNISHINGS, PART 2 - PRODUCTS, Article 2.1 – MANUFACTURERS AND PRODUCTS, Paragraph A - Products, Item 5 – Picnic Tables: Type A – 4 bench. **Delete** in its entirety and **replace** with the following:

“5. Not Used.”

Item No. 4: SECTION 02870 - SITE FURNISHINGS, PART 2 – PRODUCTS, Article 2.1 – MANUFACTURERS AND PRODUCTS, Paragraph A - Products, Item 12 – Custom Commemorative Bridge Bench. **Add** the following sentence to the first paragraph:

“Manufacturer shall be experienced in fabrication of similar precast park features, equal to Quick Crete Products Corp, 866-703-3434.”

Item No. 5: SECTION 02870 - SITE FURNISHINGS, PART 2 – PRODUCTS, Article 2.1 – MANUFACTURERS AND PRODUCTS, Paragraph A - Products, Item 12 – Custom Commemorative Bridge Bench. **Add** the following sentences to the second paragraph:

“Anti-Graffiti Coating shall be Sherwin-Williams 1K Siloxane, Evonik Industries Protectisil, or equal. Coating shall be clear and shall be applied in accordance with manufacturer’s recommendations.”

Item No. 6: SECTION 02870 - SITE FURNISHINGS, PART 2 – PRODUCTS, Article 2.1 – MANUFACTURERS AND PRODUCTS, Paragraph A - Products, Item 14 – Drinking Fountain. **Delete** the model number and **replace** with the following:

“4420BF1UDB.”

Item No. 7: SECTION 02870 - SITE FURNISHINGS, PART 2 – PRODUCTS, Article 2.1 – MANUFACTURERS AND PRODUCTS, Paragraph A - Products, Item 17 – Whale Tail Bench. **Delete** in its entirety and **replace** with the following:

“17. Whale Tail Bench:

Aluminum Whale Tail Bench by Blastworks Art & Sign, or approved equal. 6’ wide x 6’ long x 20” seat height. Installation Method: Underground Hidden Mount / Slab Not Visible as per manufacturer’s specifications and modified with brick paver installation over hidden slab.

Provide a clear coated Level 2 (sanded to 120gr) Finish.

<http://blastworks.ca/whale-tail-bus-bench/cast-aluminum-bus-benches.html>; (250) 713-1665.”

Item No. 8: SECTION 03450 - PRECAST ARCHITECTURAL CONCRETE, PART 1 – GENERAL, Article 1.4 – ACTION SUBMITTALS, Paragraph E. **Delete** in its entirety.

Item No. 9: SECTION 03450 - PRECAST ARCHITECTURAL CONCRETE, PART 1 – GENERAL, Article, 1.6. – QUALITY ASSURANCE, Paragraph A. **Delete** in its entirety and **replace** with the following:

“A. Fabricator Qualifications: Precast concrete plant with at least 15 years of experience manufacturing items similar in nature to the work required under this contract.”

Item No. 10: SECTION 03450 - PRECAST ARCHITECTURAL CONCRETE, PART 2 – PRODUCTS, Article 2.1 – PERFORMANCE REQUIREMENTS, Paragraph A. **Delete** and **replace** with the following:

“A. Not used.”

DRAWINGS:

Item No. 11: SHEET L-101 – LANDSCAPE MATERIALS PLAN – BRIDGE PARK. **Change** the detail reference for LANDSCAPE STEPPING STONES **from** F/L-151 **to** D/L-151.

Item No. 12: SHEET L-103 – LANDSCAPE MATERIALS PLAN – BRIDGE PARK PLAZA DETAIL PLAN. **Change** the detail reference for LANDSCAPE STEPPING STONES **from** F/L-151 **to** D/L-151.

Item No. 13: SHEET L-151 – LANDSCAPE MATERIALS DETAILS. **Change** the title of Detail F – LANDSCAPE STEPPING STONE **to** Detail D – LANDSCAPE AND INTERTIDAL STEPPING STONES.

Item No. 14: SHEET E-102 – SITE POWER & LIGHTING PLAN – BRIDGE PARK. **Add** the following NOTE 4:

“4. The utility work identified to be provided by AEL&P, including the utility pole relocation, medium voltage underground feeder to the padmount transformer, the padmount transformer, and the secondary feeder to the service switchboard will be paid by CBJ to AEL&P. AEL&P may include, at their own expense, the provision of a padmount switch and medium voltage feeders beneath the Douglas Bridge and to West Eighth Street as part of their system upgrades. Provide work coordination.”

By: 
Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 4

SPECIAL PROVISIONS

COMPLIANCE CERTIFICATE AND RELEASE FORM

PROJECT: DOWNTOWN SEAWALK – BRIDGE TO GOLD CREEK, PHASE III

CONTRACT NO: E16-128

The CONTRACTOR must complete and submit this to the Engineering Contract Administrator with respect to the entire contract.

Completed forms may be submitted upon completion of the Project. All requirements and submittals must be met before final payment will be made to the CONTRACTOR.

I certify that the following and any referenced attachments are true:

- All WORK has been performed, materials supplied, and requirements met in accordance with the applicable Drawings, Specifications, and Contract Documents.
- All Suppliers and Subcontractors have been paid in full with no claims for labor, materials or other services outstanding. If all Subcontractors and suppliers are not paid in full, please explain on a separate sheet.
- All employees have been paid not less than the current prevailing wage rates set by the State of Alaska (or U.S. Department of Labor, as applicable).
- All equal employment opportunity, certified payroll and other reports have been filed in accordance with the prime contract.
- The attached list of Subcontractors is complete (required from CONTRACTOR). The Contract Administrator was advised and approved of all Subcontractors before WORK was performed and has approved any substitutions of Subcontractors.
- All DBE firms listed as a precondition of the prime contract award must have performed a commercially useful function in order for the WORK to count to a DBE goal. All DBE firms performed the WORK stated and have received at least the amount claimed for credit in the Contract Documents.
- All DBE Subcontractors must attach a signed statement of the payment amount received, the nature of WORK performed, whether any balance is outstanding, and indicate that no rebates are involved.
- If the amount paid is less than the amount originally claimed for DBE credit, the CONTRACTOR has attached approval from the Contract Administrator for underutilization.

I understand it is unlawful to misrepresent information in order to receive a payment which would otherwise be withheld if these conditions were not met. I am an authorized agent of this firm and sign this freely and voluntarily. The foregoing statements are true and apply to the following project contractor.

Firm Name Capacity: CONTRACTOR

Signed Printed Name and Title Date

Return completed form to: Greg Smith, Engineering Contract Administrator, City and Borough of Juneau, 155 South Seward Street, Juneau, AK 99801. Call (907) 586-0873 if we can be of further assistance or if you have any questions.

END OF SECTION