



ADDENDUM TO THE CONTRACT

for the

**Bartlett Regional Hospital (BRH)
Tomosynthesis Renovation
Contract No. BE17-032**

ADDENDUM NO.: TWO

**CURRENT DEADLINE FOR BIDS:
November 1, 2016**

PREVIOUS ADDENDA: ONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: October 28, 2016

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

PROJECT MANUAL:

- Item No. 1 SECTION 00800 SUPPLEMENTARY GENERAL CONDITIONS, SGC 6.6 PERMITS, **Add** the following paragraph:
- C. The OWNER shall apply for, and obtain, the necessary building permit for this Project however; the CONTRACTOR is responsible for scheduling and coordinating all necessary inspection. The CBJ Inspection number is 586-1703. All other provisions of this Section remain in effect.

DRAWINGS:

- Item No. 1 A201 DEMOLITION AND RENOVATION PLANS, Detail 2 FLOOR PLAN, Key Note No. 11, **Delete** "8" from the sentence.
- Item No. 2 S001 GENERAL NOTES TYPICAL DETAILS, GENERAL NOTES, BASE COURSE, **Replace** second sentence to read "Place base course in one lift and compact to a minimum density of 95% of maximum dry unit weight according to ASTM D698".
- Item No. 3 S001 GENERAL NOTES TYPICAL DETAILS, Detail B. ANCHOR DETAIL, **Add** note: "Confirm anchor size and material with equipment manufacturer and engineer." For general information the bolt size and material information shown on the drawings is based on information provided by Hologic, during design.
- Item No. 4 S200 STRUCTURAL FOUNDATION AND SLAB PLAN, Detail No. 2 ENLARGED PLAN, **Revise** note reading "... #5 at 1'-0" oc. ..." **to read** "...#4 at 1'-0" on center each way ..."

- Item No. 5 S200 STRUCTURAL FOUNDATION AND SLAB PLAN, Detail No. 2 ENLARGED PLAN, **Add** note "Confirm anchor size and material with equipment manufacturer and engineer." For general information the bolt size and material information shown on the drawings is based on information provided by Hologic, during design.
- Item No. 6 Addendum No. 1, Hologic Drawings 2.1: Regarding optional holes. (4) mounting points are required. The optional holes offer an alternative location for 2 of the mounting points presumably to avoid conflicts in the field.

By: 

Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 2