



ENGINEERING DEPARTMENT

**INFORMATION TO BIDDERS**  
for

**Contract No. BE17-156**  
**Centennial Hall Floor Renovation**

**ISSUED BY:**

City and Borough of Juneau  
ENGINEERING DEPARTMENT  
155 South Seward Street  
Juneau, Alaska 99801

**Date Issued: February 8, 2017**

---

The following information is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: [http://www.juneau.org/engineering\\_ftp/contracts/Contracts.php](http://www.juneau.org/engineering_ftp/contracts/Contracts.php). This is ***not*** an addendum.

- ❖ Slab Moisture Test - Onsite testing results are attached.

# Centinial Hall Floor Replacement

NorthWind Architects, Onsite Testing Results

NWA-1642

Date of install: 9/10/2016

Testing Time: 11am-3pm

Date of Final Testing: 9/13/2016

Station	Air, Temp.		Air RH%		PH Test (PH)	Initial: F	RRH - Rapid RH in hole		Calcium Chloride Test		Gain (g)				
	Initial	Final	Initial	Final			Initial: %	Final: %	Init. Wt (g)	Final Wt. (g)		MVER (lbs #)			
Station 1	58F	65.4F	64.74%	64.11%	7-8, 8-9	68F	9/10/2016	66% 65F	9/13/2016	66%	9/10/2016	9/13/2016	MVER=118.932xGain/Time	1.487	0.90
Station 2	66.5F	66F	54.00%	62.90%	PH 9	N/A	N/A	N/A	N/A	N/A	14:07h	13:39h		1.817	1.10
Station 3	67F	67.6F	53.20%	59.00%	PH 8-9	65F	13:35h	64% 64F	62%	14:13h	29.3	13:34h	30.9	2.147	1.30
Station 4	66F	67.6F	55.20%	59.00%	PH 10	66F	13:50h	63% 64F	67%	14:28h	29.1	13:25h	30.6	3.304	2.00
Station 5	66.7F	66.2F	54.80%	62.30%	PH 8	67F	13:40h	74% 64F	69%	14:18h	29	13:45h	30.3	2.147	1.30
Station 6	67.3F	66.2F	53.00%	59.70%	PH 8+	68F	13:40h	73% 65F	71%	14:24h	29.6	13:50h	30.3	2.313	1.40
Station 7	67.6F	66F	52.90%	61.00%	PH 8-9	N/A	13:53h	N/A	N/A	14:33h	29.1	13:57h	30.7	2.643	1.60
							13:20h			14:36h	29.1	14:00h			