



ADDENDUM TO THE CONTRACT

for the

Blueberry Hills Road Reconstruction Contract No. BE17-139

ADDENDUM NO.: TWO

CURRENT DEADLINE FOR BIDS:
March 7, 2017

PREVIOUS ADDENDA: ONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: February 24, 2017

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php

SPECIAL PROVISIONS:

Item No. 1 SECTION 03303 SIDEWALK, CURB AND GUTTER, PART 3 EXECUTION, 3.2 CONCRETE ACCESS PAD, 6-INCHES THICK, WITH DETECTABLE TILES, **Delete and replace** Paragraph A. with the following:

- A. Concrete sidewalk segments for access ramps shall be constructed as shown on the Drawings. The concrete ramps including the side ramps shall be graded to a 1.7% maximum slope and shall be 6-inches thick. Detectable tiles shall be installed at each ramp to the dimensions and locations shown on the Drawings. Cast in place detectable tiles shall be manufactured by Armor-tile <http://www.armor-tile.com>. Number 33538, Color "Federal Yellow" sizes shown on plans. No substitutions will be allowed. Installation of the detectable tiles shall be in accordance with the manufacturer's installation instructions.

By: 
Greg Smith,
Contract Administrator