



ADDENDUM TO THE CONTRACT

for the

**Statter Harbor Breakwater
Safety Improvements
Contract No. DH18-001**

ADDENDUM NO.: ONE

**CURRENT DEADLINE FOR BIDS:
August 10, 2017**

PREVIOUS ADDENDA: NONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: August 3, 2017

The following items of the contract are modified as herein indicated. All other items remain the same. This is a faxed addendum. A confirming copy will not be mailed to you. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineeringftp/contracts/Contracts.php>

CLARIFICATION:

Item No. 1 The Alaska Hire preference does not apply to this project.

DRAWINGS:

Item No. 1 DRAWING SHEET 1.03: BREAKWATER FLOAT PARTIAL PLANS AND TYPICAL SECTION. **Add** the following note: "A 2x8 timber rubstrip not shown this sheet exists over the float exterior 4x8 timber walers. Remove and reinstall 2x rubstrip as required to access float thru-rods, incidental."

Item No. 2 DRAWING SHEET 2.01: LEDGER AND FRAMING PLAN. **Add** the following note: "Deck level of transverse concrete float units may vary vertically up to $\frac{3}{4}$ " from deck level of intersecting longitudinal concrete float units. In locations where a vertical height difference at float unit intersections occurs, field drilled holes in timber ledger shall be located such that the resulting top of grating is either one-half the distance above or one-half the distance below the deck of the vertical height difference measured at the float intersection, and to provide minimum vertical separation between deck of concrete float units and top of grating on all sides of breakwater opening."

By: 
Greg Smith
Contract Administrator

Total number of pages contained within this Addendum: 1