BARTLETT REGIONAL HOSPITAL (BRH) SERVER ROOM FIRE SUPPRESSION SYSTEM

Contract No. BE18-171

File No. 1989



SECTION 00005 - TABLE OF CONTENTS

DIVISION 0 - BIDDING AND CONTRACT REQUIREMENTS, CONTRACT FORMS, AND CONDITIONS OF THE CONTRACT

BIDDING	and CONTRACT REQUIREMENTS	No. of Pages
00005	Table of Contents	. 2
00030	Notice Inviting Bids	
00100	Instructions to Bidders	
00300	Bid	
00310	Bid Schedule	
00320	Bid Bond	
00360	Subcontractor Report	
00370	Contractor Financial Responsibility	
CONTRAC	CT FORMS	
00500	Agraement	. 7
00610	Agreement	
00620	Payment Bond	
00020	1 dyllicht Dold	. 2
CONDITIO	ONS OF THE CONTRACT	
00700	General Conditions	. 44
00800	Supplementary General Conditions	. 6
00830	Alaska Labor Standards, Reporting, and	
	Prevailing Wage Rate Determination	. 1
01700	Project Closeout	
TECHNIC	AL SPECIFICATIONS	
DIVISION	1 - GENERAL REQUIREMENTS	
011000	Summary	. 4
011005	Measurement and Payment	
012500	Substitution Procedures	
012600	Contract Modification Procedures	
012900	Payment Procedures	
013100	Project Management and Coordination	
013200	Construction Progress Documentation	
013233	Photographic Documentation	
013300	Submittal Procedures	
014200	References	
015000	Temporary Facilities and Controls	
015200	Security	
015221A	Special Safety Requirements	
015221B	ICRA Infection Control for Construction & Renovation	
016000	Product Requirements	
017300	Execution	
017700	Closeout Procedures	
017823	Operation and Maintenance Data	
017839	Project Record Documents	

SECTION 00005 - TABLE OF CONTENTS

028213	Existing Conditions – Asbestos Abatement	13
DIVISION	21 – FIRE SUPPRESSION	
211300 212200	Fire Suppression Sprinklers	4 9
DIVISION	23 - HVAC	
233300	HVAC Air Duct Accessories	3
DIVISION	26 - ELECTRICAL	
260529	Hangers and Supports for Electrical Systems	3
DIVISION	28 – ELECTRONIC SAFETY AND SECURITY	
280513 280528 28462.11	Conductors and Cables for Electrical Safety and Security Pathways for Electronic Safety and Security Addressable Fire Alarm System	6 4 11

DRAWINGS

MECHANICAL DRAWINGS

SHEET M1 - Server Room 2425, Electrical Room 1131 Plans

SHEET M2 - Server Room 2402B Plan

DIVISION 2 - SITE CONSTRUCTION

ELECTRICAL DRAWINGS

SHEET E1 - Enlarged Computer 2425 & Electrical 1131 Plans

SHEET E2 - Enlarged Shell 2402B Room Plan

SECTION 00030 - NOTICE INVITING BIDS

OBTAINING CONTRACT DOCUMENTS. The Contract Documents are entitled:

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

The Contract Documents may be obtained at the City & Borough of Juneau (CBJ) Engineering Department, 3rd Floor Marine View Center, upon payment of \$30 (non-refundable) for each set of Contract Documents (including Technical Specifications and Drawings) or may be downloaded for free at the CBJ Engineering Department webpage at: www.juneau.org/engineering

PRE-BID CONFERENCE. Prospective Bidders are encouraged to attend a Pre-Bid conference of the proposed WORK, which will be conducted by the OWNER and ARCHITECT, at 10:00 a.m. on February 21, 2018 in the City and Borough of Juneau Engineering Conference Room, 3rd Floor, Marine View Center. The object of the conference is to acquaint Bidders with the bid documents and site conditions. Conference call capability will be available for the Pre-Bid meeting. Proposers intending to participate via conference call shall notify the CBJ Engineering Contracts Division, at (907) 586-0490 or Contracts@Juneau.org by 4:30 p.m., February 20, 2018.

DESCRIPTION OF WORK. This Project consists of the following:

- A. The Work of the Project is defined by the Contract Documents and consists of the introduction of a standalone clean agent fire suppression system for Computer / Server Room 2425 with the clean agent tanks located in the adjacent Electrical Room 1131. It also includes the introduction of a second stand-alone clean agent fire suppression system within Computer / Server Room 2402B within Bartlett Regional Hospital. Both systems will be installed with a primary and backup clean agent tank, each with enough capacity to extinguish a fire in the spaces they serve.
- B. The Work will include, but is not necessarily limited to, the installation of the clean agent fire suppression systems, including control panels, storage tanks and piping. Work will also include the removal of portions of the existing wet pipe sprinkler systems in both Computer / Server Rooms, modifications to the fire detection and alarm systems, modifications to the existing supply and return air ductwork, modifications to the existing building automation / controls systems, as well as modifications to an existing AC unit in 2402B that will include the addition of an electrical shunt trip, ductwork, and condensate drain. This scope of work also includes final testing, acceptance and training on the new stand-alone clean agent systems.
- C. The Work in Electrical Room 1131 will also include the abatement / removal-disposal of a portion of the existing ACM gypsum board ceiling to facilitate access to the above-ceiling space, as well as the abatement / removal-disposal of a portion of the existing ACM spray-applied fireproofing and overspray on the underside of the steel pan decking. The ceiling area to be removed is to be no more than 24" x 24" in size. The amount of spray-applied fire proofing to be removed is to be limited to that which is necessary to complete the core drilling work through the decking. See Mechanical Drawings and Section 028213 for details.
- D. All work is to be performed with ICRA controls in place, and with protection in place to not damage active computers, servers and other equipment present in the work spaces.

SECTION 00030 - NOTICE INVITING BIDS

COMPLETION OF WORK.

Work Description

Completion Date

Substantial Completion	June 8, 2018
Final Completion	June 28, 2018

DEADLINE FOR BIDDER QUESTIONS: February 26, 2018

DEADLINE FOR BIDS: Sealed bids must be received by the Purchasing Division **prior to 2:00 p.m., Alaska Time on March 5, 2018** or such later time as may be announced by addendum at any time prior to the deadline. Bids will be time and date stamped by the Purchasing Division, which will establish the official time of receipt of bids. Bids will be opened immediately thereafter in the Assembly Chambers of the Municipal Building, 155 S. Seward Street, unless otherwise specified.

Bid documents delivered in person or by **courier** service must be delivered to:

Bid documents delivered by the <u>U.S. Postal</u> **Service** must be mailed to:

PHYSICAL LOCATION:

City and Borough of Juneau, Purchasing Division 105 Municipal Way, Room 300 Juneau, AK 99801

MAILING ADDRESS:

City and Borough of Juneau, Purchasing Division 155 South Seward Street Juneau, AK 99801

Please affix the label below to outer envelope in the lower left hand corner.

IMPORTAN	IT NOTICE TO BIDDER	
To submit y	our Bid:	
1. Print you	ur company name and address on the uppe	er left corner of
your env	velope.	
2. Comple	te this label and place it on the lower le	eft corner
of your	envelope.	
	BID NUMBER: BE18-171	
\mathbf{S}		В
${f E}$	SUBJECT: BRH Server Room	I
\mathbf{A}	Fire Suppression System	D
L		
${f E}$	DEADLINE DATE:	
D		
	PRIOR TO 2:00PM ALASKA	

Mailing/delivery times to Alaska may take longer than other areas of the U.S. Late bids will <u>not</u> be accepted and will be returned.

SITE OF WORK. The site of the WORK is 3260 Hospital Drive, Juneau, Alaska.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171 NOTICE INVITING BIDS Page 00030-2

SECTION 00030 - NOTICE INVITING BIDS

BIDDING, CONTRACT, or TECHNICAL QUESTIONS. All communications relative to this WORK, prior to opening Bids, shall be directed to the following:

Greg Smith, Contract Administrator
CBJ Engineering Department, 3rd Floor, Marine View Center
greg.smith@juneau.org
Telephone: (907) 586-0873
Fax: (907) 586-4530

BID SECURITY. Each Bid shall be accompanied by a certified or cashier's check or Bid Bond, in the amount of 5% percent of the Bid, payable to the City and Borough of Juneau, Alaska, as a guarantee that the Bidder, if its Bid is accepted, will promptly execute the Agreement. A Bid shall not be considered unless one of the forms of Bidder's security is enclosed with it.

CONTRACTOR'S LICENSE. All contractors are required to have a current Alaska Contractor's License, prior to submitting a Bid, and a current Alaska Business License prior to award.

BID TO REMAIN OPEN. The Bidder shall guarantee the Bid for a period of 120 Days from the date of Bid opening. Any component of the Bid may be awarded anytime during the 120 Days.

OWNER'S RIGHTS RESERVED. The OWNER reserves the right to reject any or all Bids, to waive any informality in a Bid, and to make award to the lowest responsive, responsible Bidder as it may best serve the interests of the OWNER.

OWNER: City and Borough of Juneau

Greg Smith, Contract Administrator

Date

2/9/2018

1.0 DEFINED TERMS. Terms used in these Instructions to Bidders and the Notice Inviting Bids, which are defined in the General Conditions, have the meanings assigned to them in the General Conditions. The term "Bidder" means one who submits a Bid directly to the OWNER, as distinct from a sub-bidder, who submits a Bid to a Bidder.

2.0 INTERPRETATIONS AND ADDENDA.

- A. INTERPRETATIONS. All questions about the meaning or intent of the Contract Documents are to be directed to the Engineering Contracts Administrator. Interpretations or clarifications considered necessary by the Engineering Contracts Administrator in response to such questions will be issued by Addendum, mailed, faxed, or delivered to all parties recorded by the Engineering Contracts Administrator, or OWNER, as having received the Contract Documents. Questions received less than seven Days prior to the Deadline for Bids may not be answered. Only questions answered by formal written Addendum will be binding. Oral and other interpretations or clarifications will be without legal effect.
- B. ADDENDA. Addenda may be issued to modify the Contract Documents as deemed advisable by the OWNER. Addenda may be faxed or, if addendum format warrants, addenda may be posted to the CBJ Engineering Department website. In any event, notification of addendum issuance will be faxed to planholders. Hard copies are available upon request. The OWNER will make all reasonable attempts to ensure that all planholders receive notification of Addenda, however, it is strongly recommended by the OWNER that bidders independently confirm the contents, number, and dates of each Addendum prior to submitting a Bid.
- **3.0 FAIR COMPETITION**. More than one Bid from an individual, firm, partnership, corporation, or association under the same or different names will not be considered. If the OWNER believes that any Bidder is interested in more than one Bid for the WORK contemplated, all Bids in which such Bidder is interested will be rejected. If the OWNER believes that collusion exists among the Bidders, all Bids will be rejected.
- **RESPONSIBILITY OF BIDDERS.** Only responsive Bids from responsible Bidders will be considered. A Bid submitted by a Bidder determined to be not responsible may be rejected. The OWNER may find a bidder to be not responsible for any one of the following reasons, but is not limited in its responsibility analysis to the following factors:
 - A. Evidence of bid rigging or collusion;
 - B. Fraud or dishonesty in the performance of previous contracts;
 - C. Record of integrity;
 - D. More than one bid for the same work from an individual, firm, or corporation under the same or different name;
 - E. Unsatisfactory performance on previous or current contracts;
 - F. Failure to pay, or satisfactorily settle, all bills due for labor and material on previous contracts;

- G. Uncompleted work that, in the judgment of the OWNER, might hinder or prevent the bidder's prompt completion of additional work, if awarded;
- H. Failure to reimburse the OWNER for monies owed on any previous contracts;
- I. Default under previous contracts;
- J. Failure to comply with any qualification requirements of the OWNER; special standards for responsibility, if applicable, will be specified. These special standards establish minimum standards or experience required for a responsible Bidder on a specific contract;
- K. Engaging in any activity that constitutes a cause for debarment or suspension under the CBJ Procurement Code 53.50 or submitting a bid during a period of debarment;
- L. Lack of skill, ability, financial resources, or equipment required to perform the contract; or
- M. Lack of legal capacity to contract.
- N. Bidders must be registered as required by law and in good standing for all amounts owned to the OWNER per Paragraph 21.0 of this Section.
- O. Failure to submit Failure to submit <u>all</u> completed documents as required and specified on the Bid Form, Section 00300.

Nothing contained in this section deprives the OWNER of its discretion in determining the lowest responsible bidder. Before a Bid is considered for award, a Bidder may be requested to submit information documenting its ability and competency to perform the WORK, according to general standards of responsibility and any special standards which may apply. It is Bidder's responsibility to submit sufficient, relevant, and adequate information. OWNER will make its determination of responsibility and has no obligation to request clarification or supplementary information.

- **5.0 NON-RESPONSIVE BIDS**. Only responsive Bids will be considered. Bids may be considered non-responsive and may be rejected. Some of the reasons a Bid may be rejected for being non-responsive are:
 - A. If a Bid is received by the CBJ Purchasing Division after the Deadline for Bids.
 - B. If the Bid is on a form other than that furnished by the OWNER, or legible copies thereof; or if the form is altered or any part thereof is detached; or if the Bid is improperly signed.
 - C. If there are unauthorized additions, conditional or alternate Bids, or irregularities of any kind which may tend to make the bid incomplete, indefinite, ambiguous as to its meaning, or in conflict with the OWNER's Bid document.
 - D. If the Bidder adds any unauthorized conditions, limitations, or provisions reserving the right to accept or reject any award, or to enter into a contract pursuant to an award. This does not exclude a Bid limiting the maximum gross amount of awards acceptable to any one Bidder at any one Bid opening, provided that any selection of awards will be made by the OWNER.

- E. If the Bid does not contain a Unit Price for each pay item listed, except in the case of authorized alternate pay items.
- F. If the Bidder has not acknowledged receipt of each Addendum.
- G. If the Bidder fails to furnish an acceptable Bid guaranty with the Bid.
- H. If any of the Unit Prices Bid are excessively unbalanced (either above or below the amount of a reasonable Bid) to the potential detriment of the OWNER.
- I. If a Bid modification does not conform to Article 15.0 of this Section.

6.0 BIDDER'S EXAMINATION OF CONTRACT DOCUMENTS AND SITE. It is the responsibility of each Bidder before submitting a Bid:

- A. To examine thoroughly the Contract Documents, and other related data identified in the Bidding documents (including "technical data" referred to below):
 - 1. To visit the site to become familiar with and to satisfy the Bidder as to the general and local conditions that may affect cost, progress, or performance, of the WORK,
 - 2. To consider federal, state and local laws and regulations that may affect cost, progress, or performance of the WORK,
 - 3. To study and carefully correlate the Bidder's observations with the Contract Documents, and other related data; and
 - 4. To notify the ARCHITECT of all conflicts, errors, or discrepancies in or between the Contract Documents and such other related data.

7.0 REFERENCE IS MADE TO THE SUPPLEMENTARY GENERAL CONDITIONS FOR IDENTIFICATION OF:

- A. Those reports of explorations and tests of subsurface conditions at the site which have been utilized by the Architect of Record in the preparation of the Contract Documents. The Bidder may rely upon the accuracy of the technical data contained in such reports, however, the interpretation of such technical data, including any interpolation or extrapolation thereof, together with non-technical data, interpretations, and opinions contained therein or the completeness thereof is the responsibility of the Bidder.
- B. Those Drawings of physical conditions in or relating to existing surface and subsurface conditions (except underground utilities) which are at or contiguous to the site have been utilized by the Architect of Record in the preparation of the Contract Documents. The Bidder may rely upon the accuracy of the technical data contained in such Drawings, however, the interpretation of such technical data, including any interpolation or extrapolation thereof, together with nontechnical data, interpretations, and opinions contained in such Drawings or the completeness thereof is the responsibility of the Bidder.
- C. Copies of such reports and Drawings will be made available by the OWNER to any Bidder on request if said reports and Drawings are not bound herein. Those reports and Drawings are not part of the Contract Documents, but the technical data contained therein upon which the Bidder is entitled to rely, as provided in Paragraph SGC-4.2 of the Supplementary General Conditions, are incorporated herein by reference.

- D. Information and data reflected in the Contract Documents with respect to underground utilities at or contiguous to the site is based upon information and data furnished to the OWNER and the Architect of Record by the owners of such underground utilities or others, and the OWNER does not assume responsibility for the accuracy or completeness thereof unless it is expressly provided otherwise in the Supplementary General Conditions, or in Section 01530 Protection and Restoration of Existing Facilities of the General Requirements.
- E. Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders on subsurface conditions, underground utilities and other physical conditions, and possible changes in the Contract Documents due to differing conditions appear in Paragraphs 4.2, 4.3, and 4.4 of the General Conditions.
- F. Before submitting a Bid, each Bidder will, at Bidder's own expense, make or obtain any additional examinations, investigations, explorations, tests, and studies and obtain any additional information and data which pertain to the physical conditions (surface, subsurface, and underground utilities) at or contiguous to the site or otherwise which may affect cost, progress, or performance of the WORK and which the Bidder deems necessary to determine its Bid for performing the WORK in accordance with the time, price, and other terms and conditions of the Contract Documents.
- G. On request in advance, the OWNER will provide each Bidder access to the site to conduct such explorations and tests as each Bidder deems necessary for submission of a Bid. Bidder shall fill all holes and shall clean up and restore the site to its former condition upon completion of such explorations.
- H. The lands upon which the WORK is to be performed, rights-of-way and easements for access thereto and other lands designated for use by the CONTRACTOR in performing the WORK are identified in the Contract Documents. All additional lands and access thereto required for temporary construction facilities or storage of materials and equipment are to be provided by the CONTRACTOR. Easements for permanent structures or permanent changes in existing structures are to be obtained and paid for by the OWNER unless otherwise provided in the Contract Documents.
- I. The submission of a Bid will constitute an incontrovertible representation by the Bidder that the Bidder has complied with every requirement of Article 6.0, "Bidder's Examination of Contract Documents and Site" herein, that without exception the Bid is premised upon performing the WORK required by the Contract Documents and such means, methods, techniques, sequences, or procedures of construction as may be indicated in or required by the Contract Documents, and that the Contract Documents are sufficient in scope and detail to indicate and convey understanding of all terms and conditions for performance of the WORK.

8.0 BID FORM.

- A. The Bid shall be made on the Bid Schedule(s) bound herein, or on the yellow Bid packet provided, or on legible and complete copies thereof, and shall contain the following: Sections 00300, 00310, the required Bid Security, and any other documents required in Section 00300 Bid.
- B. All blanks on the Bid Form and Bid Schedule must be completed in ink or typed.

- C. Bids by corporations must be executed in the corporate name by the president, a vice-president (or other corporate officer). The corporate address and state of incorporation must appear below the signature.
- D. Bids by partnerships must be executed in the partnership name and be signed by a managing partner, and the official address of the partnership must appear below the signature.
- E. The Bidder's Bid must be signed. All names must be printed or typed below the signature.
- F. The Bid shall contain an acknowledgment of receipt of all Addenda, the numbers of which shall be filled in on the Bid form. <u>Failure to acknowledge Addenda may render Bid non-responsive and may cause its rejection.</u>
- G. The address to which communications regarding the Bid are to be directed must be shown.
- **9.0 QUANTITIES OF WORK**. The quantities of WORK, or material, stated in Unit Price items of the Bid are supplied only to give an indication of the general scope of the WORK; the OWNER does not expressly or by implication agree that the actual amount of WORK, or material, will correspond therewith, and reserves the right after award to increase or decrease the amount of any Unit Price item of the WORK by an amount up to and including 25 percent of any Bid item, without a change in the Unit Price, and shall include the right to delete any Bid item in its entirety, or to add additional Bid items up to and including an aggregate total amount not to exceed 25 percent of the Contract Price (see Section 00700 General Conditions, Article 10 Changes In the WORK).
- **10.0 SUBSTITUTE OR "OR-EQUAL" ITEMS.** Substitution requests are not accepted during the bidding process. The procedure for the submittal of substitute or "or-equal" products is specified in Section 01300 Contractor Submittals.
- 11.0 SUBMISSION OF BIDS. The Bid shall be delivered by the time and to the place stipulated in Section 00030 Notice Inviting Bids. It is the Bidder's sole responsibility to see that its Bid is received in proper time. Oral, telegraphic, emailed, or faxed Bids will not be considered. The envelope enclosing the sealed Bids shall be plainly marked in the upper left-hand corner with the name and address of the Bidder and shall also include the label included in Section 00030 Notice Inviting Bids. The Bid Security shall be enclosed in the same envelope with the Bid
- 12.0 BID SECURITY, BONDS, AND INSURANCE. Each Bid shall be accompanied by a certified, or cashier's check, or approved Bid Bond in an amount of at least 5 percent of the total Bid price. The "total Bid price" is the amount of the Base Bid, plus the amount of alternate Bids, if any, which total to the maximum amount for which the CONTRACT could be awarded. Said check or Bond shall be made payable to the OWNER and shall be given as a guarantee that the Bidder, if offered the WORK, will enter into an Agreement with the OWNER, and will furnish the necessary insurance certificates, Payment Bond, and Performance Bond; each of said Bonds, if required, and insurance amounts shall be as stated in the Supplementary General Conditions. In case of refusal or failure to enter into said Agreement, the check or Bid Bond, as the case may be, may be forfeited to the OWNER. If the Bidder elects to furnish a Bid Bond as its Bid security, the Bidder shall use the Bid Bond form bound herein, or one conforming substantially to it in form. Bid Bonds must be accompanied by a legible Power of Attorney.

- **13.0 RETURN OF BID SECURITY.** The OWNER will return all Bid security checks (certified or cashier's) accompanying such of the Bids as are not considered in making the award. All other Bid securities will be held until the Agreement has been executed. Following execution of the Agreement, all other Bid security checks will be returned to the respective Bidders whose Bids they accompanied and Bid security bonds will be appropriately discarded.
- 14.0 DISCREPANCIES IN BIDS. In the event there is more than one Pay Item in a Bid Schedule, the Bidder shall furnish a price for all Pay Items in the schedule, and failure to do so may render the Bid non-responsive and cause its rejection. In the event there are Unit Price Pay Items in a Bid Schedule and the "amount" indicated for a Unit Price Bid Item does not equal the product of the Unit Price and quantity, the Unit Price shall govern and the amount will be corrected accordingly, and the Bidder shall be bound by said correction. In the event there is more than one Pay Item in a Bid Schedule and the total indicated for the schedule does not agree with the sum of the prices Bid on the individual items, the prices Bid on the individual items shall govern and the total for the schedule will be corrected accordingly, and the Bidder shall be bound by said correction.

15.0 BID MODIFICATIONS AND UNAUTHORIZED ALTERNATIVE BIDS.

A. Any bidder may deliver a modification to a bid in person, by mail or fax (907-586-4561), provided that such modification is received by the Purchasing Division no later than the deadline for bids. Modifications will be time and date stamped by the Purchasing Division, which will establish the official time of receipt of the modification. The modification must not reveal the bid price but should be in the form of an addition or subtraction or other modification so that the final prices will not be known until the sealed bid is opened.

The Bid modifications shall be provided on the **Bid Modification Form** located at the end of this Section. Submittal of any other form by the vendor may deem the modification unacceptable by the OWNER **A mail or fax modification should not reveal the Bid price but should provide the addition or subtraction or other modification so that the final prices will not be known by the City and Borough until the sealed Bid is opened. Submitted Modification forms shall include the modification to the unit price or lump sum amount of each pay item modified.**

FAX DISCLAIMER: It is the responsibility of the bidder to submit modifications in a timely manner. Bidders' use of a fax machine to modify their bid shall be at bidders' sole risk. The Purchasing Division will attempt to keep the fax machine in good working order but will not be responsible for bid modifications that are late due to mechanical failure, a busy fax machine, or any other cause arising from bidder's use of a fax machine, even if bidder submits a transmission report or provides other confirmation indicating that the bidder transmitted a bid modification prior to the deadline. The City will not be responsible for its failure to receive the modification whether such failure is caused by equipment or human error, or otherwise. Bidders are therefore strongly encouraged to confirm receipt of their bid modification with the Purchasing Division (907-586-5258) prior to deadline.

B. <u>Conditioned bids, limitations, or provisos attached to the Bid or bid modification will render it unauthorized and cause its rejection as being non-responsive</u>. The completed Bid forms shall be without interlineations, alterations, or erasures in the printed text. All changes shall be initialed by the person signing the Bid. Alternative Bids will not be considered unless called for.

16.0 WITHDRAWAL OF BID. Prior to the Deadline for Bids, the Bid may be withdrawn by the Bidder by means of a written request, signed by the Bidder or its properly authorized representative. Such written request must be delivered to the place stipulated in the Notice Inviting Bids for receipt of Bids.

17.0 AWARD OF CONTRACT.

- A. Award of a contract, if it is awarded, will be on the basis of materials and equipment described in the Drawings or specified in the Technical Specifications and will be made to the lowest responsive, responsible Bidder whose Bid complies with all the requirements prescribed. Unless otherwise specified, any such award will be made within the period stated in the Notice Inviting Bids that the Bids are to remain open. Unless otherwise indicated, a single award will be made for all the Bid items in an individual Bid Schedule.
- B. If the OWNER has elected to advertise this Project with a Base Bid and Alternates, the OWNER may elect to award the contract for the Base Bid, or the Base Bid in combination with one or more Alternates selected by the OWNER. In either case, award shall be made to the responsive, responsible bidder offering the lowest total Bid for the WORK to be awarded.

18.0 EXECUTION OF AGREEMENT.

- A. All Bids of value greater than \$1,000,000 must be approved by the CBJ Assembly. After the CBJ Assembly has approved the award and after the Bid protest period, the OWNER will issue a Notice of Intent to Award to the approved Bidder. The Bidder to whom award is made shall execute a written Agreement with the OWNER on the Agreement form, Section 00500, collect insurance, and shall furnish all certificates and Bonds required by the Contract Documents within 10 Days (calendar) from the date of the Notice of Intent to Award letter.
- B. Failure or refusal to enter into the Agreement as herein provided or to conform to any of the stipulated requirements in connection therewith shall be just cause for annulment of the award and forfeiture of the Bid security. If the lowest responsive, responsible Bidder refuses or fails to execute the Agreement, the OWNER may award the contract to the second lowest responsive, responsible Bidder. If the second lowest responsive, responsible Bidder refuses or fails to execute the Agreement, the OWNER may award the contract to the third lowest responsive, responsible Bidder. On the failure or refusal of such second or third lowest Bidder to execute the Agreement, each such Bidder's Bid securities shall be likewise forfeited to the OWNER.
- **19.0 LIQUIDATED DAMAGES**. Provisions for liquidated damages if any, are set forth in Section 00500 Agreement.

20.0 FILING A PROTEST.

A. A Bidder may protest the proposed award of a competitive sealed Bid by the City and Borough of Juneau. The protest shall be executed in accordance with CBJ Ordinance 53.50.062 PROTESTS and CBJ Ordinance 53.50.080 ADMINISTRATION OF PROTEST. The entire text of the CBJ Purchasing Ordinance can be accessed at the CBJ website, http://www.juneau.org/law/code/code.php, or call the CBJ Purchasing Division at (907) 586-5258 for a copy of the ordinance.

- B. Late protests shall not be considered by the CBJ Purchasing Officer.
- 21.0 CONTRACTOR'S GOOD STANDING WITH CBJ FINANCE DEPARTMENT: Contractors must be in good standing with the CBJ prior to award, and prior to any contract renewals, and in any event no later than seven business days following notification by the CBJ of intent to award as indicated in the Posting Notice of Bids. Good standing means: all amounts owed to the CBJ are current and the Contractor is not delinquent with respect to any taxes, fees, assessment, or other monies due and owed the CBJ, or a Confession of Judgment has been executed and the Contractor is in compliance with the terms of any stipulation associated with the Confession of Judgment, including being current as to any installment payments due; and Contractor is current in all CBJ reporting obligations (such as sales tax registration and reporting and business personal property declarations). Failure to meet these requirements may be cause for rejection of your bid. To determine if your business is in good standing, or for further information, contact the CBJ Finance Department's Sales Tax Division at (907) 586-5265 for sales tax issues, Assessor's Office at (907)586-0930 for business personal property issues, or Collections Division at (907) 586-5268 for all other accounts.
- **22.0 PERMITS AND LICENSES**. The CONTRACTOR is responsible for all WORK associated with meeting any local, state, and/or federal permit and licensing requirements.

CITY AND BOROUGH OF JUNEAU PURCHASING DIVISION FAX NO. 907-586-4561

BID MODIFICATION FORM

Note: All modifications shall be made to the original bid amount(s). If more that Modification form is submitted by any one bidder, changes from all Modification forms submitted will be combined and applied to the original bid. Changes modified Bid amounts will be calculated by the OWNER. PAY ITEM NO. PAY ITEM DESCRIPTION MODIFICA TO UNIT PR LUMP S (indicate) Indicate Total Bid Increase or Decrease: \$ Name of Bidding Firm Responsible Party Signature	
PAY ITEM NO. PAY ITEM DESCRIPTION TO UNIT PR LUMP S (indicate) Total Bid Increase or Decrease: \$ Name of Bidding Firm	cation
Name of Bidding Firm	CICE OR
Name of Bidding Firm	
Responsible Party Signature	
Printed Name (must be an authorized signatory for Bidd	ling Firm)

END OF SECTION

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

SECTION 00300 - BID

BID TO: THE CITY AND BOROUGH OF JUNEAU

 The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an Agreement with the OWNER in the form included in the Contract Documents (as defined in Article 7 of Section 00500 - Agreement) to perform the WORK as specified or indicated in said Contract Documents entitled

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

- 2. Bidder accepts all of the terms and conditions of the Contract Documents, including without limitation those in the "Notice Inviting Bids" and "Instructions to Bidders," dealing with the disposition of the Bid Security.
- 3. This Bid will remain open for the period of time stated in the "Notice Inviting Bids" unless otherwise required by law. Bidder will enter into an Agreement within the time and in the manner required in the "Notice Inviting Bids" and the "Instructions to Bidders," and will furnish insurance certificates, Payment Bond, Performance Bond, and any other documents as may be required by the Contract Documents.
- 4. Bidder has familiarized itself with the nature and extent of the Contract Documents, WORK, site, locality where the WORK is to be performed, the legal requirements (federal, state and local laws, ordinances, rules, and regulations), and the conditions affecting cost, progress or performance of the WORK and has made such independent investigations as Bidder deems necessary.
- 5. This Bid is genuine and not made in the interest of or on behalf of any undisclosed person, firm or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation; Bidder has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid; Bidder has not solicited or induced any person, firm or corporation to refrain from bidding; and Bidder has not sought by collusion to obtain for itself any advantage over any other Bidder or over OWNER.
- 6. To all the foregoing, and including all Bid Schedule and information required of Bidder contained in this Bid Form, said Bidder further agrees to complete the WORK required under the Contract Documents within the Contract Time stipulated in said Contract Documents, and to accept in full payment therefore the Contract Price based on the total bid price(s) named in the aforementioned Bid Schedule.
- 7. Bidder has examined copies of all the Contract Documents including the following Addenda (receipt of all of which is hereby acknowledged by the Undersigned):

Addenda No.	Date Issued	 Addenda No.	Date Issued

Give number and date of each addenda above. Failure to acknowledge receipt of all Addenda may cause the Bid to be non-responsive and may cause its rejection.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

SECTION 00300 - BID

8. The Bidder has read this Bid and agrees to the conditions as stated herein by signing his/her signature in the space provided below.

Dated:	Bidder:		
Alaska		(Company Name)	
CONTRACTOR's	By:		
Business License No:	<u> </u>	(Signature)	
Alaska	Printed Name:		
CONTRACTOR's			
License No:	Title:		_
Telephone No:	Address:		
		(Street or P.O. Box)	
Fax No:	<u> </u>		
		(City, State, Zip)	
Email:			

- 9. TO BE CONSIDERED, ALL BIDDERS MUST COMPLETE AND INCLUDE THE FOLLOWING AT THE TIME OF THE DEADLINE FOR BIDS:
 - ➤ Bid, Section 00300 (includes addenda receipt statement)
 - ➤ Completed Bid Schedule, Section 00310
 - ➤ Bid Security (Bid Bond, Section 00320, or by a certified or cashier's check as stipulated in the Notice Inviting Bids, Section 00030)
- 10. The apparent low Bidder is required to complete and submit the following documents by 4:30 p.m. on the *fifth business day* following the date of the Posting Notice.
 - ➤ Subcontractor Report, Section 00360
 - Contractor Financial Responsibility Form 00370

The apparent low Bidder who fails to submit a completed Subcontractor Report within the time specified in Section 00360 – Subcontractor Report will be found to be not a responsible Bidder and may be required to forfeit the Bid security. The OWNER will then consider the next lowest Bidder for award of the contract.

- 11. The successful Bidder will be required to submit, within <u>ten Days (calendar)</u> after the date of the "Notice of Intent to Award" letter, the following executed documents:
 - Agreement Forms, Section 00500
 - Performance Bond, Section 00610
 - Payment Bond, Section 00620
 - > Certificates of Insurance, (CONTRACTOR) Section 00700 and Section 00800

SECTION 00310 - BID SCHEDULE

Bid Schedule for construction of <u>BE18-</u> with the Contract Documents.	171 BRH S	erver Room Fire Suppression System, in accordance
		erials for installation of a fire suppression system in the RK as described in these Contract Documents.
TOTAL BID	\$.	(Price in Figures)
Date:	Bidder: _	(Company Name)

SECTION 00320 - BID BOND

KNOW ALL PERSONS BY	THESE PRESENTS, th	nat
as Princ	ipal, and	
as Surety, are held and firmly bound un	nto THE CITY AND 1	BOROUGH OF JUNEAU hereinafter calle
"OWNER," in the sum of		
	ly to be made, we bind	five percent of the total amount of the Bid) for ourselves, our heirs, executors, administrators presents.
WHEREAS, said Principal has the Bid Schedule of the OWNER's Co.		OWNER to perform the WORK required unde
	BRH Server Roo Fire Suppression Sy CBJ Contract No. BE	vstem
in the manner required in the "Notice Agreement on the form of Agreement be of insurance, and furnishes the require null and void, otherwise it shall remain	Inviting Bids" and the bound with said Contract description and Performance Bond are in full force and effect, said Surety shall pay al	ntract by said OWNER and, within the time and "Instructions to Bidders" enters into a writtent Documents, furnishes the required certificate and Payment Bond, then this obligation shall be. In the event suit is brought upon this bond be I costs incurred by said OWNER in such suit
SIGNED AND SEALED, this	day of	, 20
(SEAL)(Principal)		(SEAL)(Surety)
By:		Bv:
(Signature)		By:(Signature)

SECTION 00360 - SUBCONTRACTOR REPORT

LIST OF SUBCONTRACTORS (AS 36.30.115)

The apparent low Bidder must submit a list of Subcontractors that the Bidder proposes to use in the performance of this contract on the fifth business day following the Posting Notice of Bids. If the fifth day falls on a weekend or holiday, the report is due by close of business on the next business Day following the weekend or holiday. The Subcontractor Report list must include each Subcontractor's name, address, location, evidence of valid Alaska Business License, and valid Alaska Contractor's Registration under AS 08.18. If no Subcontractors are to be utilized in the performance of the WORK, write in ink or type "NONE" on line (1) below

SUBCONTRACTOR	¹ AK Contractor <u>License No.</u>	¹ Contact Name	Type of	Contract	✓ if
<u>ADDRESS</u>	² AK Business <u>License No.</u>	² Phone No.	Work	<u>Amount</u>	DBE
1	2			\$	_ 🗆
2	2			\$	_ 🗆
3	2			\$	
4	2			\$	_ 🗆
I certify that the above listed were valid at the time Bids v			OR Registration	on(s), if applicab	le,
CONTRACTOR, Authorize	d Signature				
CONTRACTOR, Printed Na	ame				
COMPANY		<u> </u>			

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171 SUBCONTRACTOR REPORT Page 00360-1

SECTION 00360 - SUBCONTRACTOR REPORT

- A. A Bidder may replace a listed Subcontractor if the Subcontractor:
 - 1. fails to comply with AS 08.18;
 - 2. files for bankruptcy or becomes insolvent;
 - 3. fails to execute a contract with the Bidder involving performance of the WORK for which the Subcontractor was listed and the Bidder acted in good faith;
 - 4. fails to obtain bonding;
 - 5. fails to obtain insurance acceptable to the OWNER;
 - 6. fails to perform the contract with the Bidder involving work for which the Subcontractor was listed:
 - 7. must be substituted in order for the CONTRACTOR to satisfy required state and federal affirmative action requirements;
 - 8. refuses to agree or abide with the Bidder's labor agreement; or
 - 9. is determined by the OWNER not to be responsible.
 - 10. is not in "Good Standing" with the OWNER as required in Article 21.0 in Section 00100 Instructions to Bidders.
- B. If a Bidder fails to list a Subcontractor or lists more than one Subcontractor for the same portion of WORK, the Bidder shall be considered to have agreed to perform that portion of WORK without the use of a Subcontractor and to have represented the Bidder to be qualified to perform that WORK.
- C. A Bidder who attempts to circumvent the requirements of this section by listing as a Subcontractor another contractor who, in turn, sublets the majority of the WORK required under the contract violates this section.
- D. If a contract is awarded to a Bidder who violates this section, the OWNER may:
 - 1. cancel the contract; or
 - 2. after notice and a hearing, assess a penalty on the Bidder in an amount that does not exceed 10 percent of the value of the subcontract at issue.
- E. On the Subcontractor Report, the apparent low Bidder must list any Subcontractors anticipated to perform WORK with a value of greater than one-half of one percent of the intended award amount, or \$2,000, whichever is less.
- F. An apparent low Bidder who fails to submit a completed Subcontractor Report within the time specified in this section may be found to be not a responsible Bidder and may be required to forfeit the Bid security. The OWNER will then consider the next lowest Bidder for award of the contract.

SECTION 00370 - CONTRACTOR'S FINANCIAL RESPONSIBILITY

The apparent low Bidder must complete this form and submit on the fifth business day following the Posting Notice of Bids. If the fifth day falls on a weekend or holiday, the report is due by close of business on the next business Day following the weekend or holiday. Attach additional sheets as necessary to respond to questions.

PROJECT: BE18-171 BRH Server Room Fire Suppression System

	the General Contractor on this project, I intend to subcontract% of the total value of this ntract.
A.	EXPERIENCE
	Have you ever failed to complete a contract due to insufficient resources? No [] Yes If YES, explain:
2.	Describe arrangements you have made to finance this work:
	Have you had previous construction contracts or subcontracts with the City and Borough of Juneau? Yes [] No
4.	Describe your most recent or current contract, its completion date, and scope of work:
5.	List below, and/or as an attachment to this questionnaire, other construction projects you have completed, dates of completion, scope of work, and total contract amount for each project completed in the past twelve months.

SECTION 00370 - CONTRACTOR'S FINANCIAL RESPONSIBILITY

6.	subcontrac		nt working days a	-		ver failed to pay a the Owner (for proj	ects
]] Yes	[] No	If yes, please	attach a detai	led explanation	for each occurrence	e.
B. 1.	•		s an attachment,	the equipmen	t you have avai	lable and intend to u	use for this
	1	ІТЕМ	QUANTITY	MAKE	MODEL	SIZE/CAPACITY	PRESENT MARKET VALUE
			ase any equipme describe type, q			listed on table B-1?	
		-	ny equipment for describe type an		t listed on table	B-1?	

SECTION 00370 - CONTRACTOR'S FINANCIAL RESPONSIBILITY

4. Is your bid based on firm offers for	all materials necessary for this project?
[] Yes [] No If NO, please exp	lain:
I hereby certify that the above staten	nents are true and complete.
Contractor Signature	Name and Title of Person Signing
Signature	Date

THIS AGREEMENT is between _	<u> THE CITY AND BOROUGH OF JUNEAU</u> (hereinafter called OWNER)
and	(hereinafter called CONTRACTOR)
OWNER and CONTRACTOR, in	consideration of the mutual covenants hereinafter set forth, agree as follows

ARTICLE 1. WORK.

CONTRACTOR shall complete the WORK as specified or as indicated under the Bid Schedule of the OWNERS Contract Documents Contract BE18-171, BRH Server Room Fire Suppression System.

The WORK is generally described as follows:

A. The Work of the Project is defined by the Contract Documents and consists of the introduction of a standalone clean agent fire suppression system for Computer / Server Room 2425 with the clean agent tanks located in the adjacent Electrical Room 1131. It also includes the introduction of a second stand-alone clean agent fire suppression system within Computer / Server Room 2402B within Bartlett Regional Hospital. Both systems will be installed with a primary and backup clean agent tank, each with enough capacity to extinguish a fire in the spaces they serve.

- B. The Work will include, but is not necessarily limited to, the installation of the clean agent fire suppression systems, including control panels, storage tanks and piping. Work will also include the removal of portions of the existing wet pipe sprinkler systems in both Computer / Server Rooms, modifications to the fire detection and alarm systems, modifications to the existing supply and return air ductwork, modifications to the existing building automation / controls systems, as well as modifications to an existing AC unit in 2402B that will include the addition of an electrical shunt trip, ductwork, and condensate drain. This scope of work also includes final testing, acceptance and training on the new stand-alone clean agent systems.
- C. The Work in Electrical Room 1131 will also include the abatement / removal-disposal of a portion of the existing ACM gypsum board ceiling to facilitate access to the above-ceiling space, as well as the abatement / removal-disposal of a portion of the existing ACM spray-applied fireproofing and overspray on the underside of the steel pan decking. The ceiling area to be removed is to be no more than 24" x 24" in size. The amount of spray-applied fire proofing to be removed is to be limited to that which is necessary to complete the core drilling work through the decking. See Mechanical Drawings and Section 028213 for details.
- D. All work is to be performed with ICRA controls in place, and with protection in place to not damage active computers, servers and other equipment present in the work spaces.

The WORK to be paid under this contract shall include the following: Total Bid as shown in Section 00310 - Bid Schedule.

ARTICLE 2. CONTRACT COMPLETION TIME.

Work Description

Completion Date

Substantial Completion	June 8, 2018
Final Completion	June 28, 2018

ARTICLE 3. DATE OF AGREEMENT

The date of this agreement will be the date of the last signature on page four of this section.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

ARTICLE 4. LIQUIDATED DAMAGES.

OWNER and the CONTRACTOR recognize that time is of the essence of this Agreement and that the OWNER will suffer financial loss if the WORK is not completed within the time specified in Article 2 herein, plus any extensions thereof allowed in accordance with Article 12 of the General Conditions. They also recognize the delays, expense, and difficulties involved in proving in a legal proceeding the actual damages suffered by the OWNER if the WORK is not completed on time. Accordingly, instead of requiring any such proof, the OWNER and the CONTRACTOR agree that as liquidated damages for delay (but not as a penalty) the CONTRACTOR shall pay the OWNER \$820 for each Day that expires after the completion time(s) specified in Article 2 herein. The amount of liquidated damages specified above is agreed to be a reasonable estimate based on all facts known as of the date of this Agreement.

ARTICLE 5. CONTRACT PRICE.

OWNER shall pay CONTRACTOR for completion of the WORK in accordance with the Contract Documents in current funds the amount set forth in the Bid Schedule. The CONTRACTOR agrees to accept as full and complete payment for all WORK to be done in this contract for: CBJ Contract BE18-171, BRH Server Room Fire Suppression System, those Lump Sum amounts as set forth in the Bid Schedule in the Contract Documents for this Project.

The total amount of this contract shall be	(\$	<u>),</u> except
as adjusted in accordance with the provisions of the Contract Documents.		•

ARTICLE 6. PAYMENT PROCEDURES.

CONTRACTOR shall submit Applications for Payment in accordance with Article 14 of the General Conditions. Applications for Payment will be processed by the ARCHITECT as provided in the General Conditions.

Progress payments will be paid in full in accordance with Article 14 of the General Conditions until ninety (90) percent of the Contract Price has been paid. The remaining ten (10) percent of the Contract Price may be retained, in accordance with applicable Alaska State Statutes, until final inspection, completion, and acceptance of the Project by the OWNER.

ARTICLE 7. CONTRACT DOCUMENTS.

The Contract Documents which comprise the entire Agreement between OWNER and CONTRACTOR concerning the WORK consist of this Agreement (pages 00500-1 to 00500-6, inclusive) and the following sections of the Contract Documents:

- ➤ Table of Contents (pages 00030-1 to 00030-2, inclusive).
- Notice Inviting Bids (pages 00030-1 to 00030-3, inclusive).
- ➤ Instructions to Bidders (pages 00100-1 to 00100-9, inclusive).
- ➤ Bid (pages 00300-1 to 00300-2, inclusive).
- ➤ Bid Schedule (pages 00310-1, inclusive).
- ➤ Bid Bond (page 00320-1, inclusive) or Bid Security.
- Subcontractor Report (pages 00360-1 to 00360-2, inclusive).
- Contractor Financial Responsibility (pages 00370-1 to 00370-3, inclusive).
- Performance Bond (pages 00610-1 to 00610-2, inclusive).
- Payment Bond (pages 00620-1 to 00620-2, inclusive).
- ➤ Insurance Certificate(s).
- ➤ General Conditions (pages 00700-1 to 00700-44, inclusive).
- ➤ Supplementary General Conditions (pages 00800-1 to 00800-6, inclusive).
- Alaska Labor Standards, Reporting, and Prevailing Wage Determination (page 00830-1).
- > Technical Specifications as listed in the Table of Contents.
- > Drawings consisting of 4 sheets, as listed in the Table of Contents.
- Addenda numbers ______ to _____, inclusive.
- ➤ Change Orders which may be delivered or issued after the Date of the Agreement and which are not attached hereto.

There are no Contract Documents other than those listed in this Article 7. The Contract Documents may only be amended by Change Order as provided in Paragraph 3.3 of the General Conditions.

ARTICLE 8. MISCELLANEOUS.

Terms used in this Agreement which are defined in Article 1 of the General Conditions will have the meanings indicated in the General Conditions.

No assignment by a party hereto of any rights under or interests in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound; and specifically but without limitation monies that may become due and monies that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.

OWNER and CONTRACTOR each binds itself, its partners, successors, assigns and legal representatives to the other party hereto, its partners, successors, assigns and legal representatives in respect of all covenants, agreements and obligations contained in the Contract Documents. This Agreement shall be governed by the laws of the State of Alaska. Jurisdiction shall be in the State of Alaska, First Judicial District.

IN WITNESS WHEREOF, OWNER and CONTRACTOR have caused this Agreement to be executed on the date listed below signed by OWNER.

OWNER:	CONTRACTOR:
City and Borough of Juneau	
	(Company Name)
(Signature)	(Signature)
By: <u>Duncan Rorie Watt, City & Borough Manager</u> (Printed Name)	By:(Printed Name, Authority or Title)
(Printed Name)	(Printed Name, Authority or Title)
Date:	Date: (CONTRACTOR Signature Date)
	(CONTRACTOR Signature Date)
OWNER's address for giving notices:	CONTRACTOR's address for giving notices:
155 South Seward Street	
Juneau, Alaska 99801	
907-586-0873 907-586-4530	
(Telephone) (Fax)	(Telephone) (Fax)
	(E-mail address)
	CONTRACTOR License No

CERTIFICATE (if Corporation)

STATE OF)) SS:				
COUNTY OF) SS:)				
I HEREBY C	ERTIFY that a meeting	of the Board of Dir	rectors of t	he	
		a cor	poration e	xisting under th	ne laws of
the State ofwas duly passed and a	, held on adopted:	1	, 20	, the following	ng resolution
of the Corpor BOROUGH (Secretary of t of this Corpor I further certif	O, thatation, be and is hereby a OF JUNEAU and this cohe Corporation, and with ration." fy that said resolution is S WHEREOF, I have here	nuthorized to execut orporation and that the the Corporate Sea now in full force ar	the Agr the execut l affixed, s and effect.	eement with the ion thereof, attended the shall be the offi	e CITY AND ested by the cial act and deed
corporation this	day of		retary		
(SEAL)					

CERTIFICATE (if Partnership)

STAT	OF)) SS:
COUN	
	HEREBY CERTIFY that a meeting of the Partners of the
	a partnership existing under the laws of the State
	, held on, 20, the following resolution was duly nd adopted:
	"RESOLVED, that, as of the Partnership, be and is hereby authorized to execute the Agreement with the CITY AND BOROUGH OF JUNEAU and this partnership and that the execution thereof, attested by the shall be the official act and deed of this Partnership."
	I further certify that said resolution is now in full force and effect.
20	IN WITNESS WHEREOF, I have hereunto set my hand this, day of,,
	Secretary
(SEAL	

CERTIFICATE (if Joint Venture)

STATE ()F)		
COUNTY	YOF) SS:		
I	HEREBY (CERTIFY that a	meeting of the Principals of the	
			a joint venture existing unc	der the laws of the
State of _adopted:		, held on	, 20, the following resolution	was duly passed and
J. B — I	oint Ventur BOROUGH further cert	e, be and is here OF JUNEAU at the standard stan	, as, as, as	h the CITY AND ereof, attested by the at Venture."
(SEAL)				Secretary

SECTION 00610 - PERFORMANCE BOND

	KNOW ALL PERSONS B	Y THESE PRESENTS	S: That we	
			(Name of CONTRA	ACTOR)
a				
		(Corporation, Part	nership, Individual)	
hereiı	nafter called "Principal" and _			
			urety)	
of	, State of	hereir	nafter called the "Surety", are he	ld and firmly bound
to <u>th</u>	ne CITY AND BOROUGH of (Owner)`		hereinafter called "OWNER",	for the penal sum
of	,	(City and State)	dollars (\$) in
			ch sum well and truly to be made and severally, firmly by these p	
certai	n contract with the OWNER,	the effective date of w	ch that whereas, the CONTRACT hich is (CBJ Contracts Office to d and made a part hereof for the	fill in effective date
		DD11 G	_	

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

NOW, THEREFORE, if the Principal shall truly and faithfully perform its duties, all the undertakings, covenants, terms, conditions, and agreements of said contract during the original term thereof, and any extensions thereof, which may be granted by the OWNER, with or without notice to the Surety, and if it shall satisfy all claims and demands incurred under such contract, and shall fully indemnify and save harmless the OWNER from all costs and damages which it may suffer by reason of failure to do so, and shall reimburse and repay the OWNER all outlay and expense which the OWNER may incur in making good any default, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to the WORK to be performed thereunder or the specifications accompanying the same shall in any wise affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the WORK or to the Specifications.

PROVIDED, FURTHER, that no final settlement between the OWNER and the Principal shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

SECTION 00610 - PERFORMANCE BOND

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

IN WITNESS WHEREOF, this instrument is issued in two (2) identical counterparts, each one of which shall be deemed an original.

CONTRACTOR:	
By:(Signature)	
(Signature)	
(Printed Name)	
(Timed Ivanie)	
(Company Name)	
(Mailing Address)	
(City, State, Zip Code)	
SURETY:	
By:	Date Issued:
By:(Signature of Attorney-in-Fact)	
(Printed Name)	
(Company Name)	
(Mailing Address)	
(City, State, Zip Code)	
(Affix SURETY'S SEAL)	

NOTE: If CONTRACTOR is Partnership, all Partners must execute bond.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

SECTION 00620 - PAYMENT BOND

VNOW ALL DEDCONG DV THESE DESCRITS. That we

INOW ALL	LENSONS DI THESE EKI	ESENTS. That we
		(Name of CONTRACTOR)
	a	
	((Corporation, Partnership, Individual)
hereinafter called "Prin	ncipal" and	
	-	(Surety)
of	, State of	hereinafter called the "Surety," are held and
firmly bound to the CI	TY AND BOROUGH of JU (Owner) (City	JNEAU, ALASKA hereinafter called "OWNER," for the and State)
penal sum of		Dollars
(\$	we bind ourselves, our hei	y of the United States, for the payment of which sum well rs, executors, administrators and successors, jointly and
		ON is such that Whereas, the CONTRACTOR has entered
		ive date of which is (CBJ Contracts Office to fill in effective which is hereto attached and made a part hereof for the

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

NOW, THEREFORE, if the Principal shall promptly make payment to all persons, firms, Subcontractors, and corporations furnishing materials for, or performing labor in the prosecution of the WORK provided for in such contract, and any authorized extension or modification thereof, including all amounts due for materials, lubricants, oil, gasoline, coal and coke, repairs on machinery, equipment and tools, consumed or used in connection with the construction of such WORK, and all insurance premiums on said work, and for all labor performed in such WORK, whether by Subcontractor or otherwise, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to the WORK to be performed thereunder or the specifications accompanying the same shall in any wise affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the WORK or to the Specifications.

PROVIDED, FURTHER, that no final settlement between the OWNER and the Principal shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

SECTION 00620 - PAYMENT BOND

BRH Server Room Fire Suppression System CBJ Contract No. BE18-171

IN WITNESS WHEREOF, this instrument is issued in two (2) identical counterparts, each one of which shall be deemed an original.

By:	
(Signature)	_
(Printed Name)	_
(Company Name)	_
(Mailing Address)	_
(City, State, Zip Code)	_
SURETY:	
Rv.	Date Issued:
By:(Signature of Attorney-in-Fact)	
(Printed Name)	_
(Company Name)	_
(Mailing Address)	_
(City, State, Zip Code)	_
(Affix SURETY'S SEAL)	

NOTE: If CONTRACTOR is Partnership, all Partners must execute bond.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

CONTRACTOR:

SECTION 00700 - GENERAL CONDITIONS

TABLE OF CONTENTS

ARTICLE 1 DEFINITIONS		00700-5
ARTICL	E 2 PRELIMINARY MATTERS	
2.1	Delivery of Bonds/Insurance Certificates	00700-9
2.2	Copies of Documents	
2.3	Commencement of Contract Time; Notice to Proceed	00700-9
2.4	Starting the WORK	00700-9
2.5	Pre-construction Conference	00700-9
2.6	Finalizing CONTRACTOR Submittals	00700-9
ARTICL	E 3 CONTRACT DOCUMENTS: INTENT, AMENDING, RE	USE
3.1	Intent	00700-10
3.2	Order of Precedence of Contract Documents	00700-10
3.3	Amending and Supplementing Contract Documents	00700-11
3.4	Reuse of Documents	
ARTICL	E 4 AVAILABILITY OF LANDS; PHYSICAL CONDITIONS	; REFERENCE POINTS
4.1	Availability of Lands	00700-11
4.2	Physical Conditions - Subsurface and Existing Structures	00700-11
4.3	Differing Site Conditions	00700-12
4.4	Physical Conditions - Underground Utilities	00700-12
4.5	Reference Points	00700-13
4.6	Use of the CBJ/State Lemon Creek Gravel Pit	00700-13
ARTICL	E 5 BONDS AND INSURANCE	
5.1	Performance, Payment and Other Bonds	00700-14
5.2	Insurance	00700-15
ARTICL	E 6 CONTRACTOR'S RESPONSIBILITIES	
6.1	Supervision and Superintendence	00700-16
6.2	Labor, Materials, and Equipment	
6.3	Adjusting Progress Schedule	
6.4	Substitutes or "Or Equal" Items	
6.5	Concerning Subcontractors, Suppliers and Others	00700-18
6.6	Permits	
6.7	Patent Fees and Royalties	
6.8	Laws and Regulations	00700-19

TABLE OF CONTENTS

ARTICLI	E 6 CONTRACTOR'S RESPONSIBILITIES (Cont'd.)	
6.9	Taxes	00700-19
6.10	Use of Premises	00700-19
6.11	Safety and Protection	00700-20
6.12	Shop Drawings and Samples	
6.13	Continuing the WORK	
6.14	Indemnification	
6.15	CONTRACTOR's Daily Reports	00700-22
6.16	Assignment of Contract	00700-22
6.17	CONTRACTOR's Responsibility for Utility Property and Services	00700-22
6.18	Operating Water System Valves	00700-22
6.19	Contractor's Work Schedule Limitations	00700-23
ARTICLI	E 7 OTHER WORK	
7.1	Related Work at Site	00700-23
7.2	Coordination	00700-23
ARTICLI	E 8 OWNER'S RESPONSIBILITIES	
8.1	Communications	00700-24
8.2	Payments	00700-24
8.3	Lands, Easements, and Surveys	00700-24
8.4	Change Orders	00700-24
8.5	Inspections and Tests	00700-24
8.6	Suspension of WORK	00700-24
8.7	Termination of Agreement	00700-24
ARTICLI	E 9 ARCHITECT'S STATUS DURING CONSTRUCTION	
9.1	OWNER's Representative	
9.2	Visits to Site	00700-24
9.3	Project Representation	00700-24
9.4	Clarifications and Interpretations.	
9.5	Authorized Variations in WORK	
9.6	Rejecting or Accepting Defective WORK	
9.7	CONTRACTOR Submittals, Change Orders, and Payments	00700-25
9.8	Decisions on Disputes	00700-25
9.9	Limitation on ARCHITECT's Responsibilities	00700-26

TABLE OF CONTENTS

ARTICLE	10 CHANGES IN THE WORK	
10.1	General	
10.2	Allowable Quantity Variations	00700-27
ARTICLE	11 CHANGE OF CONTRACT PRICE	
11.1	General	00700-27
11.2	Costs Relating to Weather	
11.3	Cost of WORK (Based on Time and Materials)	00700-28
11.4	CONTRACTOR's Fee	00700-31
11.5	Excluded Costs	00700-31
ARTICLE	12 CHANGE OF CONTRACT TIME	
12.1	General	00700-32
12.2	Extensions of Time for Delay Due to Weather	00700-33
	13 WARRANTY AND GUARANTEE; TESTS AND INSPECTIO FION, REMOVAL, OR ACCEPTANCE OF DEFECTIVE WORK	,
13.1	Warranty and Guarantee	00700 23
13.1	Access to WORK	
13.2	Inspections and Tests	
13.3	OWNER May Stop the WORK	
13.4	Correction or Removal of Defective WORK	
13.5	One Year Correction Period	
13.7	Acceptance of Defective WORK	
ARTICLE	14 PAYMENTS TO CONTRACTOR AND COMPLETION	
14.1	Schedule of Values (Lump Sum Price Breakdown)	
14.2	Unit Price Bid Schedule	
14.3	Application for Progress Payment	00700-35
14.4	CONTRACTOR's Warranty of Title	00700-36
14.5	Review of Applications for Progress Payment	00700-36
14.6	Partial Utilization	00700-37
14.7	Substantial Completion	00700-37
14.8	Final Application for Payment	00700-37
14.9	Final Payment and Acceptance	00700-37
14.10	Release of Retainage and Other Deductions	00700-38
14.11	CONTRACTOR's Continuing Obligation	00700-38
14.12	Final Payment Terminates Liability of OWNER	

TABLE OF CONTENTS

ARTICLE 15 SUSPENSION OF WORK AND TERMINATION

15.1 15.2 15.3 15.4	Suspension of WORK by OWNER Termination of Agreement by OWNER (CONTRACTOR Default) Termination of Agreement by OWNER (For Convenience) Termination of Agreement by CONTRACTOR	00700-39 00700-39
ARTICLE	16 MISCELLANEOUS	
16.1	Giving Notice	00700-40
16.2	Rights In and Use of Materials Found on the WORK	
16.3	Right to Audit	
16.4	Archaeological or Historical Discoveries	
16.5	Construction Over or Adjacent to Navigable Waters	
16.6	Gratuity and Conflict of Interest	
16.7	Suits of Law Concerning the WORK	
16.8	Certified Payrolls	
16.9	Prevailing Wage Rates	
16.10	Employment Reference	
16.11	Cost Reduction Incentive	

ARTICLE 1 DEFINITIONS

Wherever used in these General Conditions or in the Contract Documents the following terms have the meanings indicated which are applicable to both the singular and plural thereof. Where a word is capitalized in the definitions and is found not capitalized in the Contract Documents it has the ordinary dictionary definition.

Addenda - Written or graphic instruments issued prior to the opening of Bids which make additions, deletions, or revisions to the Contract Documents.

Agreement - The written contract between the OWNER and the CONTRACTOR covering the WORK to be performed; other documents are attached to the Agreement and made a part thereof as provided therein.

Application for Payment - The form furnished by the ARCHITECT which is to be used by the CONTRACTOR to request progress or final payment and which is to be accompanied by such supporting documentation as is required by the Contract Documents.

ARCHITECT - The ARCHITECT is the firm or person(s) selected by the City and Borough of Juneau (CBJ) to perform the duties of project inspection and management. CBJ will inform the CONTRACTOR of the identity of the ARCHITECT at or before the Notice to Proceed.

Architect of Record – The individual, partnership, corporation, joint-venture or other legal entity legally responsible for preparation of Design and Construction Documents for the project.

Asbestos - Any material that contains more than one percent asbestos and is friable or is releasing asbestos fibers into the air above current action levels established by the United States Occupational Safety and Health Administration.

Bid - The offer or proposal of the Bidder submitted on the prescribed form setting forth the price or prices for the WORK.

Bonds - Bid, Performance, and Payment Bonds and other instruments which protect against loss due to inability or refusal of the CONTRACTOR to perform its contract.

CBJ - City and Borough of Juneau

CBJ Project Manager - The authorized representative of the City and Borough of Juneau Engineering Department, as OWNER, who is responsible for administration of the contract.

Change Order - A document recommended by the ARCHITECT, which is signed by the CONTRACTOR and the OWNER and authorizes an addition, deletion, or revision in the WORK, or an adjustment in the Contract Price or the Contract Time, issued on or after the Effective Date of the Agreement.

Contract Documents - The Table of Contents, Notice Inviting Bids, Instructions to Bidders, Bid Forms (including the Bid, Bid Schedule(s), Information Required of Bidder, Bid Bond, and all required certificates and affidavits), Agreement, Performance Bond, Payment Bond, General Conditions, Supplementary General Conditions, Technical Specifications, Drawings, Permits, and all Addenda, Field Orders and Change Orders executed pursuant to the provisions of the Contract Documents.

Contract Price - The total monies payable by the OWNER to the CONTRACTOR under the terms and conditions of the Contract Documents.

Contract Time - The number of successive calendar Days or the specific date stated in the Contract Documents for the completion of the WORK.

CONTRACTOR - The individual, partnership, corporation, joint-venture or other legal entity with whom the OWNER has executed the Agreement.

Day - A calendar day of 24 hours measured from midnight to the next midnight.

Defective WORK - WORK that is unsatisfactory, faulty, or deficient; or that does not conform to the Contract Documents; or that does not meet the requirements of any inspection, reference standard, test, or approval referred to in the Contract Documents; or WORK that has been damaged prior to the ARCHITECT's recommendation of final payment.

Drawings - The drawings, plans, maps, profiles, diagrams, and other graphic representations which indicate the character, location, nature, extent, and scope of the WORK and which have been prepared by the Architect of Record and are referred to in the Contract Documents. Shop Drawings are not within the meaning of this paragraph.

Effective Date of the Agreement - The date indicated in the Agreement on which it becomes effective, but if no such date is indicated it means the date on which the Agreement is signed and delivered by the last of the two parties to sign and deliver.

Field Order - A written order issued by the ARCHITECT which may or may not involve a change in the WORK.

General Requirements - Division 1 of the Technical Specifications.

Hazardous Waste - The term Hazardous Waste shall have the meaning provided in Section 1004 of the Solid Waste Disposal Act (42 USC Section 9603) as amended from time to time.

Holidays - The CBJ legal holidays occur on:

- A. New Year's Day January 1
- B. Martin Luther King's Birthday Third Monday in January
- C. President's Day Third Monday in February
- D. Seward's Day Last Monday in March
- E. Memorial Day Last Monday in May
- F. Independence Day July 4
- G. Labor Day First Monday in September
- H. Alaska Day October 18
- I. Veteran's Day November 11
- J. Thanksgiving Day Fourth Thursday and the following Friday in November
- K. Christmas Day December 25.

If any holiday listed above falls on a Saturday, Saturday and the preceding Friday are both legal holidays. If the holiday should fall on a Sunday, Sunday and the following Monday are both legal holidays.

Inspector - The authorized representative of the ARCHITECT assigned to make detailed inspections for conformance to the Contract Documents. Any reference to the Resident Project Representative in this document shall mean the Inspector.

Laws and Regulations; Laws or Regulations - Any and all applicable laws, rules, regulations, ordinances, codes, and/or orders of any and all governmental bodies, agencies, authorities and courts having jurisdiction.

Mechanic's Lien - A form of security, an interest in real property, which is held to secure the payment of an obligation. When referred to in these Contract Documents, "Mechanic's Lien" or "lien" means "Stop Notice".

Milestone - A principal event specified in the Contract Documents relating to an intermediate completion date of a portion of the work, or a period of time within which the portion of the work should be performed prior to Substantial Completion of all the WORK.

Notice of Intent to Award - The written notice by the OWNER to the apparent successful bidder stating that upon compliance by the apparent successful bidder with the requirements listed therein, within the time specified, the OWNER will enter into an Agreement.

Notice of Award - The written notice by the OWNER to the apparent successful bidder stating that the apparent successful bidder has complied with all conditions for award of the contract.

Notice of Completion - A form signed by the ARCHITECT and the CONTRACTOR recommending to the OWNER that the WORK is Substantially Complete and fixing the date of Substantial Completion. After acceptance of the WORK by the OWNER's governing body, the form is signed by the OWNER. This filing starts the 30 day lien filing period on the WORK.

Notice to Proceed - The written notice issued by the OWNER to the CONTRACTOR authorizing the CONTRACTOR to proceed with the WORK and establishing the date of commencement of the Contract Time.

OWNER - The City and Borough of Juneau (CBJ), acting through its legally designated officials, officers, or employees.

Partial Utilization - Use by the OWNER of a substantially completed part of the WORK for the purpose for which it is intended prior to Substantial Completion of all the WORK.

PCB's - Polychlorinated biphenyls.

Petroleum - Petroleum, including crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute), such as oil, petroleum, fuel oil, oil sludge, oil refuse, gasoline, kerosene, and oil mixed with other non-Hazardous Wastes and crude oils.

Project - The total construction of which the WORK to be provided under the Contract Documents may be the whole, or a part as indicated elsewhere in the Contract Documents.

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM CBJ Contract No. BE18-171

Radioactive Material - Source, special nuclear, or byproduct material as defined by the Atomic Energy Act of 1954 (42 USC Section 2011 et seq.) as amended from time to time.

Shop Drawings - All drawings, diagrams, illustrations, schedules and other data which are specifically prepared by or for the CONTRACTOR and submitted by the CONTRACTOR, to the ARCHITECT, to illustrate some portion of the WORK.

Specifications - Same definition as for "Technical Specifications" hereinafter.

Stop Notice - A legal remedy for subcontractors and suppliers who contribute to public works, but who are not paid for their work, which secures payment from construction funds possessed by the OWNER. For public property, the Stop Notice remedy is designed to substitute for mechanic's lien rights.

Sub-Consultant - The individual, partnership, corporation, joint-venture or other legal entity having a direct contract with Architect of Record, or with any of its Consultants to furnish services with respect to the Project.

Subcontractor - An individual, partnership, corporation, joint-venture or other legal entity having a direct contract with the CONTRACTOR, or with any of its Subcontractors, for the performance of a part of the WORK at the site.

Substantial Completion - Refers to when the WORK has progressed to the point where, in the opinion of the ARCHITECT as evidenced by Notice of Completion as applicable, it is sufficiently complete, in accordance with the Contract Documents, so that the WORK can be utilized for the purposes for which it is intended; or if no such notice is issued, when final payment is due in accordance with Paragraph 14.8. The terms "substantially complete" and "substantially completed" as applied to any WORK refer to Substantial Completion thereof.

Supplementary General Conditions - The part of the Contract Documents which make additions, deletions, or revisions to these General Conditions.

Supplier - A manufacturer, fabricator, supplier, distributor, material man, or vendor.

Technical Specifications - Divisions 1 through 16 of the Contract Documents consisting of the General Requirements and written technical descriptions of products and execution of the WORK.

Underground Utilities - All pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments, and any encasements containing such facilities which have been installed underground to furnish any of the following services or materials: water, sewage and drainage removal, electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, traffic, or other control systems.

WORK, Work - The entire completed construction or the various separately identifiable parts thereof required to be furnished under the Contract Documents. WORK is the result of performing, or furnishing labor and furnishing and incorporating materials and equipment into the construction, and performing or furnishing services and furnishing documents, all as required by the Contract Documents.

ARTICLE 2 PRELIMINARY MATTERS

- 2.1 DELIVERY OF BONDS/INSURANCE CERTIFICATES. When the CONTRACTOR delivers the signed Agreements to the OWNER, the CONTRACTOR shall also deliver to the OWNER such Bonds and Insurance Policies and Certificates as the CONTRACTOR may be required to furnish in accordance with the Contract Documents.
- 2.2 COPIES OF DOCUMENTS. The OWNER shall furnish to the CONTRACTOR the required number of copies of the Contract Documents specified in the Supplementary General Conditions.
- 2.3 COMMENCEMENT OF CONTRACT TIME; NOTICE TO PROCEED. The Contract Time will start to run on the commencement date stated in the Notice to Proceed. If no date is stated, Contract Time shall commence upon the date of the Notice to Proceed is issued.

2.4 STARTING THE WORK

- A. The CONTRACTOR shall begin to perform the WORK within 10 days after the commencement date stated in the Notice to Proceed, but no WORK shall be done at the site prior to said commencement date.
- B. Before undertaking each part of the WORK, the CONTRACTOR shall carefully study and compare the Contract Documents and check and verify pertinent figures shown thereon and all applicable field measurements. The CONTRACTOR shall promptly report in writing to the ARCHITECT any conflict, error, or discrepancy which the CONTRACTOR may discover and shall obtain a written interpretation or clarification from the ARCHITECT before proceeding with any WORK affected thereby.
- C. The CONTRACTOR shall submit to the ARCHITECT for review those documents called for under Section 01300 CONTRACTOR Submittals in the General Requirements.
- 2.5 PRE-CONSTRUCTION CONFERENCE. The CONTRACTOR is required to attend a Pre-Construction Conference. This conference will be attended by the ARCHITECT and others as appropriate in order to discuss the WORK in accordance with the applicable procedures specified in the General Requirements, Section 01010 Summary of Work.
- 2.6 FINALIZING CONTRACTOR SUBMITTALS. At least 7 days before submittal of the first Application for Payment a conference attended by the CONTRACTOR, the ARCHITECT and others as appropriate will be held to finalize the initial CONTRACTOR submittals in accordance with the General Requirements. As a minimum the CONTRACTOR's representatives should include it's project manager and schedule expert. The CONTRACTOR should plan on this meeting taking no less than 8 hours. If the submittals are not finalized at the end of the meeting, additional meetings will be held so that the submittals can be finalized prior to the submittal of the first Application for Payment. No Application for Payment will be processed until CONTRACTOR submittals are finalized.

ARTICLE 3 CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

3.1 INTENT

- A. The Contract Documents comprise the entire agreement between the OWNER and the CONTRACTOR concerning the WORK. The Contract Documents shall be construed as a whole in accordance with Alaska Law.
- B. It is the intent of the Contract Documents to describe the WORK, functionally complete, to be constructed in accordance with the Contract Documents. Any WORK, materials, or equipment that may reasonably be inferred from the Contract Documents as being required to produce the intended result shall be supplied whether or not specifically called for. When words or phrases which have a well-known technical or construction industry or trade meaning are used to describe WORK, materials, or equipment such words or phrases shall be interpreted in accordance with that meaning, unless a definition has been provided in Article 1 of the General Conditions. Reference to standard specifications, manuals, or codes of any technical society, organization, or association, or to the Laws or Regulations of any governmental authority, whether such reference be specific or by implication, shall mean the latest standard specification, manual, code, or Laws or Regulations in effect at the time of opening of Bids, except as may be otherwise specifically stated. However, no provision of any referenced standard specification, manual, or code (whether or not specifically incorporated by reference in the Contract Documents) shall be effective to change the duties and responsibilities of the ARCHITECT, OWNER, the CONTRACTOR, or the Architect of Record or any of their consultants, agents, or employees from those set forth in the Contract Documents.
- C. If, during the performance of the WORK, CONTRACTOR discovers any conflict, error, ambiguity or discrepancy within the Contract Documents or between the Contract Documents and any provision of any such Law or Regulation applicable to the performance of the WORK or of any such standard, specification, manual or code or of any instruction of any Supplier referred to in paragraph 6.5, the CONTRACTOR shall report it to the ARCHITECT in writing at once, and the CONTRACTOR shall not proceed with the WORK affected thereby (except in an emergency as authorized by the ARCHITECT) until a clarification Field Order, or Change Order to the Contract Documents has been issued.

3.2 ORDER OF PRECEDENCE OF CONTRACT DOCUMENTS

- A. In resolving conflicts resulting from, errors, or discrepancies in any of the Contract Documents, the order of precedence shall be as follows:
 - 1. Permits from other agencies as may be required by law, excepting the definition of "Permittee" in these permits.
 - 2. Field Orders
 - 3. Change Orders
 - 4. ARCHITECT's written interpretations and clarifications.
 - 5. Agreement
 - 6. Addenda
 - 7. CONTRACTOR's Bid (Bid Form)
 - 8. Supplementary General Conditions
 - 9. Notice Inviting Bids
 - 10. Instructions to Bidders

- 11. General Conditions
- 12. Technical Specifications
- 13 Drawings
- B. With reference to the Drawings the order of precedence is as follows:
 - 1. Figures govern over scaled dimensions
 - 2. Detail drawings govern over general drawings
 - 3. Addenda/Change Order drawings govern over contract Drawings
 - 4. Contract Drawings govern over standard details
- 3.3 AMENDING AND SUPPLEMENTING CONTRACT DOCUMENTS. The Contract Documents may be amended to provide for additions, deletions, and revisions in the WORK or to modify the terms and conditions thereof by a Change Order (pursuant to Article 10 CHANGES IN THE WORK).
- 3.4 REUSE OF DOCUMENTS. Neither the CONTRACTOR, nor any Subcontractor or Supplier, nor any other person or organization performing any of the WORK under a contract with the OWNER shall have or acquire any title to or ownership rights in any of the Drawings, Technical Specifications, or other documents used on the WORK, and they shall not reuse any of them on the extensions of the Project or any other project without written consent of the OWNER.

ARTICLE 4 AVAILABILITY OF LANDS; PHYSICAL CONDITIONS; REFERENCE POINTS

AVAILABILITY OF LANDS. The OWNER shall furnish, as indicated in the Contract Documents, the lands upon which the WORK is to be performed, rights-of-way and easements for access thereto, and such other lands which are designated for the use of the CONTRACTOR. Easements for permanent structures or permanent changes in existing facilities will be obtained and paid for by the OWNER, unless otherwise provided in the Contract Documents. Nothing contained in the Contract Documents shall be interpreted as giving the CONTRACTOR exclusive occupancy of the lands or rights-of-way provided. The CONTRACTOR shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment; provided, that the CONTRACTOR shall not enter upon nor use any property not under the control of the OWNER until a written temporary construction easement, lease or other appropriate agreement has been executed by the CONTRACTOR and the property owner, and a copy of said agreement furnished to the ARCHITECT prior to said use; and, neither the OWNER nor the ARCHITECT shall be liable for any claims or damages resulting from the CONTRACTOR's unauthorized trespass or use of any such properties.

4.2 PHYSICAL CONDITIONS - SUBSURFACE AND EXISTING STRUCTURES

A. Explorations and Reports. Reference is made to SGC 4.2 Physical Conditions of the Supplementary General Conditions for identification of those reports of explorations and tests of sub-surface conditions at the site that have been utilized by the Architect of Record in the preparation of the Contract Documents. The CONTRACTOR may rely upon the accuracy of the technical data contained in such reports, however, reports are not to be considered complete or comprehensive and nontechnical data, interpretations, and opinions contained in such reports are not to be relied on by the CONTRACTOR. The CONTRACTOR is responsible for any further explorations or tests that may be

necessary and any interpretation, interpolation, or extrapolation that it makes of any information shown in such reports.

B. Existing Structures. Reference is made to SGC 4.2 Physical Conditions of the Supplementary General Conditions for identification of those drawings of physical conditions in or relating to existing surface and subsurface structures (except Underground Utilities referred to in Paragraph 4.4 herein) which are at or contiguous to the site that have been utilized by the Architect of Record in the preparation of the Contract Documents. The CONTRACTOR may rely upon the accuracy of the technical data contained in such drawings, however, nontechnical data, interpretations, and opinions contained in such drawings are not to be relied on by the CONTRACTOR. The CONTRACTOR is also responsible for any interpretation, interpolation, or extrapolation that it makes of any information shown in such drawings.

4.3 DIFFERING SITE CONDITIONS

- A. The CONTRACTOR shall promptly upon discovery (but in no event later than 14 days thereafter) and before the following conditions are disturbed, notify the ARCHITECT, in writing of any:
 - 1. Material that the CONTRACTOR believes may be material that is hazardous waste, as defined in Article 1 of these General Conditions, or asbestos, PCB's, petroleum or any other substance or material posing a threat to human or to the environment.
 - 2. Subsurface or latent physical conditions at the site differing from those indicated.
 - 3. Unknown physical conditions at the site of any unusual nature, different materially from those ordinarily encountered and generally recognized as inherent in WORK of the character provided for in the contract.
- B. The ARCHITECT shall promptly investigate the conditions, and if it finds that the conditions do materially so differ, or do involve hazardous waste, and cause a decrease or increase in the CONTRACTOR's cost of, or the time required for, performance of any part of the WORK shall issue a Change Order under the procedures described in the contract.
- C. In the event that a dispute arises between the ARCHITECT and the CONTRACTOR whether the conditions materially differ, or involved hazardous waste or other materials listed above, or cause a decrease or increase in the CONTRACTOR's cost of, or time required for, performance of any part of the WORK, the CONTRACTOR shall not be excused from any scheduled completion date provided for by the contract, but shall proceed with all WORK to be performed under the contract. The CONTRACTOR shall retain any and all rights provided either by contract or by Law which pertain to the resolution of disputes and protests between the contracting parties.

4.4 PHYSICAL CONDITIONS - UNDERGROUND UTILITIES

A. Indicated. The information and data indicated in the Contract Documents with respect to existing Underground Utilities at or contiguous to the site are based on information and data furnished to the OWNER or the Architect of Record by the owners of such Underground Utilities or by others. Unless it is expressly provided in the Supplementary General Conditions and/or Section 01530 - Protection and Restoration of Existing Facilities, the OWNER and the Architect of Record shall not be responsible for the accuracy or completeness of any such information or data, and the CONTRACTOR shall have full responsibility for reviewing and checking all such information and data, for locating all Underground Utilities indicated in the Contract Documents, for coordination of

the WORK with the owners of such Underground Utilities during construction, for the safety and protection thereof and repairing any damage thereto resulting from the WORK, the cost of which will be considered as having been included in the Contract Price.

B. Not Indicated. If an Underground Utility is uncovered or revealed at or contiguous to the site which was not indicated in the Contract Documents and which the CONTRACTOR could not reasonably have been expected to be aware of, the CONTRACTOR shall identify the owner of such Underground Utility and give written notice thereof to that owner and shall notify the ARCHITECT in accordance with the requirements of the Supplementary General Conditions and Section 01530 - Protection and Restoration of Existing Facilities of the General Requirements.

4.5 REFERENCE POINTS

- A. The ARCHITECT will provide one bench mark, near or on the site of the WORK, and will provide two points near or on the site to establish a base line for use by the CONTRACTOR for alignment control. Unless otherwise specified in the General Requirements, the CONTRACTOR shall furnish all other lines, grades, and bench marks required for proper execution of the WORK.
- B. The CONTRACTOR shall preserve all bench marks, stakes, and other survey marks, and in case of their removal or destruction by its own employees or by its subcontractor's employees, the CONTRACTOR shall be responsible for the accurate replacement of such reference points by personnel qualified under the Alaska Statute governing the licensing of architects, engineers, and land surveyors.

4.6 USE OF THE CBJ/STATE LEMON CREEK GRAVEL PIT

- A. On City and Borough of Juneau (CBJ) construction projects, the CBJ may make unclassified material available to CONTRACTORs, from the CBJ/State Lemon Creek gravel pit, at a rate less than charged other customers. CONTRACTORs are not required to use material from the CBJ/State pit and the CBJ makes no guarantee as to the quantity or quality of the available material. For this Project, contact Alec Venechuk, CBJ Material Source Manager, at (907) 586-0874 for the current material rates.
- B. CONTRACTORs proposing to use gravel from the CBJ/State pit are required to be in good standing for all amounts owed to the CBJ, for previous gravel operations, prior to submitting a mining plan for approval. CONTRACTORs using the pit must comply with Allowable Use Permit USE 2008-00061. Failure to meet these requirements, if so subject, shall be sufficient reason to deny use of the CBJ/State pit as a gravel source. To determine if your company is subject to these requirements, contact the CBJ Engineering Department, Gravel Pit Management, at (907) 586-0874.
- C. CONTRACTORs deciding to use material from the CBJ/State pit shall provide an Individual Mining Plan prepared by a professional engineer registered in the State of Alaska. The Individual Mining Plan must be reviewed and approved by the CBJ, prior to commencing operations within the pit. CONTRACTORs shall also secure a Performance Bond to ensure compliance with contract provisions, including any Individual Mining Plan stipulations. The bond shall remain in full force and effect until a release is obtained from the CBJ.
- D. If CONTRACTOR operations for a Project do not exceed 500 tons of material, the CONTRACTOR will not be required to provide an Individual Mining Plan prepared by an engineer, however, the CONTRACTOR must submit an Individual Mining Plan that is in compliance with Allowable Use

Permit USE 2008-00061 for gravel extraction within the CBJ/State pit. The CONTRACTOR must contact the CBJ Engineering Department for conditions for the extraction.

- E. CONTRACTORs using the CBJ material may do primary dry separation (screening) of materials within the pit. Crushing and washing of material will not be allowed. CONTRACTORs shall account for placement of materials removed from the pit. The CBJ may require CONTRACTORs to cross-check weight tickets, submit to an audit, or participate in other measures required by the CBJ to ensure accountability. Unprocessed overburden removed from the pit will not be weighed. All other material mined will be weighed at the CBJ scale. CONTRACTORs will be responsible for loading and/or screening their own material. If asphalt pavement is removed as part of the WORK, CONTRACTORs shall dispose of the material at a to-be-specified location within the pit area, as directed by the CBJ Gravel Pit Manager, (907) 586-0874.
- F. The gravel pit overhead charge shall be paid to the CBJ by the CONTRACTOR within 60 days after removal of all materials from the pit and prior to requesting and/or receiving final payment. Upon completion of each excavation CONTRACTORs shall notify the CBJ, in writing, in sufficient time to perform a field-compliance examination prior to vacating the pit. Any significant deviation from the stipulations of the Individual Mining Plan identified during the field inspection shall be corrected by the CONTRACTOR prior to release of the bond. A signed release from CBJ will be required prior to releasing the CONTRACTOR's bond.
- G. If asphalt pavement is removed as part of this WORK, the CONTRACTOR shall dispose of the material at the location designated as the Asphalt Storage Facility, or as directed by the ARCHITECT.
- H. The CBJ/State Pit is a seasonal operation. The hours of operation are from 7:00 a.m. to 6:00 p.m., Monday through Friday, from April 1 through October 15 of the year. CONTRACTORs may obtain gravel on weekends, or during the off-season, by applying for a separate agreement with the City and Borough of Juneau Engineering Department. The CONTRACTOR will be responsible for any additional costs incurred during weekend or off-season operations at the gravel pit.
- I. All CONTRACTORs/equipment operators using the CBJ/State Pit shall be in compliance with Federal Mine Safety and Health Administration regulations for quarry and gravel operations.

ARTICLE 5 BONDS AND INSURANCE

- 5.1 PERFORMANCE, PAYMENT, AND OTHER BONDS
 - A. The CONTRACTOR shall furnish Performance and Payment Bonds, each in the amount set forth in the Supplementary General Conditions as security for the faithful performance and payment of all the CONTRACTOR's obligations under the Contract Documents. These bonds shall remain in effect at least until one year after the date of Substantial Completion except as otherwise provided by Law or Regulation or by the Contract Documents. The CONTRACTOR shall also furnish such other Bonds as are required by the Supplementary General Conditions. All Bonds shall be in the form prescribed by the Contract Documents except as provided otherwise by Laws or Regulations, and shall be executed by such sureties as are named in the current list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Audit Staff, Bureau of Government Financial Operations, U.S. Treasury Department. All Bonds signed by an agent must be accompanied by a certified copy of such agent's authority to act.

- B. If the surety on any Bond furnished by the CONTRACTOR is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the WORK is located, the CONTRACTOR shall within 7 days thereafter substitute another Bond and Surety, which must be acceptable to the OWNER.
- C. All Bonds required by the Contract Documents to be purchased and maintained by CONTRACTOR shall be obtained from surety companies that are duly licensed or authorized in the State of Alaska to issue Bonds for the limits so required. Such surety companies shall also meet such additional requirements and qualifications as may be provided in the Supplementary General Conditions.

5.2 INSURANCE

- A. The CONTRACTOR shall purchase and maintain the insurance required under this paragraph. Such insurance shall include the specific coverages set out herein and be written for not less than the limits of liability and coverages provided in the Supplementary General Conditions, or required by law, whichever are greater. All insurance shall be maintained continuously during the life of the Agreement up to the date of Final Completion and at all times thereafter when the CONTRACTOR may be correcting, removing, or replacing Defective WORK in accordance with Paragraph 13.6, but the CONTRACTOR's liabilities under this Agreement shall not be deemed limited in any way to the insurance coverage required.
- B. All insurance required by the Contract Documents to be purchased and maintained by the CONTRACTOR shall be obtained from insurance companies that are duly licensed or authorized in the State of Alaska to issue insurance policies for the limits and coverages so required. Such insurance companies shall have a current Best's Rating of at least an "A" (Excellent) general policy holder's rating and a Class VII financial size category and shall also meet such additional requirements and qualifications as may be provided in the Supplementary General Conditions.
- C. The CONTRACTOR shall furnish the OWNER with certificates showing the type, amount, class of operations covered, effective dates and dates of expiration of policies. All of the policies of insurance so required to be purchased and maintained (or the certificates or other evidence thereof) shall contain a provision or endorsement that the coverage afforded will not be cancelled, reduced in coverage, or renewal refused until at least 30 days' prior written notice has been given to the OWNER by certified mail. All such insurance required herein (except for Workers' Compensation and Employer's Liability) shall name the OWNER, its Consultants and subconsultants and their officers, directors, agents, and employees as "additional insureds" under the policies. The CONTRACTOR shall purchase and maintain the following insurance:
 - 1. Workers' Compensation and Employer's Liability. This insurance shall protect the CONTRACTOR against all claims under applicable state workers' compensation laws. The CONTRACTOR shall also be protected against claims for injury, disease, or death of employees which, for any reason, may not fall within the provisions of a Workers' Compensation law. This policy shall include an "all states" endorsement. The CONTRACTOR shall require each Subcontractor similarly to provide Workers' Compensation Insurance for all of the latter's employees to be engaged in such work unless such employees are covered by the protection afforded by the CONTRACTOR's Workers' Compensation Insurance. In case any class of employees is not protected, under the Workers' Compensation Statute, the

- CONTRACTOR shall provide and shall cause each subcontractor to provide adequate employer's liability insurance for the protection of such of its employees as are not otherwise protected.
- 2. Commercial General Liability. This insurance shall be written in comprehensive form and shall protect the CONTRACTOR against all claims arising from injuries to persons other than its employees or damage to property of the OWNER or others arising out of any act or omission of the CONTRACTOR or its agents, employees, or Subcontractors. The policy shall contain no exclusions for any operations within the scope of this contract.
- 3. Comprehensive Automobile Liability. This insurance shall be written in comprehensive form and shall protect the CONTRACTOR against all claims for injuries to members of the public and damage to property of others arising from the use of motor vehicles, and shall cover operation on or off the site of all motor vehicles licensed for highway use, whether they are owned, non-owned, or hired. Coverage for hired motor vehicles should include endorsement covering liability assumed under this contract.
- 4. Subcontractor's Public Liability and Property Damage Insurance and Vehicle Liability Insurance. The CONTRACTOR shall either require each of its Subcontractors to procure and to maintain Subcontractor's Commercial General Liability and Property Damage Insurance and Vehicle Liability Insurance of the type and in the amounts specified in the Supplementary General Conditions or insure the activities of its subcontractors in the CONTRACTOR's own policy, in like amount.
- 5. Builder's Risk. This insurance shall be of the "all risks" type, shall be written in completed value form, and shall protect the CONTRACTOR, the OWNER, and the ARCHITECT, against risks of damage to buildings, structures, and materials and equipment. The amount of such insurance shall be not less than the insurable value of the WORK at completion. Builder's risk insurance shall provide for losses to be payable to the CONTRACTOR and the OWNER, as their interests may appear. The policy shall contain a provision that in the event of payment for any loss under the coverage provided, the insurance company shall have no rights of recovery against the CONTRACTOR, the OWNER, and the ARCHITECT. The Builder's Risk policy shall insure against all risks of direct physical loss or damage to property from any external cause including flood and earthquake. Allowable exclusions, if any, shall be as specified in the Supplementary General Conditions.

ARTICLE 6 CONTRACTOR'S RESPONSIBILITIES

6.1 SUPERVISION AND SUPERINTENDENCE

- A. The CONTRACTOR shall supervise, inspect, and direct the WORK competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the WORK in accordance with the Contract Documents. The CONTRACTOR shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction and safety precautions and programs incidental thereto. The CONTRACTOR shall be responsible to see that the completed WORK complies accurately with the Contract Documents.
- B. The CONTRACTOR shall designate in writing and keep on the work site at all times during its progress a technically qualified, English-speaking superintendent, who is an employee of the CONTRACTOR and who shall not be replaced without written notice to the OWNER and the ARCHITECT. The superintendent will be the CONTRACTOR's representative at the site and shall

have authority to act on behalf of the CONTRACTOR. All communications given to the superintendent shall be as binding as if given to the CONTRACTOR. The CONTRACTOR shall issue all its communications to the OWNER through the ARCHITECT and the ARCHITECT only.

C. The CONTRACTOR's superintendent shall be present at the site of the WORK at all times while WORK is in progress. Failure to observe this requirement shall be considered suspension of the WORK by the CONTRACTOR until such time as such superintendent is again present at the site.

6.2 LABOR, MATERIALS, AND EQUIPMENT

- A. The CONTRACTOR shall provide competent, suitably qualified personnel to survey and lay out the WORK and perform construction as required by the Contract Documents. The CONTRACTOR shall furnish, erect, maintain, and remove the construction plant and any temporary works as may be required. The CONTRACTOR shall at all times maintain good discipline and order at the site. Except in connection with the safety or protection of persons or the WORK or property at the site or adjacent thereto, and except as otherwise indicated in the Contract Documents, all WORK at the site shall be performed during regular working hours, and the CONTRACTOR will not permit overtime WORK or the performance of WORK on Saturday, Sunday, or any legal holiday without the OWNER's written consent. The CONTRACTOR shall apply for this consent through the ARCHITECT.
- B. Except as otherwise provided in this Paragraph, the CONTRACTOR shall receive no additional compensation for overtime WORK, i.e., work in excess of 8 hours in any one calendar day or 40 hours in any one calendar week, even though such overtime WORK may be required under emergency conditions and may be ordered by the ARCHITECT in writing. Additional compensation will be paid the CONTRACTOR for overtime WORK only in the event extra WORK is ordered by the ARCHITECT and the Change Order specifically authorizes the use of overtime WORK and then only to such extent as overtime wages are regularly being paid by the CONTRACTOR for overtime WORK of a similar nature in the same locality.
- C. All costs of inspection and testing performed during overtime WORK by the CONTRACTOR which is allowed solely for the convenience of the CONTRACTOR shall be borne by the CONTRACTOR. The ARCHITECT shall have the authority to deduct the cost of all such inspection and testing from any partial payments otherwise due to the CONTRACTOR.
- D. Unless otherwise specified in the Contract Documents, the CONTRACTOR shall furnish and assume full responsibility for all materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, and all other facilities and incidentals necessary for the furnishing, performance, testing, start-up, and completion of the WORK.
- E. All materials and equipment to be incorporated into the WORK shall be of good quality and new, except as otherwise provided in the Contract Documents. All warranties and guarantees specifically called for by the Specifications shall expressly run to the benefit of the OWNER. If required by the ARCHITECT, the CONTRACTOR shall furnish satisfactory evidence (including reports of required tests) as to the kind and quality of materials and equipment. All materials and equipment shall be applied, installed, connected, erected, used, cleaned, and conditioned in accordance with the instructions of the applicable Supplier except as otherwise provided in the Contract Documents; but no provisions of any such instructions will be effective to assign to the ARCHITECT, or any of the Architect's of Record consultants, agents, or employees, any duty or authority to supervise or direct the

furnishing or performance of the WORK or any duty or authority to undertake responsibility contrary to the provisions of Paragraphs 9.9C and 9.9D.

- F. The CONTRACTOR shall at all times employ sufficient labor and equipment for prosecuting the several classes of WORK to full completion in the manner and time set forth in and required by these specifications. All workers shall have sufficient skill and experience to properly perform the WORK assigned to them. Workers engaged in special WORK, or skilled WORK, shall have sufficient experience in such WORK and in the operation of the equipment required to perform all WORK, properly and satisfactorily.
- G. Any person employed by the CONTRACTOR or by any SUBCONTRACTOR who, in the opinion of the ARCHITECT, does not perform the WORK in a proper and skillful manner, or is intemperate or disorderly shall, at the written request of the ARCHITECT, be removed forthwith by the CONTRACTOR or Subcontractor employing such person, and shall not be employed again in any portion of the WORK without the approval of the ARCHITECT. Should the CONTRACTOR fail to remove such person or persons as required above, or fail to furnish suitable and sufficient personnel for the proper prosecution of the WORK, the ARCHITECT may suspend the WORK by written notice until such orders are complied with.
- 6.3 ADJUSTING PROGRESS SCHEDULE. The CONTRACTOR shall submit monthly updates of the progress schedule to the ARCHITECT for acceptance in accordance with the provisions in Section 01300 CONTRACTOR Submittals in the General Requirements.
- 6.4 SUBSTITUTES OR "OR-EQUAL" ITEMS. The CONTRACTOR shall submit proposed substitutes or "or-equal" items in accordance with the provisions in Section 01300 CONTRACTOR Submittals in the General Requirements.
- 6.5 CONCERNING SUBCONTRACTORS, SUPPLIERS, AND OTHERS. The CONTRACTOR shall be responsible to the OWNER and the ARCHITECT of Record for the acts and omissions of its subcontractors and their employees to the same extent as CONTRACTOR is responsible for the acts and omissions of its own employees. Nothing contained in this Paragraph shall create any contractual relationship between any subcontractor and the OWNER or the ARCHTIECT nor relieve the CONTRACTOR of any liability or obligation under the contract.

6.6 PERMITS

- A. Unless otherwise provided in the Supplementary General Conditions, the CONTRACTOR shall obtain and pay for all construction permits and licenses from the agencies having jurisdiction, including the furnishing of insurance and Bonds if required by such agencies. The enforcement of such requirements under this contract shall not be made the basis for claims for additional compensation. The OWNER shall assist the CONTRACTOR, when necessary, in obtaining such permits and licenses. The CONTRACTOR shall pay all governmental charges and inspection fees necessary for the prosecution of the WORK, which are applicable at the time of opening of Bids. The CONTRACTOR shall pay all charges of utility owners for connections to the WORK.
- B. These Contract Documents may require that the WORK be performed within the conditions and/or requirements of local, state and/or federal permits. These permits may be bound within the Contract Documents, included within the Contract Documents by reference, or included as part of the WORK, as designated in this Section. The CONTRACTOR is responsible for completing the WORK required

for compliance with all permit requirements; this WORK is incidental to other items in the Contract Documents. Any reference to the PERMITTEE in the permits shall mean the CONTRACTOR. If any permits were acquired by the OWNER, this action was done to expedite the start of construction. If the CONTRACTOR does not complete the WORK within the specified permit window, the CONTRACTOR shall be responsible for the permit extension, and for completing any additional requirements placed upon the permit.

- ATENT FEES AND ROYALTIES. The CONTRACTOR shall pay all license fees and royalties and assume all costs incident to the use in the performance of the WORK or the incorporation in the WORK of any invention, design, process, product, software or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the WORK and if to the actual knowledge of the OWNER or the Architect of Record its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by the OWNER in the Contract Documents. The CONTRACTOR shall indemnify, defend and hold harmless the OWNER and the Architect of Record and anyone directly or indirectly employed by either of them from and against all claims, damages, losses, and expenses (including attorneys' fees and court costs) arising out of any infringement of patent rights or copyrights incident to the use in the performance of the WORK or resulting from the incorporation in the WORK of any invention, design, process, product, or device not specified in the Contract Documents, and shall defend all such claims in connection with any alleged infringement of such rights.
- 6.8 LAWS AND REGULATIONS. The CONTRACTOR shall observe and comply with all federal, state, and local laws, ordinances, codes, orders, and regulations which in any manner affect those engaged or employed on the WORK, the materials used in the WORK, or the conduct of the WORK. If any discrepancy or inconsistency should be discovered in this contract in relation to any such law, ordinance, code, order, or regulation, the CONTRACTOR shall report the same in writing to the ARCHITECT. The CONTRACTOR shall indemnify, defend, and hold harmless the OWNER, the Architect of Record, and their officers, agents, and employees against all claims or liability arising from violation of any such law, ordinance, code, order, or regulation, whether by CONTRACTOR or by its employees, Subcontractors, or third parties. Any particular law or regulation specified or referred to elsewhere in the Contract Documents shall not in any way limit the obligation of the CONTRACTOR to comply with all other provisions of federal, state, and local laws and regulations.
- 6.9 TAXES. The CONTRACTOR shall pay all sales, consumer, use, and other similar taxes required to be paid by the CONTRACTOR in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the WORK.
- 6.10 USE OF PREMISES. The CONTRACTOR shall confine construction equipment, the storage of materials and equipment, and the operations of workers to (1) the Project site, (2) the land and areas identified in and permitted by the Contract Documents, and (3) the other land and areas permitted by Laws and Regulations, rights-of-way, permits, leases and easements. The CONTRACTOR shall assume full responsibility for any damage to any such land or area, or to the owner or occupant thereof or of any land or areas contiguous thereto, resulting from the performance of the WORK. Should any claim be made against the OWNER or the Architect of Record by any such owner or occupant because of the performance of the WORK, the CONTRACTOR shall promptly attempt to settle with such other party by agreement or otherwise resolve the claim through litigation. The CONTRACTOR shall, to the fullest extent permitted by Laws and Regulations, indemnify, defend, and hold the OWNER and the Architect of Record harmless from and against all claims, damages, losses, and

expenses (including, but not limited to, fees of Architect's of Records attorneys, and other professionals and court costs) arising directly, indirectly, or consequentially out of any action, legal or equitable, brought by any such owner or occupant against the OWNER, the Architect of Record, their consultants, sub-consultants, and the officers, directors, employees and agents of each and any of them to the extent caused by or based upon the CONTRACTOR's performance of the WORK.

6.11 SAFETY AND PROTECTION

- A. The CONTRACTOR shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the WORK. The CONTRACTOR shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:
 - 1. all employees on the WORK and other persons and organizations who may be affected thereby;
 - 2. all the WORK and materials and equipment to be incorporated therein, whether in storage on or off the site; and
 - 3. other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.
- B. The CONTRACTOR shall comply with all applicable Laws and Regulations whether referred to herein or not) of any public body having jurisdiction for the safety of persons or property or to protect them from damage, injury, or loss and shall erect and maintain all necessary safeguards for such safety and protection. The CONTRACTOR shall notify owners of adjacent property and utilities when prosecution of the WORK may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property.
- C. The CONTRACTOR shall designate a qualified and experienced safety representative at the site whose duties and responsibilities shall be the prevention of accidents and the maintaining and supervising of safety precautions and program.
- D. Materials that contain hazardous substances or mixtures may be required on the WORK. A Material Safety Data Sheet (MSDS) shall be requested by the CONTRACTOR from the manufacturer of any hazardous product used.
- E. Material usage shall be accomplished with strict adherence to all safety requirements and all manufacturer's warnings and application instructions listed on the Material Safety Data Sheet and on the product container label.
- F. The CONTRACTOR shall be responsible for coordinating communications on any exchange of Material Safety Data Sheets or other hazardous material information that is required to be made available to, or exchanged between, or among, employers at the site in accordance with Laws or Regulations.
- G. The CONTRACTOR shall notify the ARCHITECT if it considers a specified product or its intended usage to be unsafe. This notification must be given to the ARCHITECT prior to the product being ordered, or if provided by some other party, prior to the product being incorporated in the WORK.

6.12 SHOP DRAWINGS AND SAMPLES

- A. After checking and verifying all field measurements and after complying with applicable procedures specified in the General Requirements, the CONTRACTOR shall submit to the ARCHITECT for review, all Shop Drawings in accordance with Section 01300 CONTRACTOR Submittals in the General Requirements.
- B. The CONTRACTOR shall also submit to the ARCHITECT for review all samples in accordance with Section 01300 CONTRACTOR Submittals in the General Requirements.
- C. Before submittal of each Shop Drawing or sample, the CONTRACTOR shall have determined and verified all quantities, dimensions, specified performance criteria, installation requirements, materials, catalog numbers, and similar data with respect thereto and reviewed or coordinated each Shop Drawing or sample with other Shop Drawings and samples and with the requirements of the WORK and the Contract Documents.
- 6.13 CONTINUING THE WORK. The CONTRACTOR shall carry on the WORK and adhere to the progress schedule during all disputes or disagreements with the OWNER. No WORK shall be delayed or postponed pending resolution of any disputes or disagreements, except as the CONTRACTOR and the OWNER may otherwise agree in writing.

6.14 INDEMNIFICATION

- A. To the fullest extent permitted by Laws and Regulations, the CONTRACTOR shall indemnify, defend, and hold harmless the OWNER, the Architect of Record, their consultants, sub-consultants and the officers, directors, employees, and agents of each and any of them, against and from all claims and liability arising under, by reason of or incidentally to the contract or any performance of the WORK, but not from the sole negligence or willful misconduct of the OWNER, and the Architect of Record. Such indemnification by the CONTRACTOR shall include but not be limited to the following:
 - Liability or claims resulting directly or indirectly from the negligence or carelessness of the CONTRACTOR, its employees, or agents in the performance of the WORK, or in guarding or maintaining the same, or from any improper materials, implements, or appliances used in its construction, or by or on account of any act or omission of the CONTRACTOR, its employees, agents, or third parties;
 - 2. Liability or claims arising directly or indirectly from bodily injury, occupational sickness or disease, or death of the CONTRACTOR's or Subcontractor's own employees engaged in the WORK resulting in actions brought by or on behalf of such employees against the OWNER, or the Architect of Record;
 - Liability or claims arising directly or indirectly from or based on the violation of any law, ordinance, regulation, order, or decree, whether by the CONTRACTOR, its employees, or agents;
 - 4. Liability or claims arising directly or indirectly from the use or manufacture by the CONTRACTOR, its employees, or agents in the performance of this contract of any copyrighted or non-copyrighted composition, secret process, patented or non-patented invention, computer software, article, or appliance, unless otherwise specifically stipulated in this contract.

- 5. Liability or claims arising directly or indirectly from the breach of any warranties, whether express or implied, made to the ARCHITECT, OWNER or any other parties by the CONTRACTOR, its employees, or agents;
- 6. Liabilities or claims arising directly or indirectly from the willful or criminal misconduct of the CONTRACTOR, its employees, or agents; and,
- 7. Liabilities or claims arising directly or indirectly from any breach of the obligations assumed herein by the CONTRACTOR.
- B. The CONTRACTOR shall reimburse the OWNER and the Architect of Record for all costs and expenses, (including but not limited to fees and charges of Architects of Record, attorneys, and other professionals and court costs including all costs of appeals) incurred by the OWNER, and the Architect of Record in enforcing the provisions of this Paragraph 6.14.
- C. The indemnification obligation under this Paragraph 6.14 shall not be limited in any way by any limitation of the amount or type of damages, compensation, or benefits payable by or for the CONTRACTOR or any such Subcontractor or other person or organization under workers' compensation acts, disability benefit acts, or other employee benefit acts.
- 6.15 CONTRACTOR'S DAILY REPORTS. The CONTRACTOR shall complete a daily report indicating total manpower for each construction trade, major equipment on site, each Subcontractor's manpower, weather conditions, etc., involved in the performance of the WORK. The daily report shall be completed on forms provided by the ARCHITECT and shall be submitted to the ARCHITECT at the conclusion of each WORK day. The report should comment on the daily progress and status of the WORK within each major component of the WORK. These components will be decided by the ARCHITECT. The CONTRACTOR shall record the name, affiliation, time of arrival and departure, and reason for visit for all visitors to the location of the WORK.
- 6.16 ASSIGNMENT OF CONTRACT. The CONTRACTOR shall not assign, sublet, sell, transfer, or otherwise dispose of the contract or any portion thereof, or its right, title, or interest therein, or obligations thereunder, without the written consent of the OWNER except as imposed by law. If the CONTRACTOR violates this provision, the contract may be terminated at the option of the OWNER. In such event, the OWNER shall be relieved of all liability and obligations to the CONTRACTOR and to its assignee or transferee, growing out of such termination.
- 6.17 CONTRACTOR'S RESPONSIBILITY FOR UTILITY PROPERTY AND SERVICES. It is understood that any turn-on, or turn-off line locates and any other WORK or assistance necessary by the CBJ Water Utilities Division, will be at the CONTRACTOR's expense unless otherwise stated in the bid documents. All cost must be agreed to prior to any related actions, and will be considered incidental to the Project cost. Billing to the CONTRACTOR will be direct from the CBJ Water Utilities Division.

6.18 OPERATING WATER SYSTEM VALVES

A. The CONTRACTOR shall submit a written request, to the ARCHITECT, for approval to operate any valve on any in-service section of the CBJ water system. The request must be submitted at least 24-hours prior to operating any valves. The CBJ Water Utilities Division reserves the right to approve or deny the request. The request shall specifically identify each valve to be operated, the time of operation, and the operation to be performed. The CONTRACTOR shall obtain the written approval of the ARCHITECT for any scheduled operation before operating any valve.

- B. The CONTRACTOR shall be responsible for all damages, both direct and consequential, to the OWNER or any other party, caused by unauthorized operation of any valve of the CBJ water system.
- 6.19 CONTRACTOR'S WORK SCHEDULE LIMITATIONS. Construction of Buildings and Projects. It is unlawful to operate any pile driver, power shovel, pneumatic hammer, derrick, power hoist, or similar heavy construction equipment before 7:00 a.m. or after 10:00 p.m., Monday through Friday, or before 9:00 a.m. or after 10:00 p.m., Saturday and Sunday, unless a permit shall first be obtained from the City and Borough Building Official. Such permit shall be issued by the Building Official only upon a determination that such operation during hours not otherwise permitted hereunder is necessary and will not result in unreasonable disturbance to surrounding residents.

ARTICLE 7 OTHER WORK

7.1 RELATED WORK AT SITE

- A. The OWNER may perform other work related to the Project at the site by the OWNER's own forces, have other work performed by utility owners, or let other direct contracts therefor which may contain General Conditions similar to these. If the fact that such other work is to be performed was not noted in the Contract Documents, written notice thereof will be given to the CONTRACTOR prior to starting any such other work.
- B. The CONTRACTOR shall afford each other contractor who is a party to such a direct contract and each utility owner (or the OWNER, if the OWNER is performing the additional work with the OWNER's employees) proper and safe access to the site and a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such work, and shall properly connect and coordinate with their WORK. The CONTRACTOR shall do all cutting, fitting, and patching of the WORK that may be required to make its several parts come together properly and integrate with such other work. The CONTRACTOR shall not endanger any work of others by cutting, excavating, or otherwise altering their work and will only cut or alter their work with the written consent of the ARCHITECT and the others whose work will be affected.
- C. If the proper execution or results of any part of the CONTRACTOR's WORK depends upon the work of any such other contractor or utility owner (or OWNER), the CONTRACTOR shall inspect and report to the ARCHITECT in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for such proper execution and results. The CONTRACTOR's failure to report such delays, defects, or deficiencies will constitute an acceptance of the other work as fit and proper for integration with the CONTRACTOR's WORK except for latent or nonapparent defects and deficiencies in the other work.
- 7.2 COORDINATION. If the OWNER contracts with others for the performance of other work on the Project at the site, the person or organization who will have authority and responsibility for coordination of the activities among the various prime contractors will be identified in the Supplementary General Conditions, and the specific matters to be covered by such authority and responsibility will be itemized and the extent of such authority and responsibilities will be provided in the Supplementary General Conditions.

ARTICLE 8 OWNER'S RESPONSIBILITIES

- 8.1 COMMUNICATIONS
 - A. The OWNER shall issue all its communications to the CONTRACTOR through the ARCHITECT.
 - B. The CONTRACTOR shall issue all its communications to the OWNER through the ARCHITECT.
- 8.2 PAYMENTS. The OWNER shall make payments to the CONTRACTOR as provided in Paragraphs 14.5, 14.8, 14.9 and 14.10.
- 8.3 LANDS, EASEMENTS, AND SURVEYS. The OWNER's duties in respect of providing lands and easements and providing surveys to establish reference points are set forth in Paragraphs 4.1 and 4.5.
- 8.4 CHANGE ORDERS. The OWNER shall execute Change Orders as indicated in Paragraph 10.1F.
- 8.5 INSPECTIONS AND TESTS. The OWNER's responsibility in respect of inspections, tests, and approvals is set forth in Paragraph 13.3.
- 8.6 SUSPENSION OF WORK. In connection with the OWNER's right to stop WORK or suspend WORK, see Paragraphs 13.4 and 15.1.
- 8.7 TERMINATION OF AGREEMENT. Paragraphs 15.2 and 15.3 deal with the OWNER's right to terminate services of the CONTRACTOR.

ARTICLE 9 ARCHITECT'S STATUS DURING CONSTRUCTION

- 9.1 OWNER'S REPRESENTATIVE. The ARCHITECT will be the OWNER's representative during the construction period. The duties and responsibilities and the limitations of authority of the ARCHITECT as the OWNER's representative during construction are set forth in the Contract Documents.
- 9.2 VISITS TO SITE. The ARCHITECT will make visits to the site during construction to observe the progress and quality of the WORK and to determine, in general, if the WORK is proceeding in accordance with the Contract Documents. Exhaustive or continuous on-site inspections to check the quality or quantity of the WORK will not be required of the ARCHITECT. The ARCHITECT will not, during such visits, or as a result of such observations of the CONTRACTOR's WORK in progress, supervise, direct, or have control over the CONTRACTOR's WORK.
- 9.3 PROJECT REPRESENTATION. The ARCHITECT may furnish an Inspector to assist in observing the performance of the WORK. The duties, responsibilities, and limitations of authority of any such Inspector and assistants will be as provided in the Supplementary General Conditions.
- 9.4 CLARIFICATIONS AND INTERPRETATIONS. The ARCHITECT will issue with reasonable promptness such written clarifications or interpretations of the requirements of the Contract Documents (in the form of Drawings or otherwise) as the ARCHITECT may determine necessary, which shall be consistent with or reasonably inferable from the overall intent of the Contract Documents.

- 9.5 AUTHORIZED VARIATIONS IN WORK. The ARCHITECT may authorize variations in the WORK from the requirements of the Contract Documents. These may be accomplished by a Field Order and will require the CONTRACTOR to perform the WORK involved in a manner that minimizes the impact to the WORK and the contract completion date. If the CONTRACTOR believes that a Field Order justifies an increase in the Contract Price or an extension of the Contract Time, the CONTRACTOR may make a claim therefor as provided in Article 11 or 12.
- 9.6 REJECTING OR ACCEPTING DEFECTIVE WORK. The ARCHITECT will have authority to reject or accept WORK which the ARCHITECT believes to be defective and will also have authority to require special inspection or testing of the WORK as provided in Paragraph 13.3G, whether or not the WORK is fabricated, installed, or completed.

9.7 CONTRACTOR SUBMITTALS, CHANGE ORDERS, AND PAYMENTS

- A. In accordance with the procedures set forth in the General Requirements, the ARCHITECT will review all CONTRACTOR submittals, including Shop Drawings, samples, substitutes, or "or equal" items, etc., in order to determine if the items covered by the submittals will, after installation or incorporation in the WORK, conform to the requirements of the Contract Documents and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. The ARCHITECT's review will not extend to means, methods, techniques, sequences or procedures of construction or to safety precautions or programs incident thereto.
- B. In connection with the ARCHITECT's responsibilities as to Change Orders, see Articles 10, 11, and 12.
- C. In connection with the ARCHITECT's responsibilities in respect of Applications for Payment, see Article 14.

9.8 DECISIONS ON DISPUTES

- A. The ARCHITECT will be the initial interpreter of the requirements of the Contract Documents and judge of the acceptability of the WORK thereunder. Claims, disputes, and other matters relating to the acceptability of the WORK; the interpretation of the requirements of the Contract Documents pertaining to the performance of the WORK; and those claims under Articles 11 and 12 in respect to changes in the Contract Price or Contract Time will be referred initially to the ARCHITECT in writing with a request for formal decision in accordance with this paragraph, which the ARCHITECT will render in writing within 30 days of receipt of the request. Written notice of each such claim, dispute, and other matter will be delivered by the CONTRACTOR to the ARCHITECT promptly (but in no event later than 30 days) after the occurrence of the event giving rise thereto. Written supporting data will be submitted to the ARCHITECT within 60 days after such occurrence unless the ARCHITECT allows an additional period of time to ascertain more accurate data in support of the claim.
- B. The rendering of a decision by the ARCHITECT with respect to any such claim, dispute, or other matter (except any which have been waived by the making or acceptance of final payment as provided in Paragraph 14.12) will be a condition precedent to any exercise by the OWNER or the CONTRACTOR of such rights or remedies as either may otherwise have under the Contract Documents or by Law or Regulations in respect of any such claim, dispute, or other matter.

9.9 LIMITATION ON ARCHITECT'S RESPONSIBILITIES

- A. Neither the ARCHITECT's authority to act under this Article or other provisions of the Contract Documents nor any decision made by the ARCHITECT in good faith either to exercise or not exercise such authority shall give rise to any duty or responsibility of the ARCHITECT to the CONTRACTOR, any Subcontractor, any Supplier, any surety for any of them, or any other person or organization performing any of the WORK.
- B. Whenever in the Contract Documents the terms "as ordered," "as directed," "as required," "as allowed," "as reviewed," "as approved," or terms of like effect or import are used, or the adjectives "reasonable," "suitable," "acceptable," "proper," or "satisfactory" or adjectives of like effect or import are used to describe a requirement, direction, review, or judgment of the ARCHITECT as to the WORK, it is intended that such requirement, direction, review, or judgment will be solely to evaluate the WORK for compliance with the requirements of the Contract Documents, and conformance with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents, unless there is a specific statement indicating otherwise. The use of any such term or adjective shall not be effective to assign to the ARCHITECT any duty or authority to supervise or direct the performance of the WORK or any duty or authority to undertake responsibility contrary to the provisions of Paragraph 9.9C or 9.9D.
- C. The ARCHITECT will not supervise, direct, control, or have authority over or be responsible for the CONTRACTOR's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of the CONTRACTOR to comply with Laws and Regulations, applicable to the performance of the WORK. The ARCHITECT will not be responsible for the CONTRACTOR's failure to perform the WORK in accordance with the Contract Documents.
- D. The ARCHITECT will not be responsible for the acts or omissions of the CONTRACTOR nor of any Subcontractor, Supplier, or any other person or organization performing any of the WORK.

ARTICLE 10 CHANGES IN THE WORK

10.1 GENERAL

- A. Without invalidating the Agreement and without notice to any surety, the OWNER may at any time or from time to time, order additions, deletions, or revisions in the WORK; these will be authorized by a written Field Order and/or a Change Order issued by the ARCHITECT.
- B. If the CONTRACTOR believes that it is entitled to an increase or decrease in the Contract Price, or an extension or shortening in the Contract Time as the result of a Field Order, a claim may be made as provided in Articles 11 and 12.
- C. If the OWNER and CONTRACTOR agree on the value of any WORK, or the amount of Contract Time that should be allowed as a result of a Field Order, upon receiving written notice from the ARCHITECT, the CONTRACTOR shall proceed so as to minimize the impact on and delays to the WORK pending the issuance of a Change Order.
- D. If the OWNER and the CONTRACTOR are unable to agree as to the extent, if any, of an increase or decrease in the Contract Price or an extension or shortening of the Contract Time that should be

allowed as a result of a Field Order, the ARCHITECT can direct the CONTRACTOR to proceed on the basis of Time and Materials so as to minimize the impact on and delays to the WORK, and a claim may be made therefor as provided in Articles 11 and 12.

- E. The CONTRACTOR shall not be entitled to an increase in the Contract Price nor an extension of the Contract Time with respect to any WORK performed that is not required by the Contract Documents as amended, modified, supplemented by Change Order, except in the case of an emergency and except in the case of uncovering WORK as provided in Paragraph 13.3G.
- F. The OWNER and the CONTRACTOR shall execute appropriate Change Orders covering:
 - 1. changes in the WORK which are ordered by the OWNER pursuant to Paragraph 10.1A;
 - 2. changes required because of acceptance of Defective WORK under Paragraph 13.7;
 - 3. changes in the Contract Price or Contract Time which are agreed to by the parties; or
 - 4. changes in the Contract Price or Contract Time which embody the substance of any written decision rendered by the ARCHITECT pursuant to Paragraph 9.8.
- G. If notice of any change is required by the provisions of any Bond to be given to a surety, the giving of any such notice will be the CONTRACTOR's responsibility, and the amount of each applicable Bond shall be adjusted accordingly.

10.2 ALLOWABLE QUANTITY VARIATIONS

- A. In the event of an increase or decrease in bid item quantity of a unit price contract, the total amount of WORK actually done or materials or equipment furnished shall be paid for according to the unit price established for such WORK under the Contract Documents, wherever such unit price has been established; provided, that an adjustment in the Contract Price may be made for changes which result in an increase or decrease in excess of 25% of the estimated quantity of any major item of the WORK. Major Item is defined as any bid item amount that is ten percent (10%) or more of the total contract amount.
- B. In the event a part of the WORK is to be entirely eliminated and no lump sum or unit price is named in the Contract Documents to cover such eliminated WORK, the price of the eliminated WORK shall be agreed upon in writing by the OWNER and the CONTRACTOR. If the OWNER and the CONTRACTOR fail to agree upon the price of the eliminated WORK, said price shall be determined in accordance with the provisions of Article 11.

ARTICLE 11 CHANGE OF CONTRACT PRICE

11.1 GENERAL

- A. The Contract Price constitutes the total compensation payable to the CONTRACTOR for performing the WORK. All duties, responsibilities, and obligations assigned to or undertaken by the CONTRACTOR to complete the WORK shall be at its expense without change in the Contract Price.
- B. The Contract Price may only be changed by a Change Order. Any claim for an increase in the Contract Price shall be based on written notice delivered by the CONTRACTOR to the ARCHITECT promptly (but in no event later than 30 days) after the start of the occurrence or the event giving rise to the claim

and stating the general nature of the claim. Notice of the amount of the claim with supporting data shall be delivered within 60 days after such occurrence (unless the ARCHITECT allows an additional period of time to ascertain more accurate data in support of the claim) and shall be accompanied by the CONTRACTOR's written statement that the amount claimed covers all known amounts (direct, indirect, and consequential) to which the CONTRACTOR is entitled as a result of said occurrence or event. All claims for adjustment in the Contract Price shall be determined by the ARCHITECT in accordance with Paragraph 9.8A if the OWNER and the CONTRACTOR cannot otherwise agree on the amount involved. No claim for an adjustment in the Contract Price will be valid if not submitted in accordance with this Paragraph 11.1B.

- C. The value of any WORK covered by a Change Order or of any claim for an increase or decrease in the Contract Price shall be determined in one of the following ways:
 - 1. Where the WORK involved is covered by unit prices contained in the Contract Documents, by application of unit prices to the quantities of the items involved.
 - 2. By mutual acceptance of a lump sum, which may include an allowance for overhead and profit not necessarily in accordance with Paragraph 11.4.
 - 3. On the basis of the "Cost of WORK" (determined as provided in Paragraphs 11.3) plus a CONTRACTOR's fee for overhead and profit (determined as provided in Paragraph 11.4).
- 11.2 COSTS RELATING TO WEATHER. The CONTRACTOR shall have no claims against the OWNER for damages for any injury to WORK, materials, or equipment, resulting from the action of the elements. If, however, in the opinion of the ARCHITECT, the CONTRACTOR has made all reasonable efforts to protect the materials, equipment and WORK, the CONTRACTOR may be granted a reasonable extension of Contract Time to make proper repairs, renewals, and replacements of the WORK, materials, or equipment.
- 11.3 COST OF WORK (BASED ON TIME AND MATERIALS)
 - A. General. The term "Cost of WORK" means the sum of all costs necessarily incurred and paid by the CONTRACTOR for labor, materials, and equipment in the proper performance of extra WORK. Except as otherwise may be agreed to in writing by the OWNER, such costs shall be in amounts no higher than those prevailing in the locality of the Project; shall include only the following items, and shall not include any of the costs itemized in Paragraph 11.5 EXCLUDED COSTS.
 - B. Labor. The costs of labor will be the actual cost for wages prevailing for each craft or type of workers performing the extra WORK at the time the extra WORK is done, plus employer payments of payroll taxes, worker's compensation insurance, liability insurance, health and welfare, pension, vacation, apprenticeship funds, and other direct costs resulting from Federal, State or local laws, as well as assessments or benefits required by lawful collective bargaining agreements. Labor costs for equipment operators and helpers shall be paid only when such costs are not included in the invoice for equipment rental. The labor costs for forepersons shall be proportioned to all of their assigned WORK and only that applicable to extra WORK shall be paid. Non-direct labor costs including superintendence shall be considered part of the mark-up set out in paragraph 11.4.
 - C. Materials. The cost of materials reported shall be at invoice or lowest current price at which materials are locally available and delivered to the job in the quantities involved, plus the cost of freight, delivery and storage, subject to the following:

- 1. Trade discounts available to the purchaser shall be credited to the OWNER notwithstanding the fact that such discounts may not have been taken by the CONTRACTOR.
- 2. For materials secured by other than a direct purchase and direct billing to the purchaser, the cost shall be deemed to be the price paid to the actual supplier as determined by the ARCHITECT. Mark-up except for actual costs incurred in the handling of such materials will not be allowed.
- 3. Payment for materials from sources owned wholly or in part by the purchaser shall not exceed the price paid by the purchaser for similar materials from said sources on extra WORK items or the current wholesale price for such materials delivered to the WORK site, whichever price is lower
- 4. If in the opinion of the ARCHITECT the cost of material is excessive, or the CONTRACTOR does not furnish satisfactory evidence of the cost of such material, then the cost shall be deemed to be the lowest current wholesale price for the quantity concerned delivered to the WORK site less trade discount. The OWNER reserves the right to furnish materials for the extra WORK and no claim shall be allowed by the CONTRACTOR for costs and profit on such materials.
- D. Equipment. The CONTRACTOR will be paid for the use of equipment at the rental rate listed for such equipment specified in the Supplementary General Conditions. Such rental rate will be used to compute payments for equipment whether the equipment is under the CONTRACTOR's control through direct ownership, leasing, renting, or another method of acquisition. The rental rate to be applied for use of each item of equipment shall be the rate resulting in the least total cost to the OWNER for the total period of use. If it is deemed necessary by the CONTRACTOR to use equipment not listed in the publication specified in the Supplementary General Conditions, an equitable rental rate for the equipment will be established by the ARCHITECT. The CONTRACTOR may furnish cost data which might assist the ARCHITECT in the establishment of the rental rate.
 - 1. All equipment shall, in the opinion of the ARCHITECT, be in good working condition and suitable for the purpose for which the equipment is to be used.
 - 2. Before construction equipment is used on the extra WORK, the CONTRACTOR shall plainly stencil or stamp an identifying number thereon at a conspicuous location, and shall furnish to the ARCHITECT, in duplicate, a description of the equipment and its identifying number.
 - 3. Unless otherwise specified, manufacturer's ratings and manufacturer approved modifications shall be used to classify equipment for the determination of applicable rental rates. Equipment which has no direct power unit shall be powered by a unit of at least the minimum rating recommended by the manufacturer.
 - 4. Individual pieces of equipment or tools having a replacement value of \$200 or less, whether or not consumed by use, shall be considered to be small tools and no payment will be made therefor.
 - 5. Rental time will not be allowed while equipment is inoperative due to breakdowns.
 - 6. <u>Equipment</u>. Unless otherwise agreed to in writing, the CONTRACTOR will be paid for the use of equipment at the rental rate listed for such equipment specified in the current edition of the following reference publication: "Rental Rate Blue Book" available on-line at http://www.equipmentwatch.com/rrbb.htm or contact Equipment Watch at (800) 669-3282.
- E. Equipment on the WORK Site. The rental time to be paid for equipment on the WORK site shall be the time the equipment is in productive operation on the extra WORK being performed and, in addition, shall include the time required to move the equipment to the location of the extra WORK and return it to the original location or to another location requiring no more time than that required to return it to its original location; except, that moving time will not be paid if the equipment is used on other than the extra WORK, even though located at the site of the extra WORK. Loading and

transporting costs will be allowed, in lieu of moving time, when the equipment is moved by means other than its own power, except that no payment will be made for loading and transporting costs when the equipment is used at the site of the extra WORK on other than the extra WORK. The following shall be used in computing the rental time of equipment on the WORK site.

- 1. When hourly rates are listed, any part of an hour less than 30 minutes of operation shall be considered to be 1/2-hour of operation, and any part of an hour in excess of 30 minutes will be considered one hour of operation.
- 2. When daily rates are listed, any part of a day less than 4 hours operation shall be considered to be 1/2-day of operation. When owner-operated equipment is used to perform extra WORK to be paid for on a time and materials basis, the CONTRACTOR will be paid for the equipment and operator, as set forth in Paragraphs (3), (4), and (5), following.
- 3. Payment for the equipment will be made in accordance with the provisions in Paragraph 11.3D, herein.
- 4. Payment for the cost of labor and subsistence or travel allowance will be made at the rates paid by the CONTRACTOR to other workers operating similar equipment already on the WORK site, or in the absence of such labor, established by collective bargaining agreements for the type of worker and location of the extra WORK, whether or not the operator is actually covered by such an agreement. A labor surcharge will be added to the cost of labor described herein in accordance with the provisions of Paragraph 11.3B, herein, which surcharge shall constitute full compensation for payments imposed by state and federal laws and all other payments made to or on behalf of workers other than actual wages.
- 5. To the direct cost of equipment rental and labor, computed as provided herein, will be added the allowances for equipment rental and labor as provided in Paragraph 11.4, herein.
- F. Specialty WORK. Specialty WORK is defined as that WORK characterized by extraordinary complexity, sophistication, or innovation or a combination of the foregoing attributes which are unique to the construction industry. The following shall apply in making estimates for payment for specialty WORK:
 - Any bid item of WORK to be classified as Specialty WORK shall be listed as such in the Supplementary General Conditions. Specialty WORK shall be performed by an entity especially skilled in the work to be performed. After validation of invoices and determination of market values by the ARCHITECT, invoices for Specialty WORK based upon the current fair market value thereof may be accepted without complete itemization of labor, material, and equipment rental costs.
 - When the CONTRACTOR is required to perform WORK necessitating special fabrication or machining process in a fabrication or a machine shop facility away from the job site, the charges for that portion of the WORK performed at the off-site facility may, by agreement, be accepted as Specialty WORK and accordingly, the invoices for the WORK may be accepted without detailed itemization.
 - 3. All invoices for specialty WORK will be adjusted by deducting all trade discounts offered or available, whether the discounts were taken or not. In lieu of the allowances for overhead and profit specified in Paragraph 11.4, herein, an allowance of 5 percent will be added to invoices for specialty WORK.
- G. Sureties. All WORK performed hereunder shall be subject to all of the provisions of the Contract Documents and the CONTRACTOR's sureties shall be bound with reference thereto as under the

original Agreement. Copies of all amendments to surety Bonds or supplemental surety Bonds shall be submitted to the OWNER for review prior to the performance of any WORK hereunder.

11.4 CONTRACTOR'S FEE

A. Extra WORK ordered on the basis of time and materials will be paid for at the actual necessary cost as determined by the ARCHITECT, plus allowances for overhead and profit. The allowance for overhead and profit shall include full compensation for superintendence, Bond and insurance premiums, taxes, field office expense, extended overhead, home office overhead, and all other items of expense or cost not included in the cost of labor, materials, or equipment provided for under Paragraph 11.3. The allowance for overhead and profit will be made in accordance with the following schedule:

Actual Overhead and Profit Allowance

Labor1	5	percent
Materials1	0	percent
Equipment1	0	percent

To the sum of the costs and mark-ups provided for in this Article, one (1) percent shall be added as compensation for Bonds.

B. It is understood that labor, materials, and equipment may be furnished by the CONTRACTOR or by the Subcontractor on behalf of the CONTRACTOR. When all or any part of the extra WORK is performed by a Subcontractor, the allowance specified herein shall be applied to the labor, materials, and equipment costs of the Subcontractor, to which the CONTRACTOR may add five (5) percent of the Subcontractor's total cost for the extra WORK. Regardless of the number of hierarchical tiers of Subcontractors, the five (5) percent increase above the Subcontractor's total cost which includes the allowances for overhead and profit specified herein may be applied one time only.

11.5 EXCLUDED COSTS.

- A. The term "Cost of the WORK" shall not include any of the following:
 - 1. Payroll costs and other compensation of CONTRACTOR's officers, executives, principals (of partnership and sole proprietorships), general managers, architects, estimators, attorneys' auditors, accountants, purchasing and contracting agents, expenditures, timekeepers, clerks and other personnel employed by CONTRACTOR whether at the site or in CONTRACTOR's principal or a branch office for general administration of the WORK, or not specifically covered by paragraph 11.3, all of which are to be considered administrative costs covered by the CONTRACTOR's fee.
 - 2. Expenses of CONTRACTOR's principal and branch offices other than CONTRACTOR's office at the site
 - 3. Any part of CONTRACTOR's capital expenses, including interest on CONTRACTOR's capital employed for the WORK and charges against CONTRACTOR for delinquent payments.
 - 4. Cost of premiums for all Bonds and for all insurance whether or not CONTRACTOR is required by the Contract Documents to purchase and maintain the same (except for the cost of premiums covered by paragraph 11.4 above).
 - 5. Costs due to the negligence of CONTRACTOR, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but

- not limited to, the correction of Defective WORK, disposal of materials or equipment wrongly supplied and making good any damage to property.
- 6. Other overhead or general expense costs of any kind and the cost of any item not specifically and expressly included in paragraph 11.4.

ARTICLE 12 CHANGE OF CONTRACT TIME

12.1 GENERAL

- A. The Contract Time may only be changed by a Change Order. Any claim for an extension of the Contract Time (or Milestones) shall be based on written notice delivered by the CONTRACTOR to the ARCHITECT promptly (but in no event later than 30 days) after the occurrence of the event giving rise to the claim and stating the general nature of the claim. Notice of the extent of the claim with supporting data shall be delivered within 60 days after such occurrence (unless the ARCHITECT allows an additional period of time to ascertain more accurate data in support of the claim) and shall be accompanied by the CONTRACTOR's written statement that the adjustment claimed is the entire adjustment to which the CONTRACTOR has reason to believe it is entitled as a result of the occurrence of said event. All claims for adjustment in the Contract Time shall be determined by the ARCHITECT in accordance with Paragraph 9.8 if the OWNER and the CONTRACTOR cannot otherwise agree. No claim for an adjustment in the Contract Time will be valid if not submitted in accordance with the requirements of this paragraph. An increase in Contract Time does not mean that the CONTRACTOR is due an increase in Contract Price. Only Compensable time extensions will result in an increase in Contract Price.
- B. All time limits stated in the Contract Documents are of the essence of the Agreement.
- C. Where CONTRACTOR is prevented from completing any part of the WORK within the Contract Times (or Milestones) due to delay beyond the control of CONTRACTOR, the Contract Times (or Milestones) will be extended in an amount equal to the time lost on the critical path of the Project due to such delay if a claim is made therefor as provided in paragraph 12.1. Delays beyond the control of CONTRACTOR shall include, but not be limited to, acts or neglect by OWNER, acts or neglect of utility owners or other contractors performing other work as contemplated by Article 7, fires, floods, epidemics, unprecedented weather conditions or acts of God. Delays attributable to and within the control of a Subcontractor or Supplier shall be deemed to be delays within the control of CONTRACTOR.
- D. Where CONTRACTOR is prevented from completing any part of the WORK within the Contract Times (or Milestones) due to delay beyond the control of both OWNER and CONTRACTOR, an extension of the Contract Times (or Milestones) in an amount equal to the time lost on the critical path of the Project due to such delay shall be CONTRACTOR's sole and exclusive remedy for such delay. In no event shall the OWNER be liable to CONTRACTOR, any Subcontractor, any Supplier, or any other person or organization, or to any surety for or employee or agent of any of them, for damages arising out of or resulting from (i) delays caused by or within the control of CONTRACTOR, or (ii) delays beyond the control of both parties including but not limited to fires, floods, epidemics abnormal weather conditions, acts of God or acts or neglect by utility owners or other contractors performing other work as contemplated by Article 7.

12.2 EXTENSIONS OF TIME FOR DELAY DUE TO WEATHER. Contract time may be extended by the ARCHITECT because of delays in completion of the WORK due to unusually severe weather, provided that the CONTRACTOR shall, within 10 days of the beginning of any such delay, notify the ARCHITECT in writing of the cause of delay and request an extension of contract time. The ARCHITECT will ascertain the facts and the extent of the delay and extend the time for completing the WORK when, in the ARCHITECT's judgment, the findings of fact justify such an extension. Unprecedented, abnormal, or unusually severe weather will be defined as an event, or events, with a greater than 50-year recurrence interval, as determined by the National Weather Service, or equivalent state or federal agency.

ARTICLE 13 WARRANTY AND GUARANTEE; TESTS AND INSPECTIONS; CORRECTION, REMOVAL, OR ACCEPTANCE OF DEFECTIVE WORK

- 13.1 WARRANTY AND GUARANTEE. The CONTRACTOR warrants and guarantees to the OWNER and the ARCHITECT that all WORK will be in accordance with the Contract Documents and will not be defective. Prompt notice of defects known to the OWNER or ARCHITECT shall be given to the CONTRACTOR. All Defective WORK, whether or not in place, may be rejected, corrected, or accepted as provided in this Article 13.
- 13.2 ACCESS TO WORK. The OWNER, ARCHITECT, Architect of Record, their consultants, subconsultants, other representatives and personnel of OWNER, independent testing laboratories and governmental agencies with jurisdictional interests will have access to the WORK at reasonable times for their observation, inspecting and testing. CONTRACTOR shall provide them proper and safe conditions for such access and advise them of CONTRACTOR's site safety procedures and programs so that they may comply therewith as applicable.

13.3 INSPECTIONS AND TESTS

- A. The CONTRACTOR shall give the ARCHITECT timely notice of readiness of the WORK for all required inspections, tests, or approvals, and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.
- B. If Laws or Regulations of any public body having jurisdiction other than the OWNER require any WORK to specifically be inspected, tested, or approved, the CONTRACTOR shall pay all costs in connection therewith. The CONTRACTOR shall also be responsible for and shall pay all costs in connection with any inspection or testing required in connection with the OWNER's or the ARCHITECT's acceptance of a Supplier of materials or equipment proposed as a substitution or (orequal) to be incorporated in the WORK, or of materials or equipment submitted for review prior to the CONTRACTOR's purchase thereof for incorporation in the WORK. The cost of all inspections, tests, and approvals in addition to the above which are required by the Contract Documents shall be paid by the OWNER (unless otherwise specified).
- C. The ARCHITECT will make, or have made, such inspections and tests as the ARCHITECT deems necessary to see that the WORK is being accomplished in accordance with the requirements of the Contract Documents. Unless otherwise specified in the Supplementary General Conditions, the cost of such inspection and testing will be borne by the OWNER. In the event such inspections or tests reveal non-compliance with the requirements of the Contract Documents, the CONTRACTOR shall bear the cost of corrective measures deemed necessary by the ARCHITECT, as well as the cost of subsequent re-inspection and retesting. Neither observations by the ARCHITECT nor inspections, tests, or

approvals by others shall relieve the CONTRACTOR from the CONTRACTOR's obligation to perform the WORK in accordance with the Contract Documents.

- D. All inspections, tests, or approvals other than those required by Laws or Regulations of any public body having jurisdiction shall be performed by organizations acceptable to the ARCHITECT and the CONTRACTOR.
- E. If any WORK (including the work of others anticipated under paragraph 7.1) that is to be inspected, tested, or approved is covered without written concurrence of the ARCHITECT, it must, if requested by the ARCHITECT, be uncovered for observation. Such uncovering shall be at the CONTRACTOR's expense unless the CONTRACTOR has given the ARCHITECT timely notice of the CONTRACTOR's intention to perform such test or to cover the same and the ARCHITECT has not acted with reasonable promptness in response to such notice.
- F. If any WORK is covered contrary to the written request of the ARCHITECT, it must, if requested by the ARCHITECT, be uncovered for the ARCHITECT's observation and recovered at the CONTRACTOR's expense.
- G. If the ARCHITECT considers it necessary or advisable that covered WORK be observed by the ARCHITECT or inspected or tested by others, the CONTRACTOR, at the ARCHITECT's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as the ARCHITECT may require, that portion of the WORK in question, furnishing all necessary labor, material, and equipment. If it is found that such WORK is defective, the CONTRACTOR shall bear all direct, indirect, and consequential costs and damages of such uncovering, exposure, observation, inspection, and testing and of satisfactory reconstruction, including but not limited to fees and charges of Architects of Record, attorneys, and other professionals. However, if such WORK is not found to be defective, the CONTRACTOR shall be allowed an increase in the Contract Price or an extension of the Contract Time, or both, directly attributable to such uncovering, exposure, observation, inspection, testing, and reconstruction; and, if the parties are unable to agree as to the amount or extent thereof, the CONTRACTOR may make a claim therefor as provided in Articles 11 and 12.
- OWNER MAY STOP THE WORK. If the WORK is defective, or the CONTRACTOR fails to perform WORK in such a way that the completed WORK will conform to the Contract Documents, the OWNER may order the CONTRACTOR to stop the WORK, or any portion thereof, until the cause for such order has been eliminated; however, this right of the OWNER to stop the WORK shall not give rise to any duty on the part of the OWNER to exercise this right for the benefit of the CONTRACTOR or any other party.
- 13.5 CORRECTION OR REMOVAL OF DEFECTIVE WORK. If required by the ARCHITECT, the CONTRACTOR shall promptly, either correct all Defective WORK, whether or not fabricated, installed, or completed, or, if the WORK has been rejected by the ARCHITECT, remove it from the site and replace it with non-defective WORK. The CONTRACTOR shall bear all direct, indirect and consequential costs and damages of such correction or removal, including but not limited to fees and charges of Architects of Record, attorneys, and other professionals made necessary thereby.

13.6 ONE YEAR CORRECTION PERIOD

A. If within one year after the date of Substantial Completion or such longer period of time as may be prescribed by Laws or Regulations or by the terms of any applicable special guarantee required by the

Contract Documents or by any specific provision of the Contract Documents, any WORK is found to be defective, the CONTRACTOR shall promptly, without cost to the OWNER and in accordance with OWNER's written notification, (i) correct such Defective WORK, or, if it has been rejected by the OWNER, remove it from the site and replace it with non-defective WORK, and (ii) satisfactorily correct or remove and replace any damage to other work of others resulting therefrom. If the CONTRACTOR does not promptly comply with such notification, or in an emergency where delay would cause serious risk of loss or damage, the OWNER may have the Defective WORK corrected or the rejected WORK removed and replaced, and all direct, indirect, and consequential costs and damages of such removal and replacement including but not limited to fees and charges of Architects of Record, attorneys and other professionals will be paid by the CONTRACTOR.

- B. Where Defective WORK (and damage to other WORK resulting therefrom) has been corrected, removed or replaced under this paragraph 13.6, the correction period hereunder with respect to such WORK will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.
- 13.7 ACCEPTANCE OF DEFECTIVE WORK. If, instead of requiring correction or removal and replacement of Defective WORK, the OWNER prefers to accept the WORK, the OWNER may do so. The CONTRACTOR shall bear all direct, indirect, and consequential costs attributable to the OWNER's evaluation of and determination to accept such Defective WORK. If any such acceptance occurs prior to final payment, a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the WORK, and the OWNER shall be entitled to an appropriate decrease in the Contract Price.

ARTICLE 14 PAYMENTS TO CONTRACTOR AND COMPLETION

- 14.1 SCHEDULE OF VALUES (LUMP SUM PRICE BREAKDOWN). The Schedule of Values or lump sum price breakdown established as provided in the General Requirements shall serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to the ARCHITECT.
- 14.2 UNIT PRICE BID SCHEDULE. Progress payments on account of Unit Price WORK will be based on the number of units completed.

14.3 APPLICATION FOR PROGRESS PAYMENT

- A. Unless otherwise prescribed by law, on the 25th of each month, the CONTRACTOR shall submit to the ARCHITECT for review, an Application for Payment filled out and signed by the CONTRACTOR covering the WORK completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents.
- B. The Application for Payment shall identify, as a sub-total, the amount of the CONTRACTOR's Total Earnings to Date, plus the Value of Materials Stored at the Site which have not yet been incorporated in the WORK, and less a deductive adjustment for materials installed which were not previously incorporated in the WORK, but for which payment was allowed under the provisions for payment for Materials Stored at the Site, but not yet incorporated in the WORK.
- C. The Net Payment Due the CONTRACTOR shall be the above-mentioned subtotal from which shall be deducted the total amount of all previous payments made to the CONTRACTOR. Progress payments

will be paid in full in accordance with Article 14 of the General Conditions until 90% of the contract amount has been paid. The remaining 10% of the contract amount shall be retained until:

- 1. final inspection has been made;
- 2. completion of the project;
- 3. acceptance of the project by the OWNER and;
- 4. the OWNER has received notification from the Alaska Department of Labor that the CONTRACTOR has no outstanding wage/hour violations.
- D. The Value of Materials Stored at the Site shall be an amount equal to the specified percent of the value of such materials as set forth in the Supplementary General Conditions. Said amount shall be based upon the value of all acceptable materials and equipment not incorporated in the WORK but delivered and suitably stored at the Project site or at another location agreed to in writing; provided, each such individual item has a value of more than \$5000 and will become a permanent part of the WORK. The Application for Payment shall also be accompanied by a bill of sale, invoice, or other documentation warranting that the CONTRACTOR has received the materials and equipment free and clear of all liens, charges, security interests, and encumbrances (which are hereinafter in these General Conditions referred to as "Liens") and evidence that the materials and equipment are covered by appropriate property insurance and other arrangements to protect the OWNER's interest therein, all of which will be satisfactory to the OWNER.
- 14.4 CONTRACTOR'S WARRANTY OF TITLE. The CONTRACTOR warrants and guarantees that title to all WORK, materials, and equipment covered by an Application for Payment, whether incorporated in the WORK or not, will pass to the OWNER no later than the time of payment free and clear of all liens.

14.5 REVIEW OF APPLICATIONS FOR PROGRESS PAYMENT

- A. The ARCHITECT will, within seven (7) days after receipt of each Application for Payment, either indicate in writing a recommendation of payment and present the Application to the OWNER, or return the Application to the CONTRACTOR indicating in writing the ARCHITECT's reasons for refusing to recommend payment. In the later case, the CONTRACTOR may make the necessary corrections and resubmit the Application. If the ARCHITECT still disagrees with a portion of the Application, it will submit the Application recommending the undisputed portion of the Application to the OWNER for review and provide reasons for recommending non-payment of the disputed amount. Thirty days after presentation of the Application for Payment with the ARCHITECT's recommendation, the amount recommended will (subject to the provisions of Paragraph 14.5B) become due and when due will be paid by the OWNER to the CONTRACTOR.
- B. The OWNER may refuse to make payment of the full amount recommended by the ARCHITECT because claims have been made against the OWNER on account of the CONTRACTOR's performance of the WORK or Liens have been filed in connection with the WORK or there are other items entitling the OWNER to a credit against the amount recommended, but the OWNER must give the CONTRACTOR written notice within seven (7) days (with a copy to the ARCHITECT) stating the reasons for such action.

14.6 PARTIAL UTILIZATION

- A. The OWNER shall have the right to utilize or place into service any item of equipment or other usable portion of the WORK prior to completion of the WORK. Whenever the OWNER plans to exercise said right, the CONTRACTOR will be notified in writing by the OWNER, identifying the specific portion or portions of the WORK to be so utilized or otherwise placed into service.
- B. It shall be understood by the CONTRACTOR that until such written notification is issued, all responsibility for care and maintenance of all of the WORK shall be borne by the CONTRACTOR. Upon issuance of said written notice of partial utilization, the OWNER will accept responsibility for the protection and maintenance of all such items or portions of the WORK described in the written notice.
- C. The CONTRACTOR shall retain full responsibility for satisfactory completion of the WORK, regardless of whether a portion thereof has been partially utilized by the OWNER and the CONTRACTOR's one year correction period shall commence only after the date of Substantial Completion for the WORK.
- 14.7 SUBSTANTIAL COMPLETION. When the CONTRACTOR considers the WORK ready for its intended use the CONTRACTOR shall notify the OWNER and the ARCHITECT in writing that the WORK is substantially complete. The CONTRACTOR will attach to this request a list of all WORK items that remain to be completed and a request that the ARCHITECT prepare a Notice of Completion. Within a reasonable time thereafter, the OWNER, the CONTRACTOR, and the ARCHITECT shall make an inspection of the WORK to determine the status of completion. If the ARCHITECT does not consider the WORK substantially complete, or the list of remaining WORK items to be comprehensive, the ARCHITECT will notify the CONTRACTOR in writing giving the reasons thereof. If the ARCHITECT considers the WORK substantially complete, the ARCHITECT will prepare and deliver to the OWNER, for its execution and recording, the Notice of Completion signed by the ARCHITECT and CONTRACTOR, which shall fix the date of Substantial Completion.
- 14.8 FINAL APPLICATION FOR PAYMENT. After the CONTRACTOR has completed all of the remaining WORK items referred to in Paragraph 14.7 and delivered all maintenance and operating instructions, schedules, guarantees, Bonds, certificates of inspection, record as-built documents (as provided in the General Requirements) and other documents, all as required by the Contract Documents, and after the ARCHITECT has indicated that the WORK is acceptable, the CONTRACTOR may make application for final payment following the procedure for progress payments. The final Application for Payment shall be accompanied by all documentation called for in the Contract Documents, together with complete and legally effective releases or waivers (satisfactory to the OWNER) of all liens arising out of or filed in connection with the WORK.

14.9 FINAL PAYMENT AND ACCEPTANCE

A. If, on the basis of the ARCHITECT's observation of the WORK during construction and final inspection, and the ARCHITECT's review of the final Application for Payment and accompanying documentation, all as required by the Contract Documents, the ARCHITECT is satisfied that the WORK has been completed and the CONTRACTOR's other obligations under the Contract Documents have been fulfilled, the ARCHITECT will, within 14 days after receipt of the final Application for Payment, indicate in writing the ARCHITECT's recommendation of payment and present the Application to the OWNER for payment.

- B. After acceptance of the WORK by the OWNER's governing body, the OWNER will make final payment to the CONTRACTOR of the amount remaining after deducting all prior payments and all amounts to be kept or retained under the provisions of the Contract Documents, including the following items:
 - 1. Liquidated damages, as applicable.
 - 2. Two times the value of outstanding items of correction WORK or punch list items yet uncompleted or uncorrected, as applicable. All such WORK shall be completed or corrected to the satisfaction of the OWNER within the time stated on the Notice of Completion, otherwise the CONTRACTOR does hereby waive any and all claims to all monies withheld by the OWNER to cover the value of all such uncompleted or uncorrected items.

14.10 RELEASE OF RETAINAGE AND OTHER DEDUCTIONS

- A. After executing the necessary documents to initiate the lien period, and not more than 45 days thereafter (based on a 30-day lien filing period and 15-day processing time), the OWNER will release to the CONTRACTOR the retainage funds withheld pursuant to the Agreement, less any deductions to cover pending claims against the OWNER pursuant to Paragraph 14.5B.
- B. After filing of the necessary documents to initiate the lien period, the CONTRACTOR shall have 30 days to complete any outstanding items of correction WORK remaining to be completed or corrected as listed on a final punch list made a part of the Notice of Completion. Upon expiration of the 45 days, referred to in Paragraph 14.10A, the amounts withheld pursuant to the provisions of Paragraph 14.9B herein, for all remaining WORK items will be returned to the CONTRACTOR; provided, that said WORK has been completed or corrected to the satisfaction of the OWNER within said 30 days. Otherwise, the CONTRACTOR does hereby waive any and all claims for all monies withheld by the OWNER under the contract to cover 2 times the value of such remaining uncompleted or uncorrected items.
- 14.11 CONTRACTOR'S CONTINUING OBLIGATION. The CONTRACTOR's obligation to perform and complete the WORK in accordance with the Contract Documents shall be absolute. Neither recommendation of any progress or final payment by the ARCHITECT, nor the issuance of a Notice of Completion, nor any payment by the OWNER to the CONTRACTOR under the Contract Documents, nor any use or occupancy of the WORK or any part thereof by the OWNER, nor any act of acceptance by the OWNER nor any failure to do so, nor any review of a Shop Drawing or sample submittal, will constitute an acceptance of WORK not in accordance with the Contract Documents or a release of the CONTRACTOR's obligation to perform the WORK in accordance with the Contract Documents.
- 14.12 FINAL PAYMENT TERMINATES LIABILITY OF OWNER. Final payment is defined as the last progress payment made to the CONTRACTOR for earned funds, less monies withheld as applicable, pursuant to Paragraph 14.10A. The acceptance by the CONTRACTOR of the final payment referred to in Paragraph 14.9 herein, shall be a release of the OWNER and its agents from all claims of liability to the CONTRACTOR for anything done or furnished for, or relating to, the WORK or for any act of neglect of the OWNER or of any person relating to or affecting the WORK, except demands against the OWNER for the remainder, if any, of the amounts kept or retained under the provisions of Paragraph 14.9 herein; and excepting pending, unresolved claims filed prior to the date of the Notice of Completion.

ARTICLE 15 SUSPENSION OF WORK AND TERMINATION

15.1 SUSPENSION OF WORK BY OWNER. The OWNER, acting through the ARCHITECT, may, at any time and without cause, suspend the WORK or any portion thereof for a period of not more than 90 days by notice in writing to the CONTRACTOR. The CONTRACTOR shall resume the WORK on receipt from the ARCHITECT of a notice of resumption of WORK. The CONTRACTOR shall be allowed an increase in the Contract Price or an extension of the Contract Time, or both, directly attributable to any suspension if the CONTRACTOR makes an approved claim therefor as provided in Articles 11 and 12.

15.2 TERMINATION OF AGREEMENT BY OWNER (CONTRACTOR DEFAULT)

- A. In the event of default by the CONTRACTOR, the OWNER may give 10 days written notice to the CONTRACTOR of OWNER's intent to terminate the Agreement and provide the CONTRACTOR an opportunity to remedy the conditions constituting the default. It shall be considered a default by the CONTRACTOR whenever CONTRACTOR shall: (1) declare bankruptcy, become insolvent, or assign its assets for the benefit of its creditors; (2) fail to provide materials or quality of WORK meeting the requirements of the Contract Documents; (3) disregard or violate provisions of the Contract Documents or ARCHITECT's instructions; (4) fail to prosecute the WORK according to the approved progress schedule; or, (5) fail to provide a qualified superintendent, competent workers, or materials or equipment meeting the requirements of the Contract Documents. If the CONTRACTOR fails to remedy the conditions constituting default within the time allowed, the OWNER may then issue the Notice of Termination.
- B. In the event the Agreement is terminated in accordance with Paragraph 15.2A, herein, the OWNER may take possession of the WORK and may complete the WORK by whatever method or means the OWNER may select. The cost of completing the WORK shall be deducted from the balance which would have been due the CONTRACTOR had the Agreement not been terminated and the WORK completed in accordance with the Contract Documents. If such cost exceeds the balance which would have been due, the CONTRACTOR shall pay the excess amount to the OWNER. If such cost is less than the balance which would have been due, the CONTRACTOR shall not have claim to the difference.
- 15.3 TERMINATION OF AGREEMENT BY OWNER (FOR CONVENIENCE). The OWNER may terminate the Agreement at any time if it is found that reasons beyond the control of either the OWNER or CONTRACTOR make it impossible or against the OWNER's interests to complete the WORK. In such a case, the CONTRACTOR shall have no claims against the OWNER except: (1) for the value of WORK performed up to the date the Agreement is terminated; and, (2) for the cost of materials and equipment on hand, in transit, or on definite commitment, as of the date the Agreement is terminated, which would be needed in the WORK and which meet the requirements of the Contract Documents. The value of WORK performed and the cost of materials and equipment delivered to the site, as mentioned above, shall be determined by the ARCHITECT in accordance with the procedure prescribed for the making of the final Application for Payment and payment under Paragraphs 14.8 and 14.9.
- 15.4 TERMINATION OF AGREEMENT BY CONTRACTOR. The CONTRACTOR may terminate the Agreement upon 10 days written notice to the OWNER, whenever: 1) the WORK has been suspended under the provisions of Paragraph 15.1, herein, for more than 90 consecutive days through no fault or

negligence of the CONTRACTOR, and notice to resume WORK or to terminate the Agreement has not been received from the OWNER within this time period; or, 2) the OWNER should fail to pay the CONTRACTOR any monies due to the CONTRACTOR in accordance with the terms of the Contract Documents and within 60 days after presentation to the OWNER by the CONTRACTOR of a request therefor, unless within said 10-day period the OWNER shall have remedied the condition upon which the payment delay was based. In the event of such termination, the CONTRACTOR shall have no claims against the OWNER except for those claims specifically enumerated in Paragraph 15.3, herein, and as determined in accordance with the requirements of said paragraph.

ARTICLE 16 MISCELLANEOUS

16.1 GIVING NOTICE. Whenever any provision of the Contract Documents requires the giving of written notice, it will be deemed to have been validly given if delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended, or if delivered at or sent by registered or certified mail, postage prepaid, to the last business address known to the giver of the notice.

16.2 RIGHTS IN AND USE OF MATERIALS FOUND ON THE WORK

- A. The CONTRACTOR may use on the Project, with ARCHITECT's approval, such stone, gravel, sand, or other material determined suitable by the ARCHITECT, as may be found in the excavation. The CONTRACTOR will be paid for the excavation of such material at the corresponding contract unit price. No additional payment will be made for utilizing the material from excavation as borrow, or select borrow.
- B. The CONTRACTOR shall replace, at its own expense, with other acceptable material, all of that portion of the excavated material so removed and used which was needed for use on the Project. No charge for the materials so used will be made against the CONTRACTOR except that the CONTRACTOR shall be responsible for payment of any royalties required.
- C. The CONTRACTOR shall not excavate or remove any material from within the Project location which is not within the grading limits, as indicated by the slope and grade lines, without written authorization from the ARCHITECT.
- D. In the event the CONTRACTOR has processed materials from OWNER-furnished sources in excess of the quantities required for performance of this contract, including any waste material produced as a by-product, the CBJ may retain possession of such materials without obligation to reimburse the CONTRACTOR for the cost of their production. When such materials are in a stockpile, the ARCHITECT may require: that it remain in stockpile; the CONTRACTOR level such stockpile(s); or that the CONTRACTOR remove such materials and restore the premises to a satisfactory condition at the CONTRACTOR's expense. This provision shall not preclude the CBJ from arranging with the CONTRACTOR to produce material over and above the contract needs, payment for which shall be by written agreement between the CBJ and the CONTRACTOR.
- E. Unless otherwise provided, the material from any existing old structure may be used temporarily by the CONTRACTOR in the erection of the new structure. Such material shall not be cut or otherwise damaged except with the approval of the ARCHITECT.

- 16.3 RIGHT TO AUDIT. If the CONTRACTOR submits a claim to the OWNER for additional compensation, the OWNER shall have the right, as a condition to considering the claim, and as a basis for evaluation of the claim, and until the claim has been settled, to audit the CONTRACTOR's books to the extent they are relevant. This right shall include the right to examine books, records, documents, and other evidence and accounting procedures and practices, sufficient to discover and verify all direct and indirect costs of whatever nature claimed to have been incurred or anticipated to be incurred and for which the claim has been submitted. The right to audit shall include the right to inspect the CONTRACTOR's plants, or such parts thereof, as may be or have been engaged in the performance of the WORK. The CONTRACTOR further agrees that the right to audit encompasses all subcontracts and is binding upon Subcontractors. The rights to examine and inspect herein provided for shall be exercisable through such representatives as the OWNER deems desirable during the CONTRACTOR's normal business hours at the office of the CONTRACTOR. The CONTRACTOR shall make available to the OWNER for auditing, all relevant accounting records and documents, and other financial data, and upon request, shall submit true copies of requested records to the OWNER.
- 16.4 ARCHAEOLOGICAL OR HISTORICAL DISCOVERIES. When the CONTRACTOR's operation encounters prehistoric artifacts, burials, remains of dwelling sites, paleontological remains, such as shell heaps, land or sea mammal bones or tusks, or other items of historical significance, the CONTRACTOR shall cease operations immediately and notify the ARCHITECT. No artifacts or specimens shall be further disturbed or removed from the ground and no further operations shall be performed at the site until so directed. Should the ARCHITECT order suspension of the CONTRACTOR's operations in order to protect an archaeological or historical finding, or order the CONTRACTOR to perform extra WORK, such order(s) shall be covered by an appropriate contract change document.
- 16.5 CONSTRUCTION OVER OR ADJACENT TO NAVIGABLE WATERS. All WORK over, on, or adjacent to navigable waters shall be so conducted that free navigation of the waterways will not be interfered with and the existing navigable depths will not be impaired, except as allowed by permit issued by the U.S. Coast Guard and/or the U.S. Army Corps of Engineers, as applicable.
- 16.6 GRATUITY AND CONFLICT OF INTEREST. The CONTRACTOR agrees to not extend any loan, gratuity or gift of money of any form whatsoever to any employee or elected official of the OWNER, nor will the CONTRACTOR rent or purchase any equipment or materials from any employee or elected official of the OWNER, or to the best of the CONTRACTOR's knowledge, from any agent of any employee or elected official of the OWNER. Before final payment, the CONTRACTOR shall execute and furnish the OWNER an affidavit certifying that the CONTRACTOR has complied with the above provisions of the contract.

16.7 SUITS OF LAW CONCERNING THE WORK

- A. Should a suit of law be entered into, either by the CONTRACTOR (or the CONTRACTOR's surety) against the OWNER, or by the OWNER against the CONTRACTOR (or the CONTRACTOR's surety), the suit of law shall be tried in the First Judicial District of Alaska.
- B. If one of the questions at issue is the satisfactory performance of the WORK by the CONTRACTOR and should the appropriate court of law judge the WORK of the CONTRACTOR to be unsatisfactory, then the CONTRACTOR (or the CONTRACTOR's surety) shall reimburse the OWNER for all legal and all other expenses (as may be allowed and set by the court) incurred by the OWNER because of

the suit of the law and, further, it is agreed that the OWNER may deduct such expense from any sum or sums then, or any that become due the CONTRACTOR under the contract.

16.8 CERTIFIED PAYROLLS

- A. All CONTRACTORs or Subcontractor who perform work on a public construction contract for the OWNER shall file a Certified Payroll with the Alaska Department of Labor every two weeks. Before the second Friday, each CONTRACTOR and Subcontractor must file Certified Payrolls with Statements of Compliance for the previous two weeks. (Section 14-2-4 ACLA 1949; am Section 4 ch 142 SLA 1972).
- B. In lieu of submitting the State payroll form, the CONTRACTOR's standard payroll form may be submitted, provided it contains the information required by AS 36.05.040 and a statement that the CONTRACTOR is complying with AS 36.10.010.
- C. Any CONTRACTOR or Subcontractor, who performs work on public construction in the State, as defined by AS 36.95.010(3), shall pay not less than the current prevailing rate of wages as issued by the Alaska Department of Labor before the end of the pay period. (AS 36.05.010).

16.9 PREVAILING WAGE RATES

- A. Wage rates for Laborers and Mechanics on Public Contracts, AS 36.05.070. The CONTRACTOR, or Subcontractors, shall pay all employees unconditionally and not less than once a week. Wages may not be less than those stated in Paragraph 16.8C, regardless of the contractual relationship between the CONTRACTOR or Subcontractors and laborers, mechanics, or field surveyors. The scale of wages to be paid shall be posted by the CONTRACTOR in a prominent, easily accessible place at the site of the WORK.
- B. Failure to Pay Agreed Wages, AS 36.05.080. If it is found that a laborer, mechanic, or field surveyor employed by the CONTRACTOR or Subcontractor has been, or is being, paid a rate or wages less than the established rate, the OWNER may, by written notice, terminate the CONTRACTOR or Subcontractors right to proceed with the WORK. The OWNER may prosecute the WORK to completion by contract or otherwise, and the CONTRACTOR and sureties will be held liable to the OWNER for excess costs for completing the WORK. (Section 2 ch 52 SLA 1959).
- C. Listing CONTRACTORS Who Violate contracts, AS 36.05.090. In addition, a list giving the names of persons who have disregarded the rights of their employees shall be distributed to all departments of State government and all political subdivisions. No person appearing on this list, and no firm, corporation, partnership or association in which the person has an interest, may WORK as a CONTRACTOR or Subcontractor on a public construction contract for the State, or a political subdivision of the state, until three years after the date of publication of the list. (Section 3 ch 52 SLA 1959; am Section 9 ch 142 SLA).
- 16.10 EMPLOYMENT REFERENCE. Workers employed in the execution of the contract by the CONTRACTOR or by any Subcontractor under this contract shall not be required or permitted to labor more than 8 hours a day or 40 hours per week in violation of the provisions of the Alaska Wage and Hour Act, Section 23.10.060.

16.11 COST REDUCTION INCENTIVE

- A. At any time within 45 days after the date of the Notice of Award, the CONTRACTOR may submit to the ARCHITECT in writing, proposals for modifying the plans, specifications, or other requirements of this contract for the sole purpose of reducing the total cost of construction. The cost reduction proposal shall not impair in any manner the essential functions or characteristics of the project, including but not limited to, service life, economy of operation, ease of maintenance, desired appearance or design and safety standards.
- B. The cost reduction proposal shall contain the following information:
 - 1. Description of both the existing contract requirements for performing the WORK and the proposed changes.
 - 2. An itemization of the contract requirements that must be changed if the proposal is adopted.
 - 3. A detailed estimate of the time required and the cost of performing the WORK under both the existing contract and the proposed change.
 - 4. A statement of the date by which the CONTRACTOR must receive the decision from the OWNER on the cost reduction proposal.
 - 5. The contract items of WORK effected by the proposed changes including any quantity variations.
 - 6. A description and estimate of costs the OWNER may incur in implementing the proposed changes, such as test and evaluation and operating and support costs.
 - 7. A prediction of any effects the proposed change would have on future operations and maintenance costs to the OWNER.
- C. The provisions of this section shall not be construed to require the OWNER to consider any cost reduction proposal which may be submitted; nor will the OWNER be liable to the CONTRACTOR for failure to accept or act upon any cost reduction proposal submitted, or for delays to the WORK attributable to the consideration or implementation of any such proposal.
- D. If a cost reduction proposal is similar to a change in the plans or Specifications for the Project under consideration by the OWNER at the time the proposal is submitted, the OWNER will not accept such proposal and reserves the right to make such changes without compensation to the CONTRACTOR under the provisions of this section.
- E. The CONTRACTOR shall continue to perform the WORK in accordance with the requirements of the contract until an executed Change Order incorporating the cost reduction proposal has been issued. If any executed Change Order has not been issued by the date upon which the CONTRACTOR's cost reduction proposal specifies that a decision should be made by the OWNER, in writing, the cost reduction proposal shall be considered rejected.
- F. The OWNER, shall be the sole judge of the acceptability of a cost reduction proposal and of the estimated net savings in Contract Time and construction costs resulting from the adoption of all or any part of such proposal. Should the CONTRACTOR disagree with OWNER's decision on the cost reduction proposal, there is no further consideration. The OWNER reserves the right to make final determination.
- G. If the CONTRACTOR's cost reduction proposal is accepted in whole or in part, such acceptance will be made by a Contract Change Order, which specifically states that the change is executed pursuant to

this cost reduction proposal section. Such Change Order shall incorporate the changes in the plans and Specifications which are necessary to permit the cost reduction proposal or such part of it as has been accepted to be put into effect and shall include any conditions upon which the OWNER's approval is based, if such approval is conditional. The Change Order shall also describe the estimated net savings in the cost of performing the WORK attributable to the cost reduction proposal, and shall further provide that the contract cost be adjusted by crediting the OWNER with the estimated net savings amount.

- H. Acceptance of the cost reduction proposal and performance of the WORK does not extend the time of completion of the contract, unless specifically provided in the Change Order authorizing the use of the submitted proposal. Should the adoption of the cost reduction proposal result in a Contract Time savings, the total Contract Time shall be reduced by an amount equal to the time savings realized.
- I. The amount specified to the CONTRACTOR in the Change Order accepted in the cost reduction proposal shall constitute full compensation for the performance of WORK. No claims for additional costs as a result of the changes specified in the cost reduction proposal shall be allowed.
- J. The OWNER reserves the right to adopt and utilize any approved cost reduction proposal for general use on any contract administered when it is determined suitable for such application. Cost reduction proposals identical, similar, or previously submitted will not be accepted for consideration if acceptance and compensation has previously been approved. The OWNER reserves the right to use all or part of any cost reduction proposal without obligation or compensation of any kind to the CONTRACTOR.
- K. The CONTRACTOR shall bear the costs, if any, to revise all Bonds and insurance requirements for the Project, to include the cost reduction WORK.

GENERAL. These Supplementary General Conditions make additions, deletions, or revisions to the General Conditions as indicated herein. All provisions which are not so added, deleted, or revised remain in full force and effect. Terms used in these Supplementary General Conditions which are defined in the General Conditions have the meanings assigned to them in the General Conditions.

SGC 1 DEFINITIONS. *Remove* the definition for Contract Documents and *replace* with the following:

Contract Documents – The Table of Contents, Notice Inviting Bids, Instructions to Bidders, Bid Forms (including the Bid, Bid Schedule(s), Subcontractor Report, Bid Bond, and all required certificates and affidavits), Agreement, Performance Bond, Payment Bond, General Conditions, Supplementary General Conditions, Alaska Labor Standards, Reporting, and Prevailing Wage Rate Determination, Special Provisions, Standard Specifications, Technical Specifications, Drawings, Permits, and all Addenda, and Change Orders executed pursuant to the provisions of the Contract Documents.

SGC 2.2 COPIES OF DOCUMENTS. *Add* the following:

The OWNER shall furnish to the CONTRACTOR up to ten (10) copies of the Contract Documents which will include bound reduced Drawings. The CBJ Contracts Office shall contact the CONTRACTOR after issuance of Notice of Intent to Award to determine how many copies are needed. Additional quantities of the Contract Documents will be furnished at reproduction cost.

SGC 3.2 ORDER OF PRECEDENCE OF CONTRACT DOCUMENTS. *Remove* No. 12. Technical Specifications and No. 13. Drawings, and *add* the following:

- 12. Special Provisions Section
- 13. <u>Standard Specifications for Civil Engineering Projects and Subdivision Improvements</u>
 December 2003 Edition with current Errata Sheets.
- 14. Drawings.

SGC 4.2 PHYSICAL CONDITIONS - SUBSURFACE AND EXISTING STRUCTURES. *Add* the following:

C. In the preparation of the Contract Documents, the Engineer of Record has relied upon field measurements and visual inspection of the existing structures and surface conditions.

SGC - 4.6 USE OF THE CBJ/STATE LEMON CREEK GRAVEL PIT. Add the following.

The CBJ/State Lemon Creek Gravel Pit is not available for this Project.

SGC 5.1 PERFORMANCE, PAYMENT, AND OTHER BONDS. The Contractor shall furnish Performance and Payment Bonds in the amount of 100% of the Bid.

SGC 5.2 INSURANCE AMOUNTS. The limits of liability for the insurance required by Paragraph 5.2 of the General Conditions shall provide coverage for not less than the following amounts or greater where required by Laws and Regulations. The CONTRACTOR must provide certification of proper insurance coverage and amendatory endorsements or copies of the applicable policy language affecting coverage required in this agreement to the City and Borough of Juneau. All certificates of insurance supplied to the OWNER shall state that the OWNER is named as "Additional Insured for any and all work performed for the City & Borough of Juneau" for the Commercial General Liability policy and any other policies, if required

in this Section. NOTE: This requirement has changed. The OWNER no longer requires certificates of insurance referencing project names and contract numbers.

Delete paragraph C and **Replace** with the following paragraph C:

C. The CONTRACTOR shall furnish the OWNER with certificates showing the type, amount, class of operations covered, effective dates and dates of expiration of policies. Failure of CBJ to demand such certificate or other evidence of full compliance with these insurance requirements or failure of CBJ to identify a deficiency from evidence that is provided shall not be construed as a waiver of the obligation of the Contractor to maintain the insurance required by this contract. The coverage afforded will not be cancelled, reduced in coverage, or renewal refused until at least 30 days' prior written notice has been given to the OWNER by the CONTRACTOR. All such insurance required herein (except for Workers' Compensation and Employer's Liability) shall name the OWNER, its Consultants and subconsultants and their officers, directors, agents, and employees as "additional insureds" under the policies.

The CONTRACTOR shall purchase and maintain the following insurance:

1. Workers' Compensation and Employer's Liability. This insurance shall protect the CONTRACTOR against all claims under applicable state workers' compensation laws. The CONTRACTOR shall also be protected against claims for injury, disease, or death of employees which, for any reason, may not fall within the provisions of a Workers' Compensation law. The CONTRACTOR shall require each Subcontractor similarly to provide Workers' Compensation Insurance for all of the latter's employees to be engaged in such work unless such employees are covered by the protection afforded by the CONTRACTOR's Workers' Compensation Insurance. In case any class of employees is not protected, under the Workers' Compensation Statute, the CONTRACTOR shall provide and shall cause each subcontractor to provide adequate employer's liability insurance for the protection of such of its employees as are not otherwise protected. The CONTRACTOR grants a waiver of any right to subrogation against the OWNER by virtue of the payment of any loss under such insurance. This provision applies regardless of whether or not the OWNER has received a waiver of subrogation endorsement from the insurer.

Workers' Compensation: (under Paragraph 5.2C.1 of the General Conditions) as in accordance with AS 23.30.045:

a. State: Statutory

b. Applicable Federal (e.g., Longshore): Statutory

Note: If the WORK called for in the Contract Documents involves work in or on any navigable waters, the CONTRACTOR shall provide Workers' Compensation coverage which shall include coverage under the Longshore and Harbor Workers' Compensation Act, the Jones Act, and any other coverage required under Federal or State laws pertaining to workers in or on navigable waters.

a. Employers Liability

Bodily Injury by Accident: \$100,000.00 Each Accident
Bodily Injury by Disease: \$100,000.00 Each Employee
Bodily Injury by Disease: \$500,000.00 Policy Limit

- 1. CONTRACTOR agrees to waive all rights of subrogation against the OWNER for WORK performed under contract.
- 2. If CONTRACTOR directly utilizes labor outside of the State of Alaska in the prosecution of the WORK, "Other States" endorsement shall be required as a condition of the contract.
- 2. Commercial General Liability (CGL), including products and completed operations, property damage, bodily injury and personal and advertising injury, with limits no less than \$1,000,000 each occurrence and \$2,000,000 aggregate. (under Paragraph 5.2C.2 of the General Conditions) **This insurance policy is to contain, or be endorsed to contain, additional insured status for the CBJ, its officers, officials, employees, and volunteers.** If Additional insured status is provided in the form of an endorsement to the Contractor's insurance, the endorsement shall be at least as broad as ISO Form CG 20 10 11 85 or **both** CG 20 10, CG 20 26, CG 20 33, or CG 20 38; **and** CG 20 37 forms if later revisions used).
- 3. Commercial Automobile Liability: (under Paragraph 5.2C.3 of the General Conditions) including Owned, Hired, and Non-Owned Vehicles:

Combined Single Limit, Bodily Injury and Property Damage \$1,000,000.00

This insurance policy is to contain, or be endorsed to contain, additional insured status for the CBJ, its officers, officials, employees, and volunteers The CONTRACTOR shall require each Subcontractor similarly to provide Commercial Automobile Liability Insurance for all of the latter's employees to be engaged in such WORK unless such employees are covered by the protection afforded by the CONTRACTOR's Commercial Automobile Liability Insurance.

Add the following paragraphs:

- C. BUILDERS RISK is not required for this project.
- D. Hazardous Materials: As a condition of the Contract award, CONTRACTOR shall provide evidence of insurance coverage for Contractor's Pollution Liability as applicable to the WORK covered by abatement Subcontractor(s). Such coverage shall include operations addressing the removal and disposal of all hazardous materials with no exclusions for asbestos. Minimum limits shall be \$1,000,000. The policy shall not contain any exclusion relating to hazardous materials. Form of such policies shall be acceptable to the OWNER. **This insurance policy is to contain, or be endorsed to contain, additional insured status for the CBJ, its officers, officials, employees, and volunteers.**
- E. All Subcontractors are required to secure and maintain the insurance coverages listed above, unless otherwise noted.
- F. If the CONTRACTOR maintains higher limits than the minimums shown above, the OWNER requires and shall be entitled to coverage for the higher limits maintained by the CONTRACTOR. Any available insurance proceeds in excess of the specified minimum limits of insurance and coverage shall be available to the OWNER.
- G. Policies shall also specify insurance provided by CONTRACTOR will be considered primary and not contributory to any other insurance available to the OWNER.
- H. Should any of the policies described above be cancelled before the expiration date thereof, notice will be delivered in accordance with the policy provisions.

SGC 6.5 CONCERNING SUBCONTRACTORS, SUPPLIERS, AND OTHERS. Add the following:

The CONTRACTOR shall perform not less than 40% of the WORK with its own forces (i.e., without subcontracting). The 40% requirement shall be understood to mean that the CONTRACTOR shall perform, with its own organization, WORK amounting to at least 40% of the original contract amount. The 40% requirement will be calculated based upon the total of the subcontract amounts submitted for Contract Award, and any other information requested by the OWNER from the apparent low Bidder.

SGC 6.5 CONCERNING SUBCONTRACTORS, SUPPLIERS, AND OTHERS, *Add* the following paragraph:

C. CONTRACTOR must pay Subcontractors and/or Suppliers within 30 days of receiving payment from the OWNER, if that payment was made for Work performed by the Subcontractor and/or materials received. Failure to pay Subcontractors within 30 days of receiving payment from which Subcontractor and/or Supplier is to be paid may result in the OWNER initiating debarment proceedings as prescribed in the City and Borough of Juneau Purchasing Code. *The 30 day City and Borough of Juneau requirement does not supersede AS 36.90.210.*

SGC 6.6 PERMITS, *Add* the following paragraph:

D. Contractor is responsible for obtaining a Hot Works permit from the CBJ Permit Center, if performing work which requires such a permit. Work requiring a Hot Works Permit includes but is not limited to the following: cutting, welding, Thermit welding, brazing, soldering, grinding, thermal spraying, thawing pipe, installation of torch-applied roof systems or any other similar activity.

SGC 14.3 APPLICATION FOR PROGRESS PAYMENT. Paragraph D.

D. The Value of Materials Stored at the site shall be an amount equal to 85%.

SGC 14.9 FINAL PAYMENT AND ACCEPTANCE. Add the following paragraph:

C. Prior to the final payment the CONTRACTOR shall contact the Alaska Department of Labor and Workforce Development (ADOL) and provide the OWNER with clearance from the ADOL for the CONTRACTOR and all Subcontractors that have worked on the Project. This clearance shall indicate that all Employment Security Taxes have been paid. A sample form for this purpose is at the end of this section. The CONTRACTOR shall also submit a "NOTICE OF COMPLETION OF PUBLIC WORKS" signed by ADOL.

SGC 16.8 CERTIFIED PAYROLLS. *Change* paragraph A. to read:

A. All CONTRACTORs or Subcontractors who perform work on a public construction contract for the OWNER shall file a certified payroll with Alaska Department of Labor. See Section 00830 - Alaska Labor Standards, Reporting, and Prevailing Wage Rate Determination.

Add the following SGC 16.12.

SGC 16.12 EQUAL EMPLOYMENT OPPORTUNITY (EEO)

The CONTRACTOR may not discriminate against any employee or applicant for employment because of race, religion, color, national origin, age, disability, sex, marital status, changes in marital status, pregnancy or parenthood. The CONTRACTOR shall post a notice setting out the provisions of this paragraph in a conspicuous place available to employees and applicants for employment.

The CONTRACTOR and each Subcontractor shall state in all solicitations and advertisements for employees to work on this Project, that it is an Equal Opportunity Employer and that all qualified applicants will receive consideration for employment without regard to race, religion, color, national origin, age, disability, sex, marital status, changes in marital status, pregnancy or parenthood.

The CONTRACTOR shall include the provisions of this EEO article in every contract relating to this Project and shall require the inclusion of these provisions in every agreement entered into for this Project, so that those provisions will be binding upon the CONTRACTOR and each Subcontractor.

Add the following SGC 17:

SGC 17 GENERAL INFORMATION. This Project is currently funded by Bartlett Regional Hospital.

Employment Security Tax Clearance

Date:			
То:	Alaska Department of Juneau Field Tax Of PH 907-465-278 FAX 907-465-23	ffice 87	
From:			
Subject:	BRH Server Room Contract No. BE18	Fire Suppression System -171	
Timeframe of	of Contract		
	e whether or not clearance CONTRACTOR or Sub		CONTRACTOR or Subcontractor:
Name		Address	_
clearance an		oloyment Security Act, this requayment for WORK performed to	
Engineering	_		
155 S. Sewa Juneau, Alas	ska 99801		
Fax: 907-58 Email: Greg	66-4530 g.Smith@juneau.org		
() Tax Cle	arance is granted. arance is NOT granted.		
Remarks:			
~-			
Signature			Date
Title			

END OF SECTION

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM Contract No. BE18-171 SUPPLEMENTARY GENERAL CONDITIONS
Page 00800-6

SECTION 00830 - ALASKA LABOR STANDARDS, REPORTING, AND PREVAILING WAGE RATE DETERMINATION

State of Alaska, Department of Labor, Laborers' and Mechanics' Minimum Rates of Pay, AS 36.05.010 and AS 36.05.050, Wage and Hour Administration Pamphlet No. 600, the latest edition published by the State of Alaska, Department of Labor inclusive, are made a part of this contract by reference.

The CONTRACTOR is responsible for contacting the Alaska Department of Labor to determine compliance with current regulations.

Correspondence regarding Title 36 requirements may be submitted electronically or paper copies can be submitted by mail. To submit Title 36 documents electronically, go to https://myalaska.state.ak.us/home/app. If filing electronically, submit certified payrolls to ADOL at the website above and email a copy of all certified payrolls to Greg Smith at the email address below. If Contractor elects to submit paper copies, they should be submitted to the physical addresses below.

Within 10 Days of "Notice of Award/Notice to Proceed" make a list of <u>all</u> Subcontractors. Include their name, address, phone, estimated subcontract amount, and estimated start and finish dates. Send this list to the Wage and Hour Section (contact information below).

Certified Payrolls must be submitted every two weeks. Before the second Friday, each CONTRACTOR and Subcontractor must file Certified Payrolls with Statements of Compliance for the previous two weeks. Indicate "Start" on your first payroll, and "Final" on your last payroll for this Project.

As part of the **final payment request package**, CONTRACTOR must submit a "NOTICE OF COMPLETION OF PUBLIC WORKS" form signed by ADOL personnel.

Contact Information:

Wage and Hour Section

State of Alaska
Department of Labor and Workforce Development
Labor Standards and Safety Division and
Wage and Hour Administration
P.O. Box 11149
Juneau, AK 99811-1149
907-465-4842
http://labor.state.ak.us/lss/home.htm

Greg Smith, Contract Administrator

City and Borough of Juneau 155 S. Seward Street Juneau, AK 99801 (907) 586-0873 Greg.Smith@juneau.org

SECTION 01700 – PROJECT CLOSE-OUT

SECTION 01700 – PROJECT CLOSE-OUT, PART 1 - GENERAL, Article 1.3, FINAL SUBMITTALS, Paragraph A. *Delete* Items 6, 7 and 8 and *replace with the following subparagraph:*

6. Compliance Certificate and Release, signed by the CONTRACTOR, shall be submitted to the Engineering Contract Administrator.

SECTION 01700 – PROJECT CLOSE-OUT, PART 1 – GENERAL, Article 1.3, FINAL SUBMITTALS. *Add the following paragraph:*

C. Before final payment, the CONTRACTOR shall provide the Engineering Contract Administrator with clearance from the Alaska Department of Labor and Workforce Development for the CONTRACTOR and all Subcontractors that have worked on the Project. This clearance shall indicate that all Employment Security Taxes have been paid. A sample form for this purpose is at the end of Section 00800 – Supplementary General Conditions.

SECTION 01700 – PROJECT CLOSE-OUT, PART 1 - GENERAL, *add* the following Article:

- 1.5 PROJECT SIGN ASSEMBLY REMOVAL
 - A. The Project sign assembly shall be removed and the Project sign panel delivered to the CBJ Project Manager, as directed by the ENGINEER.
 - B. No progress payments will be processed by the OWNER after the CONTRACTOR has been directed by the ENGINEER to remove and deliver the Project sign panel to the CBJ, until the Project sign panel has been received by the CBJ.

SECTION 01700 – PROJECT CLOSE-OUT, PART 1 – GENERAL. *Replace* the COMPLIANCE CERTIFICATE AND RELEASE FORM with the following form:

SECTION 01700 – PROJECT CLOSE-OUT

COMPLIANCE CERTIFICATE AND RELEASE FORM

PROJECT: BRH Server Room Fire Suppression System

CONTRACT NO: BE18-171

The CONTRACTOR must complete and submit this to the Engineering Contract Administrator, Greg Smith with respect to the entire contract.

Completed forms may be submitted upon completion of the Project. All requirements and submittals must be met before final payment will be made to the CONTRACTOR.

I certify that the following and any referenced attachments are true:

- All WORK has been performed, materials supplied, and requirements met in accordance with the applicable Drawings, Specifications, and Contract Documents.
- All Suppliers and Subcontractors have been paid in full with no claims for labor, materials or other services outstanding. If all Subcontractors and suppliers are not paid in full, please explain on a separate sheet.
- All employees have been paid not less that the current prevailing wage rates set by the State of Alaska (or U.S. Department of Labor, as applicable).
- All equal employment opportunity, certified payroll and other reports have been filed in accordance with the prime contract.
- The attached list of Subcontractors is complete (required from CONTRACTOR). The Contract Administrator was advised and approved of all Subcontractors before WORK was performed and has approved any substitutions of Subcontractors.
- All DBE firms listed as a precondition of the prime contract award must have performed a commercially useful function in order for the WORK to count to a DBE goal. All DBE firms performed the WORK stated and have received at least the amount claimed for credit in the Contract Documents.
- All DBE Subcontractors must attach a signed statement of the payment amount received, the nature of WORK performed, whether any balance is outstanding, and indicate that no rebates are involved.
- If the amount paid is less than the amount originally claimed for DBE credit, the CONTRACTOR has attached approval from the Contracts Administrator for underutilization.

I understand it is unlawful to misrepresent information in order to receive a payment which would otherwise be withheld if these conditions were not met. I am an authorized agent of this firm and sign this freely and voluntarily. The foregoing statements are true and apply to the following project contractor.

	Capacity: CONTRACTO	R
Firm Name		
Signed	Printed Name and Title	Date

Return completed form to: Greg Smith, Engineering Contract Administrator, City and Borough of Juneau, 155 South Seward Street, Juneau, AK 99801. Call (907) 586-0873 if we can be of further assistance or if you have any questions. Email: Greg.Smith@juneau.org

END OF SECTION

BRH SERVER ROOM FIRE SUPPRESSION SYSTEM Contract No. BE18-171

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Work under separate contracts.
- 4. Access to site.
- 5. Coordination with occupants.
- 6. Work restrictions.
- 7. Specification and drawing conventions.
- 8. Miscellaneous provisions.

B. Related Requirements:

- 1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.
- 2. Section 015221 "Special Safety Requirements ICRA" for procedures that must be followed to maintain indoor air quality standards and contain any debris, dirt, dust, odors and/or other contaminants generated by the Contractor's operations.

1.2 PROJECT INFORMATION

- A. Project Identification: BRH Server Room Fire Suppression System CBJ Contract No: BE 18-171
 - 1. Project Location: The site of the WORK is 3260 Hospital Drive, Juneau, Alaska 99801
- B. Owner: City and Borough of Juneau, 155 South Seward Street, Juneau, Alaska 99801
 - 1. Using Agency: Bartlett Regional Hospital
 - 2. Using Agency Representative: Mark Walker, BRH Facilities Manager

e-mail: mwalker@bartletthospital.org

Work phone: 796-8888 Cell phone: 321-4333

- C. Construction Administration: Wilson Engineering, 130 South Seward St., Juneau, Alaska 99801
 - 1. Project Manager: Mike Greene mgreene@wileng.net Phone: 1-907-321-0057
- D. Engineer of Record: PDC Engineers, 907 Capitol Avenue, Juneau, Alaska 99801

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of the Project is defined by the Contract Documents and consists of the introduction of a stand-alone clean agent fire suppression system for Computer / Server Room 2425 with the clean agent tanks located in the adjacent Electrical Room 1131. It also includes the introduction of a second stand-alone clean agent fire suppression system within Computer / Server Room 2402B within Bartlett Regional Hospital. Both systems will be installed with a primary and backup clean agent tank, each with enough capacity to extinguish a fire in the spaces they serve.
- B. The Work will include, but is not necessarily limited to, the installation of the clean agent fire suppression systems, including control panels, storage tanks and piping. Work will also include the removal of portions of the existing wet pipe sprinkler systems in both Computer / Server Rooms, modifications to the fire detection and alarm systems, modifications to the existing supply and return air ductwork, modifications to the existing building automation / controls systems, as well as modifications to an existing AC unit in 2402B that will include the addition of an electrical shunt trip, ductwork, and condensate drain. This scope of work also includes final testing, acceptance and training on the new stand-alone clean agent systems.
- C. The Work in Electrcal Room 1131 will also include the abatement / removal-disposal of a portion of the existing ACM gypsum board ceiling to facilitate access to the above-ceiling space, as well as the abatement / removal-disposal of a portion of the existing ACM spray-applied fireproofing and overspray on the underside of the steel pan decking. The ceiling area to be removed is to be no more than 24" x 24" in size. The amount of spray-applied fire proofing to be removed is to be limited to that which is necessary to complete the core drilling work through the decking. See Mechanical Drawings and Section 028213 for details.
- D. All work is to be performed with ICRA controls in place, and with protection in place to not damage active computers, servers and other equipment present in the work spaces.
- E. Type of Contract.
 - 1. Project will be constructed under a single prime lump-sum contract.

1.4 WORK UNDER SEPARATE CONTRACTS

A. General: Cooperate fully with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract or other contracts. Coordinate the Work of this Contract with work performed by Owner and work being completed under separate contracts.

1.5 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for parking, materials delivery, storage and staging, and for construction operations.
- B. Use of Site: Limit use of Project site to the assigned parking / staging area. Do not disturb portions of Project site or building beyond the areas in which the Work is indicated.
 - 1. Limits: Confine construction operations to the areas designated within the project documents.

- 2. Driveways, Walkways and Entrances: Keep driveways, patient drop-off areas and entrances serving the premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weather tight condition throughout construction period. Repair damage caused by construction operations.

1.6 COORDINATION WITH OCCUPANTS

- A. Full Owner Occupancy: OWNER will occupy the Bartlett Regional Hospital during the entire construction period 24 hours a day / 7 days a week. Coordinate all construction related operations with OWNER to minimize conflicts, facilitate Owner usage of the building, and so as to not interfere with OWNER'S day-to-day operations. OWNER reserves the right to stop work on short notice to address situations which may arise whether construction related or not.
 - 1. Maintain access to existing exits, walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from OWNER and approval of authorities having jurisdiction.
 - 2. Notify User Agency Representative not less than 72 hours in advance of activities that will affect Owner's operations.
 - 3. OWNER will prepare a Certificate of Substantial Completion for the Work prior to Owner acceptance of the completed Work

1.7 WORK RESTRICTIONS

- A. Work Restrictions: The CONTRATOR MUST comply with the following restrictions associated with working within occupied portions of the building;
 - 1. The Contractor MUST erect and maintain a containment barrier or barriers around the designated work areas, and perform all work in accordance with SECTION 015221-SPECIAL SAFETY REQUIREMENTS ICRA.
 - 2. The Contractor MUST NOT stage materials within hallways or corridors. Only the materials that are to be immediately installed, or that can be staged within the area of the building turned over to the Contractor, are to be brought into the building. The Contractor MUST keep hallways and corridors clear of equipment, tools and debris at all times.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 5:00 p.m., Monday through Friday, unless otherwise indicated or specifically approved by Owner.

- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
 - 1. Notify Marc Walker, BRH Facilities Manager not less than two days in advance of proposed utility interruptions.
 - 2. Obtain written permission from Marc Walker, BRH Facilities Manager before proceeding with utility interruptions.
- D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner's occupancy with the Owner.
 - 1. Notify Marc Walker, BRH Facilities Manager not less than two days in advance of proposed disruptive operations.
 - 2. Obtain written permission from Marc Walker, BRH Facilities Manager before proceeding with disruptive operations.
- E. Nonsmoking Building: Smoking is not permitted within the building or anywhere on the Bartlett Regional Hospital campus.
- F. Controlled Substances: Use of tobacco products and other controlled substances within the Bartlett Regional Hospital building or campus is not permitted.
- G. The use of portable radios / stereos is not permitted in the building or BRH campus.

1.8 MISCELLANEOUS PROVISIONS

- A. Every member of the Contractor's work force that will be working within the Bartlett Regional Hospital must sign a confidentiality agreement before starting work.
- B. Every member of the Contractor's work force that will be coming onto the Bartlett Hospital campus must receive Hospital orientation training from the Facilities Director prior to beginning work. Coordinate with Marc Walker, BRH Facilities Manager to set up a training schedule. Training duration is estimated to be no more than 10 15 minutes.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

SECTION 011025 - MEASUREMENT AND PAYMENT

PART 1 - GENERAL

1.1 SCOPE

- A. Payment for the various items of the Bid Schedule, as further specified herein, shall include all compensation to be received by the CONTRACTOR for furnishing all tools, equipment, supplies, and manufactured articles, and for all labor, operations, and incidentals appurtenant to the items of WORK being described, as necessary to complete the various items of the WORK all in accordance with the requirements of the Contract Documents, including all appurtenances thereto, and including all costs of permits and cost of compliance with the regulations of public agencies having jurisdiction, including Safety and Health Requirements of the Occupational Safety and Health Administration of the U.S. Department of Labor (OSHA).
- B. No separate payment will be made for any item that is not specifically set forth in the Bid Schedule, and all costs therefor shall be included in the prices named in the Bid Schedule for the various appurtenant items of WORK.
- C. In addition to other incidental items of WORK listed elsewhere in the contract, the following items shall also be considered as incidental to other Items of WORK under this contract:
 - 1. Maintenance of all services (power, water, communication, data, security) through Project area.

1.2 PRICE BASED ON LUMP SUM PAY UNIT

- A. Measurement for payment for the Lump Sum Pay Unit will be based upon the completion of the entire WORK as a Lump Sum Pay Unit, complete, all in accordance with the requirements of the Contract Documents.
- B. Payment will be made at the amount shown on the Bid Schedule, which payment will constitute full compensation for all WORK.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
 - 1. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.3 GENERAL SUBMITTAL REQUIREMENTS

A. Provide name of Owner (CBJ/BRH) and CBJ project number on all substitution requests and other written communication.

1.4 ACTION SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include name of Owner, CBJ project number, Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use CSI Form 13.1A or similar approved form.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.

SECTION 012500 – SUBSTITUTION PROCEDURES

- f. Certificates and qualification data, where applicable or requested.
- g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
- h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
- i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
- j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
- k. Cost information, including a proposal of change, if any, in the Contract Sum.
- 1. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
- m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- 3. Owner/Project Manager's Action: If necessary, Owner/Project Manager will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Owner/Project Manager will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Forms of Acceptance: Change Order, Construction Change Directive, or Owner/Project Manager's Supplemental Instructions for minor changes in the Work
 - b. Use product specified if Owner/Project Manager does not issue a decision on use of a proposed substitution within time allocated.

PRODUCTS

1.5 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Owner/Project Manager will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution will not adversely affect Contractor's construction schedule.

SECTION 012500 – SUBSTITUTION PROCEDURES

- c. Requested substitution has received necessary approvals of authorities having jurisdiction.
- d. Requested substitution is compatible with other portions of the Work.
- e. Requested substitution has been coordinated with other portions of the Work.
- f. Requested substitution provides specified warranty.
- g. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Owner/Project Manager will consider requests for substitution if received within 14 days after the Notice to Proceed.
 - 1. Conditions: Owner/Project Manager will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - b. Requested substitution does not require extensive revisions to the Contract Documents.
 - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - d. Requested substitution will not adversely affect Contractor's construction schedule.
 - e. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - f. Requested substitution is compatible with other portions of the Work.
 - g. Requested substitution has been coordinated with other portions of the Work.
 - h. Requested substitution provides specified warranty.
 - i. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

EXECUTION (Not Used)

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

A. Owner/Project Manager will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time.

1.3 GENERAL SUBMITTAL REQUIREMENTS

A. Provide name of Owner (CBJ/BRH) and CBJ project number on all proposal requests and other written communication.

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Owner/Project Manager will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Owner/Project Manager are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include a statement that indicates the effect of the change on the construction schedule, including, start and finish times. Use available total float before requesting an extension of the Contract Time.
 - e. Quotation Form: Use forms acceptable to Owner/Project Manager.
- B. Contractor-Initiated Work Change Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Owner/Project Manager.

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

- 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
- 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
- 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
- 4. Include costs of labor and supervision directly attributable to the change.
- 5. Include a statement that indicates the effect of the change on the construction schedule, including, start and finish times. Use available total float before requesting an extension of the Contract Time.
- 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
- 7. Work Change Proposal Request Form: Use form acceptable to Owner/Project Manager.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Owner/Project Manager will issue a Change Order for signatures of Owner and Contractor on CBJ standard change order form.

PRODUCTS (Not Used)

EXECUTION (Not Used)

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:

- 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
- 2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 GENERAL SUBMITTAL REQUIREMENTS

A. Provide name of Owner (CBJ/BRH) and CBJ project number on all payment requests and other written communication.

1.3 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules.
 - 2. Submit the schedule of values to Owner/Project Manager at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Owner.
 - c. CBJ project number.
 - d. Name of Engineer.
 - e. Contractor's name and address.
 - f. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.
 - 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents.

SECTION 012900 – PAYMENT PROCEDURES

- 4. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
- 5. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
- 6. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.4 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Owner/Project Manager and paid for by Owner.
 - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Times: Submit Application for Payment to Owner/Project Manager by the 10th of the month. The period covered by each Application for Payment is one month, ending on the last day of the month.
- D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- E. Application Preparation: Complete every entry on form. Execute by a person authorized to sign legal documents on behalf of Contractor. Owner/Project Manager will return incomplete applications without action.
 - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 - 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- F. Transmittal: Submit electronic pdf of signed original copy of each Application for Payment to Owner/Project Manager by a method ensuring receipt within 24 hours or by electronic submittal via email in PDF format. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.

SECTION 012900 – PAYMENT PROCEDURES

- 2. When an application shows completion of an item, submit conditional final or full waivers.
- 3. Owner reserves the right to designate which entities involved in the Work must submit waivers
- 4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. Schedule of values.
 - 2. Contractor's construction schedule (preliminary if not final).
 - 3. Submittal schedule (preliminary if not final).
 - 4. List of Contractor's staff assignments.
 - 5. List of Contractor's principal consultants.
 - 6. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 - 7. Report of preconstruction conference.
- I. Application for Payment at Substantial Completion: After Owner/Project Manager issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Updated final statement, accounting for final changes to the Contract Sum.
 - 3. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
 - 4. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
 - 5. AIA Document G707-1994, "Consent of Surety to Final Payment."
 - 6. Evidence that claims have been settled.
 - 7. Final liquidated damages settlement statement.

PRODUCTS (Not Used)

EXECUTION (Not Used)

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. Requests for Information (RFIs) & Design Clarifications (DCs).
 - 2. Project meetings.

B. Related Requirements:

1. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.

1.2 DEFINITIONS

- A. RFI REQUEST FOR INFORMATION: Request from Contractor seeking information about or interpretation of the Contract Documents.
- B. DC DESIGN CLARIFICATION: Document issued by Design team providing clarification of design intent or interpretation of the Contract Documents.

1.3 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

1.4 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work.
- B. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's construction schedule.
 - 2. Preparation of the schedule of values.
 - 3. Installation and removal of temporary facilities and controls.

- 4. Delivery and processing of submittals.
- 5. Progress meetings.
- 6. Pre-installation conferences.
- 7. Project closeout activities.

1.5 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
 - 1. Owner/Project Manager will return RFIs submitted to Owner/Project Manager by other entities controlled by Contractor with no response.
 - 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
 - 1. Project name.
 - 2. CBJ Project number.
 - 3. Date.
 - 4. Name of Owner.
 - 5. Name of Contractor.
 - 6. Name of Project Manager
 - 7. Name of Engineer.
 - 8. RFI number, numbered sequentially.
 - 9. RFI subject.
 - 10. Specification Section number and title and related paragraphs, as appropriate.
 - 11. Drawing number and detail references, as appropriate.
 - 12. Field dimensions and conditions, as appropriate.
 - 13. Contractor's suggested resolution. If Contractor's solution(s) impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 - 14. Contractor's signature.
 - 15. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
- C. RFI Forms: AIA Document G716 or a Software-generated form with substantially the same content as indicated above, acceptable to Owner/Project Manager.
- D. Owner/Project Manager's Action: Owner/Project Manager will review each RFI, determine action required, and respond. Allow seven working days for Owner/Project Manager's response for each RFI. RFIs received by Owner/Project Manager after 1:00 p.m. will be considered as received the following working day.
 - 1. The following RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.

- c. Requests for coordination information already indicated in the Contract Documents.
- d. Requests for adjustments in the Contract Time or the Contract Sum.
- e. Requests for interpretation of Owner/Project Manager's actions on submittals.
- f. Incomplete RFIs or inaccurately prepared RFIs.
- 2. Owner/Project Manager's action may include a request for additional information, in which case Owner/Project Manager's time for response will date from time of receipt of additional information.
- 3. Owner/Project Manager's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Owner/Project Manager in writing within 10 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log monthly. Include the following:
 - 1. CBJ Project name.
 - 2. Name and address of Contractor.
 - 3. Name and address of Engineer.
 - 4. RFI number including RFIs that were dropped and not submitted.
 - 5. RFI description.
 - 6. Date the RFI was submitted.
 - 7. Date Owner/Project Manager's response was received.
- F. On receipt of Owner/Project Manager's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Owner/Project Manager within seven days if Contractor disagrees with response.
 - 1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 - 2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.6 DESIGN CLARIFICATIONS (DCs)

- A. On receipt of Design Clarification immediately distribute the DC to affected parties.
 - 1. Owner/Project Manager's action on DCs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the DC warrants change in the Contract Time or the Contract Sum, notify Owner/Project Manager in writing within 7 days of receipt of the DC.

1.7 PROJECT MEETINGS

- A. General: Owner/Project Manager is to schedule and conduct meetings and conferences at Project site unless otherwise indicated.
 - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner/Project Manager and Architect of scheduled meeting dates and times.
 - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 - 3. Minutes: Project Manager will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Contractor and Architect, within three days of the meeting.
- B. Preconstruction Conference: Owner/Project Manager will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner/Project Manager and Architect, but no later than 10 days after execution of the Agreement.
 - 1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Critical work sequencing and long-lead items.
 - c. Designation of key personnel and their duties.
 - d. Procedures for processing field decisions and Change Orders.
 - e. Procedures for RFIs & DC's.
 - f. Procedures for processing Applications for Payment.
 - g. Distribution of the Contract Documents.
 - h. Submittal procedures.
 - i. Preparation of record documents.
 - j. Use of the premises.
 - k. Work restrictions.
 - 1. Working hours.
 - m. Owner's occupancy requirements.
 - n. Responsibility for temporary facilities and controls.
 - o. Construction waste management and recycling.
 - p. Parking availability.
 - q. Office, work, and storage areas.
 - r. Equipment deliveries and priorities.
 - s. First aid.
 - t. Security.
 - u. Progress cleaning.
 - 3. Minutes: Owner/Project Manager is responsible for conducting meeting & will record and distribute meeting minutes.

- C. Progress Meetings: Owner/Project Manager to conduct progress meetings at weekly intervals or as otherwise needed.
 - 1. Attendees: In addition to representatives of Owner/Project Manager and Architect, each contractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Sequence of operations.
 - 2) Status of submittals.
 - 3) Deliveries.
 - 4) Off-site fabrication.
 - 5) Access.
 - 6) Progress cleaning.
 - 7) Quality and work standards.
 - 8) Status of correction of deficient items.
 - 9) Field observations.
 - 10) Status of RFIs and DCs.
 - 11) Status of proposal requests.
 - 12) Pending changes.
 - 13) Status of Change Orders.
 - 14) Pending claims and disputes.
 - 3. Minutes: Owner/Project Manager is responsible for conducting the meeting and will record and distribute the meeting minutes to each party present and to parties requiring information.
 - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PRODUCTS (Not Used)

EXECUTION (Not Used)

SECTION 013200 – CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's construction schedule.
 - 2. Construction schedule updating reports.
 - 3. Weekly construction reports
 - 4. Site condition reports.

1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- C. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.

1.3 GENERAL SUBMITTAL REQUIREMENTS

A. Provide name of Owner (CBJ /BRH) and CBJ project number on all submittals and other written communication.

1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file, where indicated.
 - 2. PDF electronic file.
- B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

SECTION 013200 – CONSTRUCTION PROGRESS DOCUMENTATION

- 1. Submit a working electronic copy of schedule, using software indicated, and labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.
- C. Construction Schedule Updating Reports: Submit with Applications for Payment.
- D. Weekly Construction Reports: Submit at weekly intervals.
- E. Site Condition Reports: Submit at time of discovery of differing conditions.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Time Frame: Extend schedule from date established for the Notice to Proceed, to date that all submittals are to be reviewed and approved, to date that all materials are on site, to construction start date, to date of final completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- B. Activities: Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 10 days, unless specifically allowed by Owner/Project Manager.
 - 2. Procurement Activities: Include procurement process activities for long lead items and major items, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 - 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
 - 4. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
 - 5. Punch List and Final Completion: Include not more than 14 days for completion of punch list items and final completion.
- C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
 - 1. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use of premises restrictions.
 - f. Provisions for future construction.
 - g. Environmental control.

SECTION 013200 – CONSTRUCTION PROGRESS DOCUMENTATION

D. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (GANTT CHART)

- A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal, Gantt-chart-type, Contractor's construction schedule within 15 days of date established for commencement of the Work.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

2.3 REPORTS

- A. Weekly Construction Reports: Prepare a construction report recording the following information concerning events at Project site:
 - 1. Approximate count of personnel at Project site.
 - 2. Equipment at Project site.
 - 3. Material deliveries.
 - 4. High and low temperatures and general weather conditions, including presence of rain or snow.
 - 5. Accidents.
 - 6. Meetings and significant decisions.
 - 7. Unusual events.
 - 8. Stoppages, delays, shortages, and losses.
 - 9. Meter readings and similar recordings.
 - 10. Emergency procedures.
 - 11. Orders and requests of authorities having jurisdiction.
 - 12. Change Orders received and implemented.
 - 13. Construction Change Directives received and implemented.
 - 14. Services connected and disconnected.
 - 15. Substantial Completions authorized.
- B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

SECTION 013200 – CONSTRUCTION PROGRESS DOCUMENTATION

- 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
- 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
- 3. As the Work progresses, indicate final completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Project Manager Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
 - 1. Post copies in Project meeting rooms and temporary field offices.
 - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

SECTION 013233 - PHOTOGRAPHIC DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Preconstruction photographs.
 - 2. Completion Construction photographs.
- B. Related Requirements:
 - 1. Section 017700 "Closeout Procedures" for submitting photographic documentation as Project Record Documents at Project closeout.

1.2 INFORMATIONAL SUBMITTALS

- A. Key Plan: Submit key plan of Project site / work areas and building with notation of vantage points marked for location and direction of each photograph. Include same information as corresponding photographic documentation.
- B. Digital Photographs: Submit unaltered, original, full-size image files within three days of taking photographs.
 - 1. Digital Camera: Minimum sensor resolution of 8 megapixels.
 - 2. Identification: Provide the following information with each image description in file metadata tag:
 - a. Name of Project.
 - b. Name and contact information for photographer.
 - c. Date photograph was taken.
 - d. Description of vantage point, indicating location and direction (by compass point).
- C. Pre Construction and Completion Construction Photographs: Submit one digital image print of each photographic view within seven days of taking photographs.
 - 1. Format: 8-by-10-inch (203-by-254-mm) digital.
 - 2. Identification: Provide a digital identification with the following information:
 - a. Name of Project.
 - b. Date photograph was taken.
 - c. Description of vantage point or key, indicating location, direction (by compass point), and elevation or story of construction.
 - d. Unique sequential identifier keyed to accompanying key plan.

SECTION 013233 - PHOTOGRAPHIC DOCUMENTATION

1.3 USAGE

- A. Photographs will be used to assure contractor completion of the required scope of work and protection for the contractor against damage that could occur by building occupancy/use during the construction project.
- B. Obtain and transfer copyright usage rights from photographer to Owner for unlimited reproduction of photographic documentation.

PART 2 - PRODUCTS

2.1 PHOTOGRAPHIC MEDIA

A. Digital Images: Provide images in JPG format, with minimum size of 8 megapixels.

PART 3 - EXECUTION

3.1 CONSTRUCTION PHOTOGRAPHS

- A. Photographer: Engage a qualified photographer to take construction photographs.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
 - 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
 - 1. Date and Time: Include date and time in file name for each image.
 - 2. Images: Maintain one set of images available in pdf format accessible for distribution by email for reference.
- D. Preconstruction Photographs: Before starting construction, take photographs of Project site and surrounding areas, including existing items to remain during construction, from different vantage points, as required to view all surfaces impacted by project.
 - 1. Take photographs of existing building to accurately record physical conditions at start of construction.
- E. Final Completion Construction Photographs: Take the same number of photographs from the same view point as preconstruction photographs after date of Substantial Completion for submission as Project Record Documents. Take daily photographs of completed portions of work.

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

B. Related Requirements:

- 1. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
- 2. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
- 3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Engineer's responsive action.
- B. Informational Submittals: Written and graphic information and physical samples that do not require Engineer's responsive action. Submittals may be rejected for not complying with requirements.

1.3 GENERAL SUBMITTAL REQUIREMENTS

A. Provide name of Owner (CBJ/BRH) and CBJ project number on all submittal documents, transmittals or other written communication.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Engineer's Digital Data Files: Electronic copies of digital data files of the Contract Drawings will be provided by Engineer for Contractor's use in preparing submittals.
 - 1. Engineer will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings.
 - a. Engineer makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
 - b. Digital Drawing Software Program: The Contract Drawings are available in AutoCAD.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

SECTION 013300 – SUBMITTAL PROCEDURES

- 1. Coordinate each submittal with fabrication, purchasing, delivery, other submittals, and related activities that require sequential activity.
- 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Engineer's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow 10 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Engineer will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 10 days for review of each resubmittal.
- D. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
 - 1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
 - 2. Name file with submittal number or other unique identifier, including revision identifier.
 - a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., CBJ B18-171-061000.01). The sequential number shall increase for each added submittal/resubmittal (e.g., CBJ B18-171-061000.02).
 - 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Engineer.
 - 4. Transmittal Form for Electronic Submittals: Use from containing the following information:
 - a. Project name. Include Owner name (CBJ/BRH)
 - b. Date.
 - c. Name and address of Engineer.
 - d. Name of Project Manager.
 - e. Name of Contractor.
 - f. Name of firm or entity that prepared submittal.
 - g. Names of subcontractor, manufacturer, and supplier.
 - h. Category and type of submittal.
 - i. Submittal purpose and description.
 - j. Specification Section number and title.
 - k. Specification paragraph number or drawing designation and generic name for each of multiple items.
 - 1. Drawing number and detail references, as appropriate.
 - m. Location(s) where product is to be installed, as appropriate.

SECTION 013300 - SUBMITTAL PROCEDURES

- n. Related physical samples submitted directly.
- o. Transmittal number.
- p. Remarks.
- E. Options: Identify options requiring selection by Engineer.
- F. Deviations: Identify deviations from the Contract Documents on submittals.
- G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with approval notation from Engineer's action stamp.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Engineer's action stamp.

PRODUCTS

1.5 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements:
 - 1. Submit electronic submittals via email as PDF electronic files.
 - a. Engineer will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
 - 2. Mark each copy of each submittal to show which products and options are applicable.
 - 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.

SECTION 013300 - SUBMITTAL PROCEDURES

- g. Notation of coordination requirements.
- 4. Submit Product Data before or concurrent with Samples.
- 5. Submit Product Data in the following format:
 - a. PDF electronic file.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
 - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Notation of coordination requirements.
 - d. Notation of dimensions established by field measurement.
 - e. Relationship and attachment to adjoining construction clearly indicated.
 - 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 11 inches x 17 inches.
 - 3. Submit Shop Drawings in the following format:
 - a. PDF electronic file.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
 - 1. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of applicable Specification Section.
 - 2. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Engineer will return submittal with options selected.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Submit product schedule in the following format:
 - a. PDF electronic file.

SECTION 013300 – SUBMITTAL PROCEDURES

- F. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."
- G. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures.
- H. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."
- I. Maintenance Data: Comply with requirements specified in Section 017823 "Operation and Maintenance Data."
- J. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

EXECUTION

1.6 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Engineer.
- B. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

1.7 ENGINEER'S ACTION

- A. General: Engineer will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Engineer will review each submittal, make marks to indicate corrections or revisions required, and return it. Engineer will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- C. Informational Submittals: Engineer will review each submittal and will not return it, or will return it if it does not comply with requirements. Engineer will forward each submittal to appropriate party.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Engineer's action on Contractor's submittals, applications, and requests, "approved" is limited to Engineer's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Engineer. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space identified / available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

SECTION 014200 - REFERENCES

1.3 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.
 - 1. IAPMO International Association of Plumbing and Mechanical Officials; www.iapmo.org.
 - 2. ICC International Code Council; www.iccsafe.org.
 - 3. ICC-ES ICC Evaluation Service, LLC; www.icc-es.org.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Requirements:
 - 1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.
 - 2. Section 015221 Special Safety Requirements (ICRA)

1.2 USE CHARGES

A. Water and Electrical Power from Existing System: Water and Power from Owner's existing water and power systems are available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

PART 2 - PRODUCTS - Not Used

PART 3 - EXECUTION

- A. Sanitary Facilities: Use of Owner's existing toilet facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- B. Parking: Contractor personnel are to park within the gravel portion of the general parking lot located adjacent to the Juneau Medical Center building.
- C. Materials Staging: Materials can be staged within gravel portion of the general parking lot. Exterior storage and storage within the building is limited.
- D. All trash and debris is to be removed from the project site at the end of every work shift.
- E. Existing Elevator Use: Use of Owner's existing elevators will be permitted, provided elevators are cleaned and maintained in a condition acceptable to Owner.
 - 1. Do not load elevators beyond their rated weight capacity.
- F. Existing Stair Usage: Use of Owner's existing stairs will be permitted, provided stairs are cleaned and maintained in a condition acceptable to Owner.
- G. Existing Corridor Usage: No construction reated materials of any kind are to be staged within any of the building corridors. Only "sticky" walk-off mats can be left in corriors, and only if securely attached to the floor.

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

3.2 SECURITY AND PROTECTION OF EXISTING FACILITIES

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, finishes, utilities, and other improvements at the Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
- B. Protection of Existing Server Equipment: Coordinate all CONTRCTOR activities, particularly within Server Room 2402B and Server Room 2425, to prevent damage to the existing server equipment or interruption to any server equipment functions. Extreme care must be taken to prevent existing wires from being pulled or dislodged from connection points. Prior to the start of work, coordinate with BRH IT Staff to review the existing wire management in both server rooms. Review and implement methods to secure loose wires that might become damaged during construction activities.

SECTION 015220 - SECURITY

PART 1 – GENERAL

1.1 SECURITY PROGRAM

A. The CONTRACTOR shall:

- 1. Protect WORK, existing premises, and Using Agency's operations from theft, vandalism, unauthorized entry, and unauthorized exiting from secure areas.
- 2. Initiate security efforts in coordination with Using Agency's existing security program at initialization of Project mobilization.
- 3. Maintain security efforts throughout construction period until Final Completion.
- 4. Do NOT prop open server room doors at any time, for any reason.

1.2 PERSONNEL IDENTIFICATION

- A. At the discretion of the OWNER, the CONTRACTOR shall:
 - 1. Require each person authorized to enter premises to possess and visibly display an identification card.
 - 2. Require return of cards from all individuals when they are no longer involved with WORK at the Project site.
- B. Identification cards shall be provided by the Using Agency and will include personal photograph; name, title and employer, and assigned number. Identification cards will be issued only after each individual has completed a special training program administered by Bartlett Regional Hospital. The program is anticipated to take less than one hour, but is mandatory.

1.3 RESTRICTIONS

A. All personnel employed on the Project site by the CONTRACTOR, Subcontractors, Suppliers, installers and other entities engaged in WORK shall strictly adhere to the security, safety, confidentiality, and hospital compliance program requirements depicted in Section 015221 – Special Safety Requirements (ICRA).

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

SECTION 015221A – SPECIAL SAFETY REQUIREMENTS

PART 1 – GENERAL

1.1 SAFETY PROGRAM

A. General:

- 1. The safety of bidders, the CONTRACTOR, their work forces in total, the USING AGENCY's personnel, patients and the public is a major concern of the OWNER and the PROJECT MANAGER. To ensure Project and campus wide safety, the CONTRACTOR shall carefully adhere to the requirements outlined within this section and within any attached BRH policies.
- 2. CONTRACTOR shall employ a safety program to insure that CONTRACTOR's personnel and all personnel of the Subcontractors, Suppliers, Installers and material workers are trained and kept abreast of hospital safety requirements. In addition to the safety requirements enforced by code or jurisdictional entities, the CONTRACTOR's safety program shall also address fire safety and deployment plans for the Project site, response to accidental release of hazardous materials, breach of infection containment barriers, and general emergency response.
- 3. CONTRACTOR's safety program will be provided to the PROJECT MANAGER, in writing, prior to commencement of WORK. Plans shall be periodically revised in response to issues that may arise during the course of the WORK. Such revisions shall be provided promptly to the PROJECT MANAGER.

B. The CONTRACTOR shall;

- 1. Abide by all applicable safety practices and requirements, irrespective of their origins.
- 2. Attend safety related meetings as may be required by the OWNER or PROJECT MANAGER.
- 3. CONTRACTOR shall employ a safety program to insure that CONTRACTOR's personnel and all personnel of the Subcontractors, Suppliers, Installers and material workers are trained and kept abreast of hospital safety requirements. Maintain program throughout construction period until Final Completion.

1.2 SAFETY STANDARDS

- A. Applicable safety related standards promulgated by safety or code enforcement agencies, such as but not limited to; AK-DEC, OSHA, Building Officials and Fire Marshal's Office representatives.
- B. Safety/guidelines and policies established by the Department of Infection Control/Safety/Facilities of Bartlett Regional Hospital covering Infection Control for Construction and Renovation. (See BRH Policy at the end of this section.)
- C. Safety guidelines and policies established by Bartlett Regional Hospital covering Interim Life Safety Plan. (See BRH Policy at the end of this section.)
- D. Safety Requirements required by the Contract Documents.

SECTION 015221A – SPECIAL SAFETY REQUIREMENTS

1.3 SAFETY PROCEDURES

- A. In addition to devices required by safety or code enforcement agencies, the CONTRACTOR shall employ safety and containment devices (barricades, temporary separation/isolation walls, temporary directional signage, warning signs, etc.) at all locations where the public, patients or hospital staff may have access to, or mistakenly venture into, an area of active construction or an area where material / equipment items may be stored or staged. The PROJECT MANAGER will have the final determination as to the locations and the extent of the required safety containment devices and temporary directional / warning signage.
- B. As determined by the PROJECT MANAGER, and where conditions necessitates the construction of temporary exit routes or temporary exit detours, the CONTRACTOR shall develop and/or construct such routes to the standards of the Contract Documents, or the enforcement agency. The CONTRACTOR shall provide and post temporary directional and warning signs at all temporary exit routes. Such routes and all temporary signage shall be approved by the PROJECT MANAGER prior to putting them into use.
- C. Temporary signage shall consist of pre-printed 8-1/2x11 inch standard paper stock attached to walls or doors with removable painters tape. No tacks, pins or staples are to be used in conjunction with any temporary signage.
- D. CONTRACTOR shall not remove, block or otherwise obscure any of the existing permanent directional signage without specific written direction by the PROJECT MANAGER. CONTRACTOR shall cooperate with and assist the USING AGENCY in the establishment and maintenance of temporary "user oriented" direction signage.
- E. Permanent directional signage that has been disrupted or damaged during the course of construction shall be immediately repaired or replaced by the CONTRACTOR.

1.4 SECURITY SERVICE

A. The CONTRACTOR shall;

- Provide all security personnel and programs as described in Specification Section 015220 Security.
- 2. Cooperate with the USING AGENCY, the security forces employed by the USING AGENCY and the PROJECT MANAGER to insure the security and safety of the Project, the public, patients and BRH staff, and all other facilities on the hospital campus.

SECTION 015221A – SPECIAL SAFETY REQUIREMENTS

1.5 RESTRICTIONS WITHIN ACTIVE CONSTRUCTION AREAS

A. All personnel employed on the Project site by the CONTRACTOR, Subcontractors, Suppliers, installers and other entities engaged in WORK shall strictly adhere to the security, safety, confidentiality, and hospital compliance program requirements depicted within this section.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

Bartlett Regional Hospital

Title: ICRA: INFECTION CONTROL FOR CONSTRUCTION AND RENOVATION

Department: Infection Control/Safety/Facilities

Original Date: 07-02 Author: Infection Control

PURPOSE:

To establish a process for the identification and reduction of risk from airborne transmission of infectious agents during construction, demolition, renovation, and repair on the Bartlett Regional Hospital Campus.

DEFINITIONS:

- A. **ICRA:** Infection Control Risk Assessment. Analysis of a construction, demolition, or renovation project to establish infection risk and control by a multidisciplinary group designated for that purpose.
- B. Infection Control Permit: A permit issued by Infection Control for construction and renovation projects that are Class III or above as determined by the Infection Control Risk Group Matrix. (in the Infection Control Risk Assessment Packet, Appendix C)
- C. **ICRAC:** Infection Control Risk Assessment Committee. An ad hoc subcommittee of the BRH Infection Control Committee tasked with development, oversight, and enforcement of this policy.
- D. **HEPA Filter:** High efficiency particulate air filters. (99% of 0.3-micron size particles)
- E. **HVAC:** Heating, Ventilation, Air-conditioning. (Air-handling unit.)
- F. CRP: Construction and Renovation Policy. (This policy.)

POLICY:

- A. An Infection Control Risk Assessment (ICRA) will be performed for every construction, demolition, and renovation project on the BRH campus, including site work (utilities, landscaping, etc) even when no building is being constructed or renovated.
- B. Bartlett Regional Hospital requires any subcontractor, sub-subcontractor, vendor, employee, or agent to be bound by these requirements. Before any demolition or construction on-site begins, the contractor and contractor's employees will attend mandatory training sessions provided by a Bartlett Regional Hospital Safety or Infection Control representative. Course objectives will be distributed at class.
- C. An Infection Control Permit (see the Infection Control Risk Assessment Packet Appendix C) will be issued by the ICRAC and posted at the work-site as appropriate for the duration of the project, as indicated by the ICRA.
- D. Changes to the ICRA may be made by the ICRAC at any time during the project. Changes will be communicated to the Construction Manager or designee.
- E. Bartlett Regional Hospital's Safety Officer or the ICRAC may modify performance requirements for certain activities. A modification made by BRH personnel does not relieve the contractor of compliance with proper infection control procedures.

- F. When required by the Infection Control Permit, HEPA equipped filtration machines shall provide air flow into construction area not less than 100 FPM at barricade entrances with doors fully open. HEPA equipped air filtration machines shall be connected to normal power and ganged to a single switch for emergency shutoff and shall run continuously. In the event of a power failure and no back-up power is immediately available, work will be stopped until power becomes available.
- G. Documentation of the ICRA process will be maintained by the Construction Manager or designee.
- H. Regular reports will be provided to the Infection Control Committee by a representative of the ICRAC.

PROCEDURES:

A. Responsibilities During Project Planning

- A.1. An interdisciplinary team including architects, construction managers, contractors, department personnel, the Infection Control Coordinator, and Safety Officer will evaluate any construction project from design through completion for infection control concerns.
- A.2. The Infection Control Coordinator will be involved in the design phase of any project. The design and function considerations for infection control are listed in Appendix A. These considerations are for the duration of the project, as well as considerations for the infection control issues for the finished project. The Construction Manager or designee will contact the Infection Control Coordinator for obtaining input on the project.
- A.3. Each project will have an Infection Control Risk Assessment (ICRA) performed during the planning phase of the project. Projects in Class III, III/IV, or IV require an Infection Control Permit to be posted at the site for the duration of the project. (Appendix C)
- A.4. Construction measures required by the ICRA will be communicated to the contractors by the Construction Manager or designee during the bidding phase of the project. All contractors and contract construction personnel be responsible for maintaining and complying with the general and class specific infection control and safety practices for the project.

B. Responsibilities During the Active Construction Phase

- B.1. The Construction Manager or designee will perform a Safety and Infection Control Risk Assessment for every day that there is work on the site (Appendix B). Unsafe conditions will be corrected immediately and corrections documented on the form. The Construction Manager or designee is responsible for oversight and documentation of this process.
- B.2. As a quality control measure, a member of the ICRAC will review monitoring reports compiled by the Project Manager for each project of Class III or greater. The ICRAC will receive updates via written reports, emails, or meetings as circumstances warrant. The Construction Manager or designee will be notified immediately to correct any unsafe conditions.
- B.3. The contractor shall be required to take immediate action to correct all deficiencies.
- B.4. The ICRAC has the authority to stop construction for any breach in the infection control practices, or for any patient safety concern related to infection and construction. This will be done through the Construction Manager or designee.
- B.5. Failure of the contractor to promptly correct such deficiencies will result in corrective action taken by CBJ and BRH Construction Management per project documents.
- B.6. The Contractor will notify the Construction Manager or designee for any assistance with medical waste, work in negative pressure areas, or any concerns involving patients or patient care areas.
- C. General Infection Control Practices for All Construction and Renovation Projects

- C.1. Construction activities causing disturbance of existing dust, or creating new dust, must be conducted in tight enclosures cutting off any flow of particles into patient areas.
- C.2. Construction areas will have dust mops, wet mops, brooms, buckets, and clean rags for wiping fine dust from floors and surfaces in adjacent areas.
- C.3. Walk-off (sticky) mats shall be used outside of every construction entrance. Any dust outside the barrier shall be cleaned up immediately using a HEPA-filtered vacuum or wet mop.
- C.4. Debris from the construction site will be removed with carts that are covered in a manner that does not allow the escape of dust.
- C.5. Any ceiling tiles that are moved (even for visualization) outside of the construction barrier will be replaced immediately when unattended.

C.6. Barriers

- C.6.1. Closed door with masking tape applied over the frame and door is acceptable for projects that can be contained within a single room.
- C.6.2. Construction, demolition or reconstruction not capable of containment within a single room must have the following barriers erected:
- C.6.2.1. Small, short duration projects generating minimal dust may use fire-rated plastic sheeting that extends from floor to ceiling. Seams must be sealed with tape to prevent dust and debris from escaping and have at least 2-foot overlapping flaps for access to entry.
- C.6.2.2. Any project generating moderate to high levels of dust or of more than short duration must require rigid dust-proof, and fire-rated barrier walls (e.g. drywall) with caulked seams. An interim plastic dust barrier may be required to protect the area while the rigid impervious barrier is being constructed.
- C.6.2.3. Barriers are required at penetrations of ceiling envelopes, chases and ceiling spaces to stop movement of air and debris.
- C.6.2.4. Large dusty projects require an anteroom or double entrance vestibule for workers to remove protective clothing or vacuum off existing clothing.
- C.7. HEPA-filtered negative pressure units will be run continually during the course of the project (24 hours per day).

D. Performing An Infection Control Risk Assessment

- D.1. Each project will have an Infection Control Risk Assessment done during the programming phase of the project. The results will be communicated with the architect and contractor. (See ICRA Packet, Appendix C).
- D.2. Class III and higher projects require an Infection Control Permit before construction begins. (ICRA Packet, Appendix C)

REFERENCES:

Bartley, J., ed. (1999). <u>APIC Infection Control Toolkit Series: Construction and Renovation</u>. Washington, DC: Association for Professionals in Infection Control and Epidemiology, Inc.

Centers for Disease Control and Prevention, Healthcare Infection Control Practices Advisory Committee. (2001). <u>Draft</u> Guideline for Environmental Infection Control in Healthcare Facilities.

Comprehensive Manual on Accreditation of Hospitals (2001). Oakbrook, IL.: Joint Commission on Accreditation of Hospitals and Healthcare Organizations: 2001.

Davis, S. (2001). "Don't Wait for Dust to Settle on Patient Risk." In Environment of Care Leader (6) 11. (May 21, 2001).

Approval/Review/Revision						
Date:	Signature:	Date:	Signature:	Date:	Signature:	
11/1/02	Dr. Hunter-Joerns					
8/3/04	Dr. Hunter-Joerns					

2/07/06	Dr. Hunter-Joerns		
2/21/08	Dr. Hunter-Joerns		
8/2/11	Dr. Hunter-Joerns		

APPENDIX A:

Construction Design and Function Considerations for Environmental Infection Control

- A. Location of sinks and handwashing product dispensers.
- B. Types of faucets (aerated vs. non-aerated, and type of faucet e.g. wrist blades, knee, foot, or infrared controlled).
- C. Air-handling systems engineered for optimal performance and easy maintenance and repair.
- D. Air changes per hour (ACH) and pressure differentials to accommodate special patient care areas.
- E. Location of fixed sharps containers.
- F. Types of surface finishes (non-porous vs. porous).
- G. Well-caulked wall with minimal seams.
- H. Location of adequate storage and supply areas.
- I. Appropriate location of medicine preparation areas (e.g. >3ft. from a sink).
- J. Appropriate location and type of ice machines.
- K. Appropriate materials for sinks and wall coverings.
- L. Appropriate traffic flow (no "dirty" movement through "clean" areas).
- M. Isolation rooms with anterooms as required.
- N. Appropriate flooring (e.g. seamless floors in dialysis units).
- O. Sensible use of carpeting (e.g. no carpeting in special care areas or areas likely to become wet.)
- P. Properly engineered areas for linen services and solid waste management.
- Q. Location of main generator to minimize risk of system failure from flooding or other emergency.
- R. Installation guidelines for gypsum wallboard.

From: Centers for Disease Control (2001) Guidelines for Environmental Infection Control in Healthcare Facilities (draft).

APPENDIX B:

Safety and Infection Control Risk Assessment T	ssment Too	Risk A	Control	Infection	and	Safety
--	------------	--------	---------	-----------	-----	--------

•			
Project No.	SERVER ROOM FIRE PROTECTION SYSTEM	Date	Time

DAILY INFECTION CONTROL MONITOR:

Standard	Yes	No	Corrected? / Comments
A. Construction Barricades:			
Barricades sealed, no penetrations			
Walk-off mats at all exits			
Barricade doors have closers			
Door frames gasketed, close and seal properly			
Adjacent ceiling areas intact			
Adjacent floors clean, no dust tracked			
B. Negative Air:			
Negative pressure at barricade entrance			
All windows and doors closed behind barricade			
Negative air machines running, filters clean, dis-			
charge hoses intact			
Demonstrated use of appropriate equipment to			
prevent airborne particulate matter: this includes			
HEPA filtration units, HEPA vacuum equipment,			
and continuous use of exhaust fans			
No construction activity within 25 feet of existing fresh air intake			
C. Jobsite:			
Project area clean, debris removed daily			
Debris removed in suitable closed containers			
No signs of pests			
No signs of water leakage			
D. Occupied Areas:			
Work authorized and scheduled			
Sheet plastic barricade in place and properly			
sealed			
Surrounding area clean			
Patient care equipment and supplies removed from			
construction area			
Ceiling tiles replaced when not being accessed (if			
occupied area, adjacent patient doors are closed)			

015221B ICRA Infection Control for Construction & Renovation DAILY SAFETY MONITOR:

Standard	Yes	No	Corrected? / Comments
A. General Safety:			
Contract workers wearing required identification			
Construction personnel wearing required PPE (e.g.			
hardhat, goggles, coveralls, etc.)			
Construction area secure (e.g. barriers adequate to prevent entry of unauthorized persons)			
prevent entry or unauthorized persons)			
Construction personnel following safe work prac-			
tices (e.g. ladder safety, no smoking, trip and fall			
hazards, etc.)			
Power secured at end of each day			
Extension cords grounded, in good condition			
B. Exits			
Exits provide free and unobstructed access			
Alternate egress established and workers received			
training			
Negative air machines running, filters clean, dis-			
charge hoses intact			
C. Fire Equipment:	ı		
Fire alarms, detection, and suppression systems operational			
Additional fire equipment and training provided for			
personnel			
D. Fire Safety:			
No smoking policy implemented			
Minimum of two fire drills per shift per quarter			
Area free of storage, housekeeping materials, food			
waste, and debris to reduce flammable and com-			
bustible fire load of building			
Additional comments and observations:			
Inspector Signature:			

INFECTION CONTROL RISK ASSESSMENT PACKET

An Infection Control Risk Assessment (ICRA) will be performed by the Construction Manager or designee for every construction, demolition, and renovation project on the Bartlett Regional Hospital campus, including site work (utilities, land-scaping, etc.) even when no building is being constructed or renovated.

1. Step #1: Using the following table, determine the <u>type</u> of construction activity and <u>circle</u> Type A, B, C, or D.:

The construction activity types are defined by the amount of dust generated, the duration of the activity, and the amount of shared HVAC systems.

Contact Infection Control if any activity is questionable under these guidelines.

Circle one **Type** below:

Туре А	Inspection and Non-Invasive Activities Includes, but is not limited to: removal of ceiling tiles for visual inspection limited to 1 tile per 50 square feet painting (but not sanding) wall covering, electrical trim work, minor plumbing, and activities which do not generate dust or require cutting of walls or access to ceilings other than for visual inspection	
Туре В	Small Scale, Short Duration Activities Which Create Minimal Dust Includes, but is not limited to: ☐nstallation of telephone and computer cabling ☐ access to chase spaces ☐ cutting of walls or ceiling where dust migration can be controlled	
Type C	Work That Generates a Moderate to High Level of Dust or Requires Demolition or Removal of Any Fixed Building Components or Assemblies Includes, but is not limited to: • sanding of walls for painting or wall covering □ removal of floor coverings, ceiling tiles and casework □ new wall construction □ minor duct work or electrical work above ceilings □ major cabling activities □ any activity which cannot be completed within a single workshif	
Type D	Major Demolition and Construction Projects Includes, but is not limited to: ☐ activities that require consecutive work shifts ☐ lequires heavy demolition or removal of a complete cabling system ☐ new construction	_

2. Step # 2.: Using the following table, identify the Infection Control Risk Group or Groups that will be affected by the construction activity, and *circle* Group 1, 2, 3, or 4.

*Circle the appropriate **Risk Group(s)** below:

Group 1	Group 2	Group 3	Group 4
Low Risk	Medium Risk	High Risk	Highest Risk
☐ Office Areas	☐ Cafeteria	☐ Emergency Depatr-	☐ Critical Care Unit
☐ Public Areas	Patient care areas, inp-	ment	Special Care Nursery
(except when associated	tient and outpatient,	☐ Radiology	Operating Rooms,n-
with a higher risk area)	except as noted in	☐ PACU	cluding C-Section
☐ All other nonpatient	Groups 3 and 4.	☐ Same Day Surgery	Rooms
work areas (e.g. facili-		☐ Laboratory	☐ Central Sterile Supply
ties, stores)		☐ Kitchen	☐ Endoscopy
☐ Behavioral Health bits		☐ Obstetrics	☐ Infusion Therapy
		☐ Newborn Nursery	☐ Pharmacy Admixture
		☐ Parmacy	☐ Negative Pressure Isœl-
		☐ PT: Tub and Tre tment	tion Rooms
		Rooms	

3. Step # 3: Determine the Level of Infection Control Activity required by *matching* the Construction **Type** with the Risk **Level** using the matrix below.

Circle one Class below:

	Construction Activity-Infection Control Matrix						
	Construction Activity						
Risk Level	Type A	Type B	Type C	Type D			
Group 1	I	II	II	III/IV			
Group 2	I	II	III	IV			
Group 3	I	II	III/IV	IV			
Group 4	II	III/IV	III/IV	IV			

^{4.} Step # 4. Obtain an Infection Control Permit:

- An Infection Control Permit and approval will be required when the Construction Activity and Risk Level indicate Class III or higher (shaded areas).
- This permit will remain posted at the worksite for the duration of the project.
- This permit will be returned to the Construction Manager or designee at the completion of the project.

5. Step # 5. Identify Areas Surrounding Project Area

Identify the areas surrounding the project area, assessing potential impact. *

Identify Unit Below			Identify Lateral Unit	Identify Unit Behind	Identify Unit Front
Identify Risk Group: 1 2 3 4	Identify Risk Group 1 2 3 4				
Potential Impact? Yes No	Potential Impact? Yes No	Potential Impact? Yes No	Potential Impact? Yes No	Potential Impact? Yes No	Potential Impact? Yes No
See comments	See comments	See comments	See comments	See comments	See comments

See comments	See comments	See comments	See comments	See comments	See comments	
Comments*				•		_
					*note: Anothe	er aspect of
"Areas Surroundi	ng Project Area" ai	re any nearby build	ings where patients	s are present that co		
	0 0	on, excavation, four		•	oute of in the puni	01 010 111
<i>aust</i> c omm. g mom	current acmond	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		., 4110 5100 11 5111		
6. Step # 6. Ident	ify specific site of	activity, e.g.: patie	ent rooms, medica	tion room, etc.		
	J					
7 Sten # 7 Wo	rk hours: Can or	will the work be	done during non-	natient care hour	s?	
Yes		No	•	patient dare near	0.	
Other			or applicable		_	

Infection Control Permit

Bartlett Regional Hospital Infection Control Construction Permit							
		<u>.</u>			Permit No:		
Loca	tion o	f Construction:		Projec	ct Start Date:		
Proje	ct Co	ordinator		Estimated Duration:			
Cont	ractor	Performing Work		Permi	t Expiration Date:		
Supe	rvisor			Telep			
YES	NO	CONSTRUCTION ACTIVITY	YES	NO	INFECTION CONTROL RISK GROUP		
		TYPE A: Inspection, non-invasive activity			GROUP 1: Least Risk		
		TYPE B: Small scale, short duration, moderate to high levels			GROUP 2: Medium Risk		
		TYPE C: Activity generates moderate to high levels of dust, requires greater 1 work shift for completion			GROUP 3: Medium/High Risk		
		TYPE D: Major duration and construction activities Requiring consecutive work shifts			GROUP 4: Highest Risk		
CLAS	S I	 Execute work by methods to minimize raising dust from construction operations. Immediately replace any ceiling tile displaced for visual inspection. 	3. 1	Minor Der	nolition for Remodeling		
CLASS II 1. 2. 3. 4. 5.		Provides active means to prevent air-borne dust from dispersing into atmosphere Water mist work surfaces to control dust while cutting. Seal unused doors with duct tape. Block off and seal air vents.		 Contain construction waste before transport in tightly covered containers. Wet mop and/or vacuum with HEPA filtered vacuum before leaving work area. Place dust mat at entrance and exit of work area. Remove or isolate HVAC system in areas where work is being performed. 			
Da	1. Obtain infection control permit before construction begins. 2. Isolate HVAC system in area where work is being done to prevent contamination of the duct system. 3. Complete all critical barriers or implement control cube method before construction begins. 4. Maintain negative air pressure within work site utilizing HEPA equipped air filtration units. 5. Do not remove barriers from work area until complete		7. 8. 1 9. 6 10. 6 11. 1	Vacuum work with HEPA filtered vacuums. Wet mop with disinfectant Remove barrier materials carefully to minimize spreading of dirt and debris associated with construction. Contain construction waste before transport in ightly covered containers. Cover transport receptacles or carts. Tape covering. Remove or isolate HVAC system in areas where work is being performed/			
Class	Class IV 1. Obtain infection control permit before construction begins. 2. Isolate HVAC system in area where work is being done to prevent contamination of duct system. 3. Complete all critical barriers or implement control cube method before construction begins.		 All personnel entering work site are required to wear shoe cover Do not remove barriers from work area until completed project oughly cleaned by the Environmental Service Dept. Vacuum work area with HEPA filtered vacuums. Wet mop with disinfectant. 				
Da	ite	4. Maintain negative air pressure within work site utilizing		Remove barrier materials carefully to minimize spreading of dirt ar			
6. Construct anteroom and require all personnel to pass through this room so they can be vacuumed using a HEPA		12. (1 1 2				
Additio	onal Req	uirements:					
			ı				
Date	_	Initials	Date		xceptions/Additions to this permit		



Bartlett Regional Hospital

MAINTENANCE/CONSTRUCTION IN PROCESS

KEEP DOOR CLOSED

at	for questions
Con	tact the Project Manager
Per	Intection Control Policy

SECTION 016000 – PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling and comparable products.

B. Related Requirements:

1. Section 012500 "Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.3 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Engineer will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

SECTION 016000 – PRODUCT REQUIREMENTS

- a. Form of Approval: As specified in Section 013300 "Submittal Procedures."
- b. **Use product specified** if Engineer does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.

1.4 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

- 1. Schedule delivery to minimize storage time at Project site and to prevent overcrowding of construction spaces.
- 2. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
- 3. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

C. Storage:

- 1. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation / rust.
- 2. Protect UV sensitive materials from exposure to sunlight, except to extent necessary for period of installation and concealment.
- 3. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
- 4. Protect stored products from damage and liquids from freezing.

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
 - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 - 2. Where products are accompanied by the term "as selected," Engineer will make selection.
 - 3. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Product Selection Procedures:

SECTION 016000 – PRODUCT REQUIREMENTS

 Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Engineer will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Engineer may return requests without action, except to record noncompliance with these requirements:
 - 1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 - 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Installation of the Work.
 - 3. Cutting and patching.
 - 4. Progress cleaning.
 - 5. Protection of installed construction.

B. Related Requirements:

- 1. Section 011000 "Summary" for limits on use of Project site.
- 2. Section 017700 "Closeout Procedures" for submitting Project Record Documents and final cleaning.

1.2 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Structural Elements: Do not cut or patch structural elements.
 - 2. Operational Elements: Do not cut and patch operating elements and related components.
 - 3. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Owner's / Project Manager's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Owner / Project Manager for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Examine walls and ceilings for suitable conditions where products and systems are to be installed
 - 2. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- B. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 013100 "Project Management and Coordination."

3.3 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

- C. Conduct construction operations so no part of the Work is subjected to damaging operations.
- D. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- G. Attachment: Provide attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Owner/Project Manager.
- H. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.4 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Protection: Protect in-place construction during cutting and patching to prevent damage.
- C. Adjacent Occupied Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- D. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, putty, and similar materials from adjacent finished surfaces.

3.5 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
 - 1. Remove all materials and debris from the work areas on a daily basis.
- B. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials

- specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- C. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- D. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.
- E. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- F. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period.

3.6 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
 - 5. Repair of the Work.

B. Related Requirements:

- 1. Section 013233 "Photographic Documentation" for submitting final completion construction photographic documentation.
- 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
- 3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 MAINTENANCE/REPLACEMENT MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items indicated.

1.4 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 5 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation and similar final record information.

- 2. Submit closeout submittals specified in individual Sections, including specific warranties, and similar documents.
- 3. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to BRH Facilities Manager Marc Walker. Label with manufacturer's name and model number where applicable.
 - a. Obtain Facility Manager's signature for receipt of submittals.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 5 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Terminate and remove temporary facilities from Project site, construction tools, and similar elements.
 - 2. Complete final cleaning requirements, including touchup painting.
 - 3. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 5 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Project Manager will either proceed with inspection or notify Contractor of unfulfilled requirements. Project Manager will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Engineer, that must be completed or corrected before certificate will be issued.
 - 1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.
 - 2. Results of completed inspection will form the basis of requirements for final completion.

1.5 FINAL COMPLETION PROCEDURES

- A. Preliminary Procedures: Before requesting final inspection for determining final completion, complete the following:
 - 1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 - 2. Certified List of Incomplete Items: Submit certified copy of Engineer's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Engineer. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 - 3. Instruct Owner's personnel in maintenance of products.
- B. Inspection: Submit a written request for final inspection to determine acceptance. On receipt of request, Project Manager will either proceed with inspection or notify Contractor of unfulfilled requirements. Project Manager will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
 - 1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected. The Owner anticipates one substantial completion

inspection and one final inspection. Additional inspections required due to incomplete work will be charged to the contractor through a credit by change order.

1.6 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties with the operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 - 1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, and grounds, in areas disturbed by construction activities, free of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove spills, stains, and other foreign deposits.
 - c. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - d. Wash finish walls, ceilings and floors affected by work including newly installed materials.
 - e. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
 - f. Remove labels that are not permanent.
 - g. Leave Project clean and ready for occupancy.

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Restore damaged construction and permanent facilities used during construction to specified condition.
 - 1. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
 - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.

END OF SECTION 017700

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - Product maintenance manuals.

1.2 CLOSEOUT SUBMITTALS

- A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Owner/Engineer will comment on whether content of operations and maintenance submittals are acceptable.
- B. Format: Submit operations and maintenance manuals in the following format:
 - 1. PDF electronic file. Assemble each manual into a composite electronically indexed file. Submit on digital media acceptable to Engineer.
 - a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.
 - b. Enable inserted reviewer comments on draft submittals.
- C. Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Engineer will return copy with comments.
 - 1. Correct or revise each manual to comply with Engineer's comments. Submit copies of each corrected manual within 7 days of receipt of Engineer's comments and prior to commencing demonstration and training.

PART 2 - PRODUCTS

2.1 REQUIREMENTS FOR MAINTENANCE MANUALS

- A. Directory: Prepare a single, comprehensive directory of maintenance data and materials.
- B. Title Page: Include the following information:
 - 1. Subject matter included in manual.
 - 2. Name and address of Project.
 - 3. Name and address of Owner.

SECTION 017823 - OPERATION AND MAINTENANCE DATA

- 4. Date of submittal.
- 5. Name and contact information for Contractor.
- 6. Name and contact information for Project Manager.
- 7. Name and contact information for Engineer.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
- D. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
 - 1. File Names and Bookmarks: Enable bookmarking of individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Configure electronic manual to display bookmark panel on opening file.

2.2 PRODUCT MAINTENANCE MANUALS

- A. Content: Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.
- C. Maintenance Procedures: Include manufacturer's written recommendations and the following:
 - 1. Inspection procedures.
 - 2. Types of cleaning agents to be used and methods of cleaning.
 - 3. List of cleaning agents and methods of cleaning detrimental to product.
 - 4. Schedule for routine cleaning and maintenance.
 - 5. Repair instructions.
- D. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- E. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

SECTION 017823 - OPERATION AND MAINTENANCE DATA

В.	Comply with Section 017700 "Closeout Procedures"	" for schedule for submitting operation and
	maintenance documentation.	

END OF SECTION 017823

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
 - 1. Record Drawings.
- B. Related Requirements:
 - 1. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit ONE set of marked-up record prints.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised Drawings as modifications are issued.
 - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Record data as soon as possible after obtaining it.
 - 2. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 - 3. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 - 4. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.
- B. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Engineer's and Project Manager's reference during normal working hours.

END OF SECTION 017839

PART 1-GENERAL

1.1 RELATED DOCUMENTS

- A. General provisions of the Contract, including General and Supplementary Conditions.
- B. Contract drawings.

1.2 SUMMARY

- A. Bulk sampling has identified the following asbestos containing materials (ACM) in Bartlett Regional Hospital (BRH) that will impact this project:
 - 1. Spray-on fireproofing and overspray on beams, ceilings, steel pan deck, and equipment in the above-ceiling space of original construction in the building; and
 - 2. Gypsum wallboard mud on wall and ceiling systems in original construction of the building.
- B. The intent of the abatement portion of the overall project is to:
 - 1. Create a 24" x 24" opening in the ACM gypsum wallboard ceiling of E1131. Opening shall be cut from center of ceiling joist to center of adjacent ceiling joist with neat rectangular cuts to facilitate future repair of the ceiling.
 - 2. Remove all ACM fireproofing and overspray on the steel pan deck of the overlying room (E2425) and any equipment or utilities within the projected 24" x 24" area between the ceiling opening and the steel pan deck above it.
 - 3. Isolate the cleaned area from the remaining ceiling space by creating a semi-permanent enclosure that is sealed to the underside of the pan deck and the <u>upper</u> side of the gypsum ceiling board. The enclosure shall be constructed of fire-proof reinforced polyethylene sheeting of a minimum thickness of 6 mils. Adhesion to the steel pan deck shall be sufficient to withstand proximity to the wet coring drill.
 - 4. The finished product shall provide a clean work space that will allow non-certified workers access to the floor pan while coring through the floor of E2425 (above) into the ceiling of E1131. The enclosure shall be constructed in a manner that allows it to remain in place while the ceiling is repaired or a ceiling hatch is installed.
- C. The abatement project includes all material, labor, equipment and other related costs for:
 - coordinating with prime contractor to determine the location and timing for abatement.
 - 2. mobilizing (including moving all plant and equipment onto the site; providing necessary project utilities or improving existing utilities as necessary, arranging for approved storage areas, issuing and posting all notices, and submitting all submittals),
 - 3. installing all necessary critical barriers to establish non-permanent asbestos control areas to isolate the various abatement areas,
 - 4. completing all abatement elements as described in Paragraph C. above,
 - 5. cleaning all surfaces and spaces within the confines of the asbestos control areas,
 - 6. providing air monitoring, including appropriate elements summarized in <u>Asbestos Air Monitoring</u> in DEFINITIONS below, and in accordance with PART 3 EXECUTION of this section,
 - 7. providing lab analysis for required air monitoring,
 - 8. disposing of ACM and related demolition debris in accordance with these contract documents,
 - 9. removing the non-permanent asbestos control areas,
 - 10. general cleanup and demobilization.

D. Contract drawings illustrate the locations where the above-described work is necessary and allow quantification for the bidding purposes.

1.3 COORDINATION AND TIMING OF ABATEMENT ACTIVITIES

- A. Abatement subcontractor shall coordinate timing of work with General Contractor, who shall coordinate with Owner to select a time frame for abatement that minimizes inconvenience for BRH staff.
- B. Work shall take place in an actively used mechanical room that requires access by BRH workers. The maximum length of time that E1131 may be unavailable is 48 hours.
- C. The building will be occupied.
- D. The OWNER will provide access to temporary power and to hot and cold water for direct project use. The abatement Subcontractor is responsible for all costs and effort required to develop those utilities for his use.
- E. Electrical and mechanical systems not directly modified by this project shall remain functional, and shall be protected from contamination during the abatement work.
- F. The OWNER shall be allowed access to electrical and mechanical systems as necessary throughout the abatement project to ensure their operational continuity.
- G. Security to the site shall be maintained for the duration of the abatement project. It will be the responsibility of the abatement Subcontractor to coordinate with the CONTRACTOR and other trades to sequence the work.

1.4 REFERENCE SPECIFICATIONS, CODES, AND STANDARDS

A. The publications listed below form a part of the specification to the extent referenced. The publications are referred to in the text by the basic designation only.

1. Code of Federal Regulations (CFR) Publications:

29 CFR 1910.1001 Asbestos (for general industry standards)
29 CFR 1910.134 Respiratory Protection
29 CFR 1910.145 Specifications for Accident Prevention Signs and Tags
29 CFR 1910.1200 Hazard Communications
29 CFR 1926.1101 Asbestos (for construction and demolition standards)
40 CFR 61 Sub-part A General Provisions
40 CFR 61 Sub-part M National Emission Standard for Asbestos
40 CFR 241 Guidelines for Land Disposal of Solid Wastes

2. Alaska Statutes Title 23, Labor and Workers Compensation: 8AAC 61.600-790: Asbestos Abatement Statutes and Regulations

3. Additional References:

US EPA Publication 560/5-85-024: A Revision to the US EPA's 1985 Guidance for Controlling Asbestos Containing Materials in Buildings, March 2015 ASTM 1368-14: Visual Inspection of Asbestos Abatement Projects

1.5 DEFINITIONS

A. <u>ACM:</u> See Asbestos Containing Material (ACM).

- B. <u>Abandonment:</u> Leaving in place existing asbestos materials. An example is leaving pipes inside walls when new piping is to be routed differently. Complete documentation must be made of the exact location and condition of the asbestos before abandonment, including the type and method of use of any encapsulant.
- C. <u>Action Level:</u> See Exposure Standards.
- D. Aggressive Conditions: Required technique to prepare an area that has passed visual inspection for clearance sampling. Before starting the sampling pumps, the exhaust from forced air equipment (such as a 1 horsepower leaf blower) shall be directed against all walls, ceilings, floors, ledges and other surfaces in the room. This effort shall take at least 5 minutes per 1,000 square feet of floor. Next, a 20-inch fan shall be placed in the center of the space (one such fan shall be employed for every 10,000 cubic feet of room volume), directed towards the ceiling, and set to run on slow speed. Once the fans are set up and operational, the sampling pumps shall be started and run for the required time. Once sampling is complete all 20-inch fans shall be secured.
- E. <u>Amended Water:</u> Water containing a wetting agent specifically designated by the manufacturer for the wetting of asbestos.
- F. Approved Laboratory: An independent laboratory properly staffed and equipped for the collection and analysis of asbestos bulk and/or air samples, and who maintains demonstrable satisfactory performance from all technicians involved in the performance of these analyses. For air samples, participation and a documented record of satisfactory performance in either the NIOSH Proficiency Analytical Testing (PAT) program, equivalent American Industrial Hygiene Association (AIHA) program, or an equivalent inter-laboratory testing protocol in accordance with 29 CFR 1926.1101, Appendix A is required. The lab must be capable of performing both phase contract illumination microscopy, and transmission electron microscopy, and be capable of the required short turn around times. For bulk analysis, participation in and maintenance of a satisfactory record with the bulk asbestos analysis program with the Research Triangle Park, NC 27709-2194, (919) 541- 6000, is required. If any participation in any equivalent program is proposed to meet this requirement, the details of the program, documentation of satisfactory performance, and name, address and telephone number of the operator of the program must be submitted as part of the asbestos work plan for approval.
- G. Area Monitoring: See Asbestos Air Monitoring.
- H. <u>Asbestos:</u> A class of six naturally occurring fibrous hydrous mineral silicates. Minerals included in this group are chrysotile, crocidolite, amosite and the fibrous forms of anthophyllite, tremolite and actinolite.
- I. <u>Asbestos Air Monitoring</u>: An approved air monitoring plan is required if air monitoring is part of the abatement work. To be approved such a plan must include the following elements:
 - 1. <u>Area Monitoring:</u> Sampling for airborne concentrations of asbestos fibers within the existing or planned asbestos control area that is representative of the fiber levels that may reach the worker's breathing zone. Area pumps drawing 10 liters per minute through the filter cassette are used for area monitoring and should pull at least 1,200 liters of air for each sample.
 - 2. <u>Environmental Monitoring:</u> Sampling for airborne concentrations of asbestos fibers outside the asbestos control area to assure that no asbestos fibers are escaping the enclosure, and that personnel outside the control area are not being exposed. Where a

sealed area is not used, such as during exterior siding removal, this will refer to sampling conducted at the perimeter of the control area to assure that a sufficient buffer zone around the work in progress has been established, and that personnel outside this zone are not being exposed. Area pumps drawing 10 liters per minute through the filter cassette are used for environmental monitoring and should pull at least 1,200 liters of air for each sample.

- 3. <u>Baseline (Background) Monitoring:</u> Sampling conducted to determine the initial level of airborne asbestos fibers present prior to the start of asbestos work. Area pumps drawing ≥ 1 but < 10 liters per minute through the filter cassette are used for this monitoring and should pull at least 1,200 liters of air for each sample. This sampling can be subdivided into three parts:
 - a. Natural Background Sampling: Sampling conducted outside the structure where the work will be accomplished to determine the naturally occurring fiber levels present in that locale. When results indicate that this level may reach or exceed 0.01 f/cc, a minimum of 5 consecutive days of sampling will be used to establish an arithmetic average. This average will be used as the background level.
 - b. <u>Environmental Background Sampling</u>: Sampling conducted to determine the background fiber levels within a structure, but outside the planned asbestos work area. This sampling is accomplished to ascertain the normal background fiber level within these areas of the structure. Special care must be taken during this sampling to minimize sample contamination by non-asbestos fibers, such as from cloth, paper and carpet.
 - c. Work Area Background Sampling: Sampling conducted in the area where asbestos work is planned, normally used to determine the level of personal and other protective measures required by personnel preparing the area for asbestos work and to establish the level of contamination present prior to the beginning of asbestos operations.
- 4. <u>Initial Exposure Assessment Monitoring</u>: Sampling conducted by a "competent person" immediately before or at the initiation of the operation to ascertain the expected exposures during that operation. Initial Exposure Assessment Monitoring must be completed in time to allow compliance with requirements which are triggered by exposure data or the lack of a "negative exposure assessment", and to provide information necessary to assure that all control systems planned are appropriate for the operation and will work properly. Until Initial Exposure Assessment Monitoring confirms that employees on the job will not be exposed in excess of the PEL, or a "negative exposure assessment" for non-friable asbestos has been accepted, it shall be assumed that employees are exposed in excess of the TWA and excursion limit.
- 5. <u>Negative Exposure Assessment:</u> For any one specific asbestos job involving non-friable material which will be performed by trained employees, it may be demonstrated that employee exposures will be below the PEL by data which conform to the following criteria:
 - a. Objective data demonstrating that the product or material containing asbestos minerals or the activity involving such product or material cannot release airborne fibers in concentrations exceeding the TWA and excursion limit under those work conditions having the greatest potential for releasing asbestos.
 - b. Where the employer has monitored prior asbestos jobs for the PEL and the excursion limit within 12 months of the current or projected job, the monitoring and analyses were performed in compliance with the asbestos standard in effect; and the data were obtained during work operations conducted workplace conditions "closely

- resembling" the processes, type of material, control methods, work practices, and environmental conditions in the current operations, the operations were conducted by employees whose training and experience are no more extensive than that of employees performing the current job, and these data show that under the conditions prevailing and which will prevail in the current workplace there is a high degree of certainty that employee exposures will not exceed the TWA and excursion limit.
- c. The results of initial exposure monitoring of the current job made from breathing zone air samples that are representative of the 8-hour TWA and 30 minute short-term exposures of each employee covering operations that are most likely during the performance of the entire asbestos job to result in exposures over the PEL.
- 6. <u>Clearance Monitoring:</u> Sampling occurring at the completion of the asbestos work or at the completion of a specific phase of asbestos work, prior to removing the enclosure. It is accomplished to prove that the clean-up activities have been effective, and that remaining fiber levels both inside and outside the enclosure comply with airborne fiber concentrations defined in "Clearance Levels" below. Clearance sampling is normally accomplished in the same locations and by the same methods as the baseline monitoring, and is done in an aggressive manner (see EPA 560/5-85-024 for description of methods). Transmission Electron Microscopy (TEM) analysis is required for clearance monitoring inside schools and sometimes for inside public buildings to assure that the area is truly safe for reoccupancy. For public buildings the requirement for TEM analysis can be waived in favor of Phase Contrast Illumination Microscopy (PCM) at the OWNER's option. See PART 3-EXECUTION, MONITORING for additional information.
- 7. Personal Monitoring: Sampling for asbestos fiber concentrations at the breathing zone of a worker, used to document individual exposures, and, in conjunction with the work area sampling, to determine the required degree of personal and respiratory protection. A minimum of two samples shall be collected per eight-hour shift at a flow rate of 0.5 to 2.5 liters per minute. At least 25% of the workers doing a particular job shall be sampled each eight-hour shift. See Exposure Standards for more information.
- J. <u>Asbestos Containing Material (ACM):</u> Material composed of asbestos of any type, and in any amount equal to or greater than 1 percent by weight, either alone or mixed with other fibrous or non-fibrous materials.
- K. <u>Asbestos Control Area:</u> An area where operations involving asbestos are performed which is isolated by physical barriers designed to prevent the spread of asbestos dust, fibers, and debris, and to prevent or deter the entry or unauthorized and unprotected personnel. For areas where isolation is not feasible, it will be an area that is physically demarcated, e.g., bounded by a physical barrier such as a rope, barricade, etc., separating the known "clean" zone from the asbestos work area and buffer zone.
- L. <u>Asbestos Fibers:</u> This expression refers to a particular form of asbestos, fibrous tremolite, anthophyllite, or actinolite having a length to diameter aspect ratio of 3:1 or greater, and an overall length of 5.0 micrometers or longer. Where specialized analytical techniques, such as electron microscopy, are utilized for analysis, this shall refer to the number of fibers considered to equate to a specific weight of asbestos.
- M. <u>Asbestos Survey:</u> A detailed survey accomplished by specially trained, experienced technicians of a specific area to determine the presence, absence, condition, and amount of asbestos and asbestos contamination present in that area.

- N. <u>Asbestos Workers' Personal Hygiene Area:</u> A dedicated area containing shower(s), change room and, if required, toilet facilities where personnel working with asbestos (where a control area is not established) can change into protective clothing, and can disrobe, shower, and change into clean clothing without danger of transferring contamination to themselves or others.
- O. <u>Baseline Monitoring:</u> See Asbestos Air Monitoring.
- P. <u>Bulk Sampling and Analysis:</u> Representative samples taken from materials suspected to contain asbestos, analyzed by an approved laboratory using polarized light microscopy (PLM). When specialized methodology, such as electron microscopy is required, collection and analysis shall be in accordance with the recommendations of the laboratory providing the analysis, and the result expressed as both mass per unit volume and percent by weight shall be given.
- Q. <u>Clean</u>: As used in these documents, "clean" means that the surface in question is free of visible asbestos, to the point where no physical sample can be collected for analysis.
- R. <u>Clean Room:</u> An uncontaminated room having facilities for storage of employees' street clothing, uncontaminated materials and equipment.
- S. <u>Clearance Levels:</u> The maximum fiber levels present after completion of the asbestos work, or a given phase of work, sampled during initial or final clearance monitoring. This level shall be the lower of the baseline work area monitoring value for the location, or less than **0.01 fibers/cc**, whichever is lower. In the special case where the naturally occurring outdoor background levels outside the structure are greater than or equal to 0.01 f/cc, averaged arithmetically over a minimum 5-day period, the clearance level shall be the interior work area background level prior to the start of CONTRACTOR work, or less than or equal to the average natural background level, wherever is lower.
- T. <u>Clearance Monitoring</u>: See Asbestos Air Monitoring.
- U. <u>Competent Person:</u> An individual experienced in the abatement and control of asbestos who has received specialized additional training in the supervision and management of asbestos abatement projects. This individual is the full-time on-site manager responsible for ensuring that all safety, health and environmental protection requirements are met, that approved operational methods are followed, and that all personnel on the site comply with these requirements. Specialized training must include an EPA recognized course in the management of asbestos abatement projects. The Competent Person shall report to the Industrial Hygienist.
- V. Containment: See Enclosure.
- W. <u>Decontamination Area:</u> An enclosed area adjacent and connected to a sealed asbestos control area and consisting of an equipment room, shower area, and clean room used for the decontamination of workers, materials and equipment. This also forms the only authorized entry and exit for the control area, except as required in Equipment Decontamination Area below.
- X. <u>Encapsulant:</u> A liquid material which can be applied to ACM which reduces the potential for release of asbestos fibers from a material, either by creating a membrane over the surface (bridging encapsulant) or by penetrating into the material and binding its components together (penetrating encapsulant).
- Y. <u>Encapsulate:</u> The process whereby an encapsulant is applied to ACM to seal in or bind together the individual asbestos fibers, thereby reducing the potential for the release of these fibers.

- Z. <u>Enclosure:</u> Construction of a sealed, permanent structure around asbestos. Complete documentation must be made of the exact location and condition of the asbestos before the enclosure is finished, including the type and method of use of any encapsulant.
- AA. <u>Equipment Decontamination Area:</u> When used, a separate area designed similarly to the personnel decontamination area, but on a large scale. Used to decontaminate large items, or for the purpose of a separate exit for asbestos waste removal where the normal means of egress is not effective (such as the removal of long pieces of pipe from the basement of a structure).
- BB. <u>Equipment Room (Change Room):</u> A room located within the decontamination area that is supplied with impermeable bags or receptacles for the disposal or storage of contaminated protective clothing and equipment, and lockers for the storage and contaminated tools and work shoes.

CC. Exposure Standards

- 1. Workers:
 - a. Action Level: An action level concept shall be used by the abatement Subcontractor to ensure that no personnel are exposed to airborne concentrations of asbestos, actinolite, anthophyllite, or tremolite fibers, or a combination of these mineral fibers, equaling or exceeding **0.1 fibers per cubic centimeter** (0.1 f/cc) expressed as an 8-hour time weighted average (TWA) without placement on a medical monitoring program for asbestos. Personnel exposed at or above this level must be provided proper training in the removal of asbestos containing materials, and must be provided proper personal protective equipment.
 - b. Excursion Limit (EL): An airborne concentration of asbestos of **1.0 fiber per cubic centimeter** of air (1 f/cc) as averaged over a sampling period of 30 minutes.
 - c. <u>Permissible Exposure Level (PEL):</u> The abatement Subcontractor shall ensure that no employee is exposed to an airborne concentration of asbestos, actinolite, anthophyllite, or tremolite fibers, or a combination of these mineral fibers, exceeding **0.1 fibers per cubic centimeter** (0.1 f/cc) expressed as an 8-hour time weighted average (TWA) as defined by the NIOSH sampling and analytical method 7400. (Reference 29 CFR 1926.1101, Appendix A.)

2. Non-Workers:

- a. Personnel who are not asbestos workers as defined by OSHA and this specification shall not be exposed to levels of asbestos fibers exceeding the EPA clearance level criteria of **0.01 f/cc**.
- DD. <u>Fibers:</u> All fibers, regardless of composition, as determined by analysis in accordance with the method described in 29 CFR 1926.1101, Appendix A. When specialized methodology, such as electron microscopy is required, collection and analysis shall be in accordance with the recommendations of the laboratory providing the analysis, and the equivalent fiber level, expressed in both mass per unit volume and fibers per cubic centimeter shall be given.
- EE. Glovebag Technique: A method with limited applications for removing small amounts of friable asbestos-containing material from HVAC ducts, short piping runs, valves, joints, elbows, and other non-planar surfaces not isolated inside an enclosure. The glovebag assembly is a manufactured or fabricated device consisting of a glovebag (typically constructed of 6-mil transparent polyethylene or polyvinyl chloride plastic), two inward projecting long sleeve gloves, an internal tool pouch, and an attached, labeled receptacle for asbestos waste. The glovebag is

constructed and installed in such a manner that it surrounds the object or material to be removed and contains all asbestos fibers released during the process. All workers who are permitted to use the glovebag technique must be highly trained, experienced and skilled in this method.

- FF. <u>HEPA Filter Equipment:</u> High Efficiency Particulate Air (HEPA) filtered vacuuming, local exhaust, or respiratory protective equipment equipped with specialized filters capable of collecting and retaining asbestos fibers. Filters must be of 99.97 percent or greater efficiency at collection of 0.3-micron diameter particles. Filters must be factory tested and certified as meeting this filtration requirement.
- GG. Industrial Hygienist: An individual certified by the American Board of Industrial Hygiene, and having significant prior experience in managing and evaluating the health and safety aspects on asbestos projects of similar nature and scope to ensure capability of performing asbestos work in a satisfactory manner. Prior project similarities shall be in areas related to material composition, project size, number of employees, and in the engineering, work practice, environmental, and personal protection control required. An equivalent individual, such as a Licensed Professional Safety Engineer, Certified Safety Professional, and other qualified person with a minimum of 5 years of experience in industrial hygiene, including extensive experience in the management and evaluation of health and safety aspects of asbestos abatement, may substitute for the Certified Industrial Hygienist, subject to approval by the ENGINEER. The Industrial Hygienist shall be responsible for all monitoring, training and asbestos work, for ensuring that all safety and health requirements prescribed by State and Federal regulations, as well as these specifications, are compiled with, and for ensuring that the competent person performs all assigned duties in accordance with this specification and applicable Federal and State regulations.
- HH. Initial Exposure Assessment Monitoring: See Asbestos Air Monitoring.
- II. Lockdown Sealant: A spray-on liquid-type sealant applied to surfaces from which ACM has been removed. It is applied after final cleaning and visual inspection has occurred, but prior to initial clearance sampling. Its purpose is to control and minimize the amount of airborne asbestos fiber generation that might result from any residual ACM debris on the substrate. All lockdown sealant shall be acrylic copolymer blend that forms a durable non-combustible barrier that when cured becomes an excellent primer for spray back insulation and water based architectural coatings.
- JJ. Lower Limit of Detection (LLD): The smallest quantifiable amount of a substance, or number of fibers, present in a given sample that can be determined accurately by the sampling and analysis methods in use. A LLD is normally specified to represent a 95% confidence level. All samples taken for baseline, background, environmental or clearance sampling shall have an LLD of 0.01 f/cc or less. Samples taken for bulk analysis shall have an LLD of less than 0.1 percent by weight of the sample of homogeneous samples.
- KK. Negative Exposure Assessment: See Asbestos Air Monitoring.
- LL. <u>Negative Pressure:</u> A minimum of **minus 0.02 inches of water pressure** (negative pressure) differential between the asbestos control area and all adjacent areas, at a minimum flow rate of **four air changes per hour** at all points within the asbestos control area. See PART 3-EXECUTION; SAFETY AND HEALTH COMPLIANCE; Vacuums and local exhaust systems for additional information.
- MM. Permissible Exposure Level (PEL): See Exposure Standards.

- NN. Personal Monitoring: See Asbestos Air Monitoring.
- OO. <u>Phase Contrast Illumination Microscopy (PCM):</u> An analytical method for counting fibers in air sampling filters.
- PP. <u>Polarized Light Microscopy (PLM):</u> An analytical method for determining asbestos content in bulk samples.
- QQ. <u>Time Weighted Average (TWA):</u> The TWA is an average of the airborne concentration of asbestos fibers, expressed as the number of fibers per cubic centimeter (f/cc) of air, measured and calculated for a minimum of 8 hours, and taken into account the relative proportions of time exposed when averaging different exposure levels.
- RR. Transmission Electron Microscopy (TEM): A procedure whereby an electron beam is scanned through a specially prepared air-sampling filter. The beam diffraction pattern is then analyzed by computer, which differentiates between the patterns of asbestos and the non-asbestos materials, and quantifies the mass of the asbestos present on the filter. This mass can then be referenced to an equivalent number of fibers per cubic centimeter. By far the most sensitive and specific test for airborne asbestos, it is expensive and results cannot normally be provided for several days. Used for detection of extremely low levels, or when suspected non-asbestos fibers are believed to be interfering with the accuracy or readability of normal sampling methods. All clearance samples for projects inside school buildings must use TEM in accordance with methods set forth in 40 CFR 760, Subpart E.

1.6 PRE-WORK SUBMITTALS

- A. The Pre-Work Submittal shall be submitted digitally as a complete package and modified as necessary to obtain approval by the ENGINEER five working days prior to any work on the project. The abatement Subcontractor shall perform his work in compliance with the approved Pre-Work Submittal which shall include:
 - 1. <u>Asbestos Work Plan:</u> A plain language plan describing work procedures to be used during each and all operations involving asbestos. Annotated building plans or site plans no larger than 11 inches by 17 inches shall be included to detail locations for asbestos control areas, monitoring locations, access and disposal routes, and other activities where needed. The plan shall include as a minimum the following elements:
 - a. Location and construction of each asbestos control area.
 - b. Sequencing of asbestos work to include separate sequences if the work is to be accomplished in separate sections or phases.
 - c. A detailed air monitoring plan that complies with 05.045 Alaska Department of Labor Construction Code (Asbestos), 29 CFR 1926.1101, current US EPA guidance, and applicable requirements of "Asbestos Air Monitoring", "Exposure Standards", and "Personal Monitoring" in DEFINITIONS above.
 - d. Transport and disposal plans.
 - e. A contingency plan for potential emergencies/accidents/incidents covering, but not limited to:
 - Medical emergencies/accidents inside the control area.
 - Violation of the control area.
 - Spills inside the control area.

- Spills outside the control area.
- Fire inside and outside the control area.
- Loss of power.
- Loss of negative pressure in the controlled area.
- Discovery that fiber levels inside or outside the control area have exceeded prescribed limits.
- Spills during transport or disposal.
- f. A notification listing of personnel and organizations to be contacted by the abatement Subcontractor in the event of an incident, emergency or contingency.
- g. The 24-hour contact point for the abatement Subcontractor and the designated "competent person" to contact in case of an on-site problem. Response time to the site shall not exceed 1 hour from the time of the notification.
- 2. <u>Notifications</u>: Copies of EPA and OSHA notifications submitted prior to work.
- 3. <u>Competent Person:</u> Submit the name(s) proposed, address (es), telephone number(s) and complete documentation the individual's qualifications proving the person's qualifications meet the requirements described in DEFINITIONS above.
- 4. <u>Industrial Hygienist:</u> Submit the name, address and telephone number of the Industrial Hygienist selected to prepare the asbestos work plan, and direct monitoring and training. Include documentation proving the person's qualification meet the requirements described in DEFINITIONS above.
- 5. Training: Submit certificates signed by each employee and the Industrial Hygienist that each employee has received the training required by 29 CFR 1910.1001, 29 CFR 1926.1101, and appropriate State of Alaska regulations and this specification. Include proof that each employee is certified as an asbestos worker in the State of Alaska in accordance with current state regulations.
- 6. <u>Testing Laboratory:</u> If <u>Asbestos Air Monitoring</u> is included in the Contract, submit the name, address, telephone number and qualifications of the independent testing laboratory selected to perform the monitoring, testing and reporting of airborne asbestos fibers, including documentation certifying that all technicians performing the analysis have been judged proficient by successful participation within the last year in the NIOSH PAT program or the AIHA program, or an equivalent inter-laboratory testing program.
- 7. <u>Protective Equipment and Protective Method Plans:</u> Details of planned personal protective equipment requirements and protective methods, including respirators as required for each specific type of operation or condition. Include supporting justification when alternate (e.g., less than the maximum specified) protection is proposed.
- B. Any changes to procedures, methods, conditions, etc., identified in the approved Pre-Work Submittal must be submitted in writing for review and approval by the ENGINEER prior to the inception of the change. The changes must be reviewed and approved by the Certified Industrial Hygienist prior to being submitted to the ENGINEER for review. Where changes must be implemented immediately for the protection of workers, personnel outside the work area, the structure or the environment, and the change established an environment more stringent than that previously existing, the changes may be implemented by the competent person or other individuals with appropriate authority, and the ENGINEER notified immediately. These changes will then be submitted in writing within 24 hours for final review and approval.

1.7 POST-WORK SUBMITTALS

- A. The Post-Work Submittal shall be submitted digitally and approved by the ENGINEER as complete before final payment is approved. The Post-Work Submittal shall include:
 - 1. Work Log: A detailed log of all operations involving the asbestos portion of the work, to

include but not be limited to:

- a. The names, entry and exit dates and times, duties performed, and protective equipment worn by each individual during their time within the asbestos control area, covering all personnel, (including inspectors, monitoring personnel and visitors) entering each asbestos control area. This information is normally provided in the form of fully legible copies of the entry/exit control log for the control area. Each day's listing should also include a summary of the work performed (quantity, type, location, etc.).
- b. A listing of all personnel performing asbestos related work outside the control area, showing duties performed, date, time, duration, and location of the work and protective equipment worn while performing these duties. Each day's listing should also include a summary of the work performed (quantity, type, location, etc.).
- c. Copies of the complete and reviewed sampling results as an attachment.
- d. A summary of each problem, incident, contingency, and emergency that occurred, and the actions taken to resolve the situation.
- e. A copy of all shipping manifests that document disposal of all ACM at an approved solid waste facility. Full payment shall not be released until this document is received by the Owner or ENGINEER.

PART 2-PRODUCTS-NOT USED

PART 3-EXECUTION

3.1 PROTECTION OF ADJACENT AREAS

A. Perform all asbestos work in such a way as to not contaminate 1) adjacent areas, or 2) interior spaces of components within the abatement area (such as cabinets, ducts, or electrical components). Where such areas or spaces are contaminated, they shall be cleaned and/or restored to their original condition as directed by the ENGINEER at the abatement Subcontractor's expense.

3.2 NOTIFICATIONS AND PERMITS

- A. The abatement Subcontractor shall notify the regional office of the United States Environmental Protection Agency (US EPA) in accordance with 40 CFR 61 Subpart M.
- B. The abatement Subcontractor shall notify, also, the Alaska Department of Labor and Workforce Development, Occupational Safety and Health Division (AK OSHD) in accordance with current State of Alaska asbestos regulations.
- C. The abatement Subcontractor shall notify the ENGINEER 48 hours prior to commencement of any abatement work, and immediately upon completion or termination of the work.
- D. The abatement Subcontractor shall carry out disposal in accordance with state and federal requirements, and shall secure necessary permits in conjunction with asbestos removal and transport, and provide timely notification of such actions as may be required by Federal, State, regional and local authorities.

3.3 COMPETENT PERSON

A. All asbestos work, including setup and teardown of the asbestos enclosure(s) and control area(s), and all asbestos disposal operations shall be under the direct and continuous on-site supervision of the Competent Person (who is identified in the Pre-Work Submittal and whose qualifications and duties are defined in DEFINITIONS above). The Industrial Hygienist shall oversee all activities of the competent person.

3.4 INDUSTRIAL HYGIENIST

- A. The abatement Subcontractor shall conduct all monitoring, training and asbestos work under the direction of the Industrial Hygienist (who is identified in the Pre-Work Submittal and whose qualifications and duties are defined in DEFINITIONS above).
- B. While performing asbestos work, the abatement Subcontractor may be subject to on-site inspection by the OWNER, the ENGINEER (or a designated representative), fire, safety, and health personnel, and Federal and State inspectors. If the work is in violation of specification requirements, or applicable Federal or State regulations, the ENGINEER may issue a stop-work order to be in effect immediately, and which will remain in place until the violation(s) are resolved and, if required by the ENGINEER, a new or amended asbestos work plan is submitted. Restart will not be accomplished without approval of the ENGINEER. Standby time and expenses required to resolve the violation(s) and provide new or amended submittals shall be at the abatement Subcontractor's expense.

3.5 SAFETY AND HEALTH COMPLIANCE

A. The abatement Subcontractor shall comply with all laws, ordinances, rules and regulations of Federal, State, regional and local authorities regarding demolition, handling, storing, transporting and disposing of asbestos and asbestos containing materials. He shall also comply with the applicable requirements of the current issues of 29 CFR 1910.1001, 29 CFR 1926.1101, and 40 CFR 61 Subparts A and M. Asbestos removal is also required to comply with the provisions of the State of Alaska, Solid Waste Management Codes, title 18 of the Alaska Administrative Code, and the State of Alaska OSHA Standards.

3.6 ASBESTOS WORK PROCEDURES

- A. The work specified in these contract documents shall be carried out in accordance with all applicable local, state, and federal regulations, and the following special requirements:
 - 1. Negative Air: The CONTRACTOR shall use negative air machines to ensure that air is drawn into the abatement WORK area and exhausted through HEPA filters.
 - 2. OSHA Class I asbestos WORK: Class I WORK shall comply with the appropriate sections of OSHA 1926.1101(g)(4) "Class I Requirements" and OSHA 1926.1101(g)(5). Certified asbestos abatement workers are a requirement for Class I asbestos WORK.
 - 3. OSHA Class II asbestos WORK: Class II WORK shall comply with the appropriate sections of OSHA 1926.1101(g)(7) "Work Practices and Engineering Controls for Class II WORK" and OSHA 1926.1101(g)(8). Certified asbestos abatement workers are a requirement for Class II asbestos WORK.
 - 4. Asbestos Handling Procedures: The CONTRACTOR shall sufficiently wet ACM with a fine spray of amended water during removal, cutting or other handling to reduce the emission of airborne fibers. All removed and waste materials shall be placed in plastic disposal bags or other approved containers. Under no circumstances shall asbestos waste or debris be allowed to accumulate in the WORK area.

5. Disposal of Asbestos: Procedures for hauling and disposal shall comply with 40 CFR 61, Subpart M, 40 CFR 241 and 257, and state, regional, and local standards. Abated material and associated debris shall be packaged in accordance with applicable regulations and disposed of at an approved facility. All ACM shall be transported in an enclosed vehicle.

3.7 MONITORING

- A. The abatement Subcontractor shall provide third-party air monitoring for the duration of the Project in accordance with the approved Pre-WORK Submittal.
- B. At a minimum the CONTRACTOR shall provide "Area Monitoring", "Baseline (Background) Monitoring", "Personal Monitoring" and "Clearance Monitoring" all as specified in Paragraph 1.5 "DEFINITIONS", above.
- C. The CONTRACTING OFFICER reserves the right to perform confirmation air monitoring including all elements summarized in Asbestos Air Monitoring in DEFINITIONS, above.

D. Clearance Procedures

- After abatement activities are complete but prior to the application of lockdown sealant and the performance of clearance monitoring, the abatement Subcontractor and the ENGINEER (or a designated representative) shall perform a detailed visual inspection of the work area for any visible asbestos residual. If any is found, a complete re-cleaning of the area shall be performed, and the area re-inspected. Once the visual inspection is satisfactorily completed the lockdown shall be applied.
- 2. The abatement Subcontractor shall be responsible for all costs relating to all visual inspections after the second failed visual inspection.
- 3. After the site has passed the visual inspection and has received spray application of lockdown sealant but prior to the removal of the enclosure, clearance monitoring of the work area shall be accomplished to confirm the effectiveness of the clean-up operations. Such sampling shall not be performed until all areas and materials within the work area are fully dry.
- 4. Clearance sampling for this project shall be done using PCM analysis. Once clearance criteria have been achieved, clearance shall be considered final and removal of any temporary protective enclosure in the room shall be accomplished. The semi-permanent barrier constructed above the ceiling is to remain in place.
- 5. The abatement Subcontractor shall be responsible for all costs relating to all clearance monitoring after the first failed clearance sampling.

END OF SECTION 028213

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Wet-pipe sprinkler system.
- B. System design, installation, and certification.

1.2 RELATED REQUIREMENTS

- A. Section 21 2200 Clean-Agent Fire Extinguishing System
- B. Section 280513 Conductors and Cables for Electronic Safety and Security
- C. Section 280528 Pathways for Electronic Safety and Security
- D. Section 284621.11 Addressable Fire Alarm System

1.3 REFERENCE STANDARDS

- A. NFPA 13 Standard for the Installation of Sprinkler Systems; National Fire Protection Association; 2010.
- B. UL (FPED) Fire Protection Equipment Directory; Underwriters Laboratories Inc.; current edition.

1.4 SUMMARY OF WORK

A. Remove the existing wet sprinkler heads, supports, and branch piping from the following spaces: Server Room 2425 and Server Room 2402B. Cap off the system outside of the space and firestop all penetrations.

1.5 WORK INCLUDED

A. The Mechanical Work is governed by the entire Specifications and not just Division 21. The entire Specifications must be examined for requirements relating to the Work hereunder. The Work covered by this and all other Mechanical sections consists of furnishing labor, equipment, and materials in accordance with the Specifications or Drawings, or both, together with any incidental items not shown or specified which can be reasonably inferred or taken as belonging to the Work and necessary in good practice to provide a complete system described or shown as intended.

1.6 SUBMITTALS

- A. General: Provide submittals according to Conditions of Contract and as required hereunder. Drawings and general provisions of the contract including General, Supplementary Conditions, and all Division 1 Specification Sections, apply to this Section. Approval of the data shall not eliminate responsibility for compliance with the Drawings or Specifications unless specific attention has been called in writing to proposed deviations at the time of transmittal of the data and such deviations have been approved, not shall it eliminate the responsibility for freedom of errors of any sort in the data. All Mechanical submittal data for Project construction is to be turned in for approval at the same time in order for an efficient review process. Partial submittals may be rejected until the full submittal is received.
- B. Specific Products: Trade names and catalog numbers of manufactured products included herein are intended to indicate the type, size and grade of quality of equipment and materials required and such equipment and materials are approved for installation subject to full compliance with the Specifications. Except where single manufacture is specified for standardization, requires for approval of other manufacturers than those specified must be accompanied by complete descriptions including overall dimensions, performance data, and, if catalog material, identification of specific products or items proposed.
- E. Submittal Format: All data shall be submitted at one time in neatly bound loose-leaf three ring binders with pockets and tabulated in order of Specification Division 21. All data shall be typed, minimum 10 point font, not exceptions. Data submitted that is not conforming to these specification requirements will be returned without reviewing and will need to be resubmitted at Contractors sole complete cost.
 - 1. Each binder shall have a set of separators with index tabs A to Z. Tabs are to be printed type. Slip in tabs not acceptable.
 - 2. The first page shall be a cover sheet with project name, address, data, submittal product name, all applicable contractors and contact information, and all applicable consultants and contact information.
 - 3. Second page shall be a submittal manual index of all project Specification sections with respective tab numbers, and respective book number, if applicable.
 - 4. The first page of each manuals section shall be an index of the respective project Specification section and number with each product name, manufacturer name and model number.
 - 5. Each manuals section shall be labeled and certified by mechanical Subcontractor that the data presented is in accordance with project Specifications. Index sheet in front of completed binder listing each piece of equipment or material submitted.
 - 6. Product Data to be utilized shall be flagged and noted and all other data shall be crossed out or otherwise flagged that it is not in the project.
 - 7. Data shall be inserted in binders in order of Specification number. Specification number shall be clearly labeled on each submittal page.
- F. As-Built Drawings: As-builts shall accurately show all changes for Contract Document for piping, ductwork, and equipment. As-Built drawings shall be updated daily and available for inspection on-site by the ARCHITECT.

- I. Submit prior to Substantial Completion Inspection and Final Inspection a detailed list of equipment and systems that will NOT be completed for the completion date. Include status and information of deficiencies from all previous inspection reports.
- J. Submit prior to Re-inspections of Substantial Completion Inspections, if applicable, and the Final Inspection a marked copy of the previous Engineers Inspection Reports detailing all items that have been completed and all items that have not been completed with reasons thereof. Reinspection or Final Inspection will not occur until receipt of this list.

1.7 COOPERATIVE WORK

- A. The Work hereunder shall be coordinated between various fire protection and mechanical Sections and with the Work specified under other divisions or contracts toward rapid completion of the entire Project. If any cooperative Work must be altered due to lack of proper supervision hereunder, or failure to make proper provisions in time, then the Work hereunder shall include all expense of such changes as are necessary to be made in the Work under other divisions and contracts, and such changes shall be directly supervised by the OWNER and shall be made to the satisfaction of the OWNER.
- B. In general pitched plumbing piping and ductwork shall take preference in location within the Project area. Coordination of all drain valves, duct access doors, and other equipment requiring access and maintenance procedures is required with all building components during construction for maximum accessibility and proper location as intended. Coordinate closely with all other Contractors.

1.8 QUALITY ASSURANCE

- A. Maintain one copy of referenced design and installation standard on site.
- B. Conform to UL requirements.
- C. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- D. Installer Qualifications: Company specializing in performing the work of this section with minimum 3 years experience approved by manufacturer.
- E. Equipment and Components: Provide products that bear UL label or marking.
- F. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

PART 2 - PRODUCTS

2.1 SPRINKLER SYSTEM

- A. Remove the existing wet sprinkler heads, supports, and branch piping from the following spaces: Server Room 2425 and Server Room 2402B. Cap off the system above ceiling in 2425 and firestop all penetrations.
- B. Occupancy: Comply with NFPA 13.
- C. Pipe Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
 - 1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
 - 2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
 - 3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
 - 4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
 - 5. Other Types: As required.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install in accordance with referenced NFPA design and installation standard.
- B. Install equipment in accordance with manufacturer's instructions.
- C. Place pipe runs to minimize obstruction to other work.
- D. Place piping in concealed spaces above finished ceilings.

3.2 INTERFACE WITH OTHER PRODUCTS

- A. Ensure required devices are installed and connected as required to fire alarm system.
- B. Coordinate testing of related fire alarm components with fire alarm contractor.

END OF SECTION 211300

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Total flooding extinguishing system for enclosed spaces.
- B. Fire detection system.
- C. Control and supervision systems.
- D. Extinguishing agent, containers, distribution and discharge system.
- E. System maintenance after closeout.

1.2 RELATED REQUIREMENTS

- A. Section 211300 Fire-Suppression Sprinklers
- B. Section 280513 Conductors and Cables for Electronic Safety and Security
- C. Section 280528 Pathways for Electronic Safety and Security
- D. Section 284621.11 Addressable Fire Alarm Systems

1.3 REFERENCE STANDARDS

- A. ASME B16.3 Malleable Iron Threaded Fittings: Classes 150 and 300; The American Society of Mechanical Engineers; 2011.
- B. ASME B31.1 Power Piping; The American Society of Mechanical Engineers; 2012 (ANSI/ASME B31.1).
- C. ASME B40.100 Pressure Gauges and Gauge Attachments; The American Society of Mechanical Engineers; 2005.
- D. ASME (BPV VIII, 1) Boiler and Pressure Vessel Code, Section VIII, Division 1 Rules for Construction of Pressure Vessels; The American Society of Mechanical Engineers; 2013.
- E. ASME (BPV IX) Boiler and Pressure Vessel Code, Section IX Welding and Brazing Qualifications; The American Society of Mechanical Engineers; 2013.
- F. ASTM A53/A53M Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc Coated, Welded and Seamless; 2012.
- G. ASTM A106/A106M Standard Specification for Seamless Carbon Steel Pipe for High-Temperature Service; 2011.
- H. ASTM A135/A135M Standard Specification for Electric-Resistance-Welded Steel Pipe; 2009.

- I. ASTM A234/A234M Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service; 2011a.
- J. AWS D1.1/D1.1M Structural Welding Code Steel; 2010.
- K. FM P7825 Approval Guide; Factory Mutual Research Corporation; current edition.
- L. ISO 9000 ISO Standards Compendium: ISO 9000 Quality management; 2005.
- M. ITS (DIR) Directory of Listed Products; Intertek Testing Services NA, Inc.; current edition.
- N. NEMA ICS 6 Industrial Control and Systems: Enclosures; National Electrical Manufacturers Association; 1993 (R2006).
- O. NFPA 70 National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- P. NFPA 72 National Fire Alarm and Signaling Code; National Fire Protection Association; 2013.
- Q. NFPA 2001 Standard on Clean Agent Fire Extinguishing Systems; National Fire Protection Association; 2012.
- R. UL (FPED) Fire Protection Equipment Directory; Underwriters Laboratories Inc.; current edition.
- S. UL 393 Indicating Pressure Gauges for Fire-Protection Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.
- T. UL 404 Gauges, Indicating Pressure, for Compressed Gas Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

1.4 SUBMITTALS

- A. See Division 1 Administrative Requirements, for submittal procedures.
- B. Product Data: To bear stamp of approval of authority having jurisdiction. Provide for each piece of equipment comprising the system including detectors, release devices, discharge nozzles, manual controls, alarm devices, annunciators, extinguishing agent containers, manifolds, and control panel.
- C. Shop Drawings: To bear stamp of approval of authority having jurisdiction. Indicate detailed layout of system, including piping and location of each component. Include control diagrams, wiring diagrams, and written sequence of operation.
- D. Design Data: Submit design calculations bearing stamp of approval of authority having jurisdiction. Include calculations that verify system pressures, nozzle flow rate, orifice code numbers, piping pressure losses, component flow data, and pipe sizes.

- E. Installer's Qualification Statement. Statement noting that the installer meets the requirements outlined in section 3. 1 of this specification.
- F. Certificates: Certify that products meet or exceed specified requirements.
 - 1. Manufacturer: Certify that system meets or exceeds specified requirements.
 - 2. Welders: Submit certificate indicating compliance with ASME Section IX.
- G. Manufacturer's Instructions: Include recommended equipment installation and system components.
- H. Test Reports: Indicate successful completion of tests; include certification of extinguishing agent container pressure and extinguishing agent quantity.
- I. Code Authority Approval: Submit copy of inspection approval of fire protection system by authority having jurisdiction.
- J. Maintenance/ service Contract:
 - 1. Provide Owner with a 1 year service/maintenance contract. Contract proposal to include required maintenance, inspection, and testing of clean agent fire extinguishing system meeting NFPA and State Fire Marshall requirements. This contract is to begin on the date of Substantial Completion. This contract will include 24/7 emergency service with the ability to recharge the largest suppression system within 24 hours after a discharge. Contract is to include reimbursement for refill service if the release is not the result of a system malfunction.
 - 2. Provide Owner with a proposal for a separate 5 year maintenance contract to start on the completion of the initial 1 year contract noted above. Contract proposal to include required maintenance, inspection, and testing of clean agent fire extinguishing system meeting NFPA and State Fire Marshall requirements. This contract will include 24/7 emergency service with the ability to recharge the largest suppression system within 24 hours after a discharge. Contract is to include reimbursement for refill service if the release is not the result of a system malfunction.
- K. Project Record Documents: Record actual locations of components and equipment, equipment identification markings, conduit and piping routing details, and agent container positions.
- L. Operation and Maintenance Data:
 - 1. Include electrical schematic written description of system design, drawings illustrating control logic and equipment locations, and technical brochures describing equipment.
 - 2. Include list of recommended spare parts.
 - 3. Include checklists and procedures for emergency situations, trouble shooting techniques, abort functions, system control panel operation, trouble procedures, and safety requirements.
 - 4. Include emergency service contact information.
- M. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer. Warranty to include a 1-year construction warranty as well as the requirements noted in section 1.7 of this specification.

- N. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Division 1 Product Requirements, for additional provisions.
 - 2. Equipment Maintenance Tools: One set, including all special tools necessary for servicing and maintaining the equipment installed.
 - 3. Extra Detectors: One of each type.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
 - 1. ISO 9000 registered.
- B. Welding Materials and Procedures: Conform to ASME Section IX.
- C. Installer Qualifications:
 - 1. Company specializing in performing the work of this section with minimum five years documented experience.
 - 2. Trained and approved by manufacturer to design, install, test and maintain the equipment specified herein.
 - 3. Complies with manufacturer's certification requirements.
 - 4. Complies with manufacturer's insurance requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store equipment in shipping containers with labeling in place. Deliver fire extinguishing agent in approved containers. Protect from weather.

1.7 WARRANTY

- A. Warranties in this section are in addition to any warranty requirements of the General Conditions of the Contract or local applicable laws.
- B. Provide a 3MTM Novec TM 1230 Fire Protection Fluid Blue SkyTM Warranty 20-year protection against regulatory bans or restrictions as described at www.3M.com/novec1230fluid, under the product literature tab in the file "3MTM NovecTM 1230 Fire Protection Fluid Blue SkyTM Warr". It is the contractor's responsibility to assist the Owner in proper registration of the product.

PART 2 PRODUCTS

2.1 GENERAL

- A. All equipment furnished under this specification shall be new, current products of the manufacturer, and listed for its intended application. Where two or more pieces of equipment that perform the same function are required, they shall be the product of one manufacturer and exact duplicates.
- B. Any material, equipment or product to be used which is approved by Factory Mutual (FM) and not listed by Underwriter's Laboratories (UL), requires the approval of SRP.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA70, Article100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

2.2 CLEAN AGENT FIRE SUPPRESSION FLUID

- A. Clean agent fire suppression fluid shall be 3M Novec 1230 Fire Protection Fluid, or approved equal.
- B. Clean Agent Fluid shall have an Ozone Depletion Potential (ODP) of zero. ODP as defined by the US EPA.
- C. Clean Agent Fluid shall have a Global Warming Potential (GWP) of less than 10 (100 year ITH). GWP as defined by the intergovernmental Panel on Climate Change Fourth Assessment Report (IPCC AR4) or in U.S. EPA documentation and approvals.
- D. Clean Agent Fluid shall not be one of these greenhouse gases; Perfluorocarbons (PFCs), Hydrofluorocarbons (HFCs), and Sulphur Hexafluoride.
- E. Clean agent must have a minimum safety factor of 60% between the design concentration percentage and the No Observed Adverse Effect Level (NOAEL) for acute toxicity, including cardiac sensitization of 10%.

2.3 TOTAL FLOODING SYSTEM REQUIREMENTS

- A. SYSTEM manufacture shall be an approved original equipment manufacturer for the clean agent being utilized.
- B. The name of the manufacturer, part numbers and serial numbers shall appear on all major suppression system components.
- C. All devices, components and equipment shall be the products of the same manufacturer or be certified by the manufacturer as compatible with devices, components, and equipment of the manufacturer.
- D. All devices, components and equipment shall be new and standard products of the manufacturer's latest design, suitable to perform the intended functions.

- E. Provide locks on all cabinets. All locks are to be keyed alike.
- F. SYSTEM shall include at a minimum heat/smoke detectors, detector wiring, alarms, horns, strobes, bells, alarm wiring, control panels, control wiring, devices, piping, nozzles, primary and backup storage cylinders, valves, manual discharge switches, control panels, abort stations, conduit, wiring, signage, labeling, security keying and other system required elements for a complete operational system that includes active and backup tanks connected into the system.
- G. Provide control signals as required to close dampers, and for room 2402B, deactivate the portable AC Unit prior to SYSTEM discharge.
- H. Assist the enclosure construction contractor with training on how to establish the room air tightness. If an existing construction, survey the room prior to pricing and provide any necessary room integrity upgrades in pricing.

2.4 TOTAL FLOODING SYSTEM DESCRIPTION

- A. The SYSTEM shall be of a type designed for use with 3MTM NovecTM 1230 Fire Protection Fluid or approved equal. Its suitability shall have been validated through listing or approval similar to that promulgated by Underwriters Laboratories, Inc, USA. The listing or approval shall also utilize a test protocol equal to the latest edition of UL 2166, "Halocarbon Clean Agent Extinguishing System Units".
- B. Details and requirements for suppression system installation shall be as follows:
 - 1. As a minimum, the SYSTEM design concentration shall be based upon the expected fuel contained within the hazard for all protected spaces anticipating the minimum temperature within the hazard space(s).
 - 2. The SYSTEM shall be complete in every respect. It shall include all mechanical and electrical installation, all detection and control equipment, agent storage containers, proper quantity of clean agent fluid, nozzles, pipe and fittings, manual release and abort stations, audible and visual alarm devices, auxiliary devices and controls, shutdowns, alarm interface, caution/advisory signs, functional checkout and testing, training and all other operations necessary for a functional, listed and approved system.
 - 3. The SYSTEM(s) shall be actuated by a combination of ionization and/or photoelectric detectors installed at a maximum spacing of 250 ft2/detector (23m2/detector) in all spaces. If the airflow exceeds one (1) air change per minute, photoelectric detectors only shall be installed at a spacing not to exceed 125 ft2/detector (11.5m2/detector). Reference NFPA 72 current edition.
 - 4. The SYSTEM detection wiring shall be of an approved method.
 - 5. Automatic operation of each protected space shall be as follows:
 - i. The actuation of one(1) detector within the space shall;
 - 1. Illuminate the "ALARM" lamp on the control panel face.
 - 2. Energize the alarm bell and an optional visual indicator.
 - 3. Transfer two(2) sets of 10 amp rated auxiliary contacts, which can perform auxiliary functions, such as;

- a. Operate door holders/closures on access doors.
- b. Transmit a signal to a fire alarm system.
- c. Shut down HVAC equipment.
- 4. Light an individual lamp on an optional graphic annunciator.
- ii. The actuation of a second detector within the space shall;
 - 1. Illuminate the "PRE-DISCHARGE" lamp on the control panel face.
 - 2. Energize an alarm horn or horn/strobe device.
 - 3. Shut down the HVAC system and/or close dampers.
 - 4. Start the time-delay sequence.
 - 5. Enable SYSTEM abort sequence.
- iii. After completion of the time-delay sequence, the SYSTEM shall discharge and the following shall occur;
 - 1. Illuminate a "SYSTEM FIRED" lamp on the control panel face.

2.5 TOTAL FLOODING SYSTEM LOCATIONS:

- A. Server room 2425. In this installation the clean agent tanks located on the floor below in Electrical Room 1131. No Detection, or alarms are required in room 1131. The monitoring panel will be located in Server Room 2425.
- B. Server room 2402B. This installation will have the clean agent tanks and monitoring panel located in Server Room 2402B.

2.6 PIPING

- A. Conceal piping to the maximum extent possible. Piping shall be inspected, tested and approved before being concealed. Provide fittings for changes in direction of piping and for all connections. Make changes in piping sizes through standard reducing pipe fittings; the use of bushings is not permitted.
- B. ASTM A 53 or ASTM A 106, black or zinc-coated, threaded, Schedule 40.
- C. ASME B16.11 or ASME B16.3, Class 300, zinc-coated, threaded, except Class 150 or 300 for pipe 3/4 inch or smaller.
- D. Rods, hangers and supports shall be zinc plated. It is recommended that pipe hangers and supports be furnished and installed by the Contractor as follows: at a minimum spacing of 7 feet for pipe 1" nd smaller, and 8 feet for piping 2" and smaller. All larger pipe can have spacing at 11 feet.
- E. Provide sleeves where piping passes through concrete floors, Sleeves in outside walls below and above grade, in floor, and in roof slabs, shall be standard weight zinc coated steel pipe. Sleeves in partitions shall be zinc coated sheet steel having a nominal weight of not less than 0.90 pounds per square foot. Space between piping and the sleeve, shall be not less than 0.5 inch. Sleeves shall be of sufficient length to pass through the entire thickness of walls, partitions and slabs. Extend sleeves in floor slabs 2 inches above the finished floor. Pack space between the pipe and sleeve with a Listed through penetration fire stop system.

- F. Provide escutcheon plates for piping passing through floors, walls and ceilings with one piece or split type plates. Plates where pipe passes through finished ceilings shall be painted to match the ceiling color. Other plates shall be of steel or cast iron, with aluminum paint finish. Securely anchor plates in place.
- G. Discharge nozzles shall be fabricated of corrosion resistant materials. All nozzles shall be designed so that the orifice piece is connected directly to the supply pipe. The size of pipe and nozzles shall be determined from the calculated flow and terminal pressures in accordance with established, recognized test data contained in the manufacturer's Listed design manual.
- H. Storage cylinders shall be constructed of high strength alloy steel, conforming to all applicable specifications of the Department of Transportation. Container design shall permit on-site reconditioning and refilling when required. Safety valves, manifolds, pressure gauges, and pressure switches shall be furnished and installed.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that enclosing walls are continuous above ceilings and below raised floors to enable required concentration to be built up and maintained for required time to ensure fire is extinguished.

3.2 Installer Qualifications

- A. The Installer must maintain required licensing for the City and Borough of Juneau, the State of Alaska as well as any national credentials.
- B. The installing contractor shall be trained by the equipment manufacturer to design, install, test and maintain the SYSTEM.
- C. The installing contractor shall employ a person who can show proficiency at least equal to a NICET level III certification in special hazards design.
- D. The installer shall be experienced and regularly engaged in the installation of automatic fire suppression systems using 3MTM NovecTM 1230 Fire Protection Fluid, or similar, in strict accordance with applicable codes and standards.
- E. The installer shall maintain or have contractually available a recharging station listed or approved for recharging. The /installer shall provide proof of his ability to recharge the largest of such a suppression system within 24 hours after a discharge. Include the amount of clean agent bulk storage available. Provide a written document to the Owner stating the amount of fluid required for refill.
- F. The installer shall be an authorized distributor of the manufacturer for the suppression system designed for use with 3MTM NovecTM 1230 Fire Protection, or similar Fluid so that the immediate replacement parts are readily available from inventory.
- G. The installer will have a 24/7 emergency contact number that will allow for emergency services to be made available within 24 hours of a clean agent release, or for a malfunction in the system.

3.3 Installation

- A. All installations shall be in accordance with the manufacturer's recommendations, codes, standards, regulations, listings and approvals.
- B. Installations to be installed per these specifications and the accompanying contract documents.
- C. Work is to be performed in a manner that meets compliance with all ICRA Requirements as per Division 1 Section 015221 SPECIAL SAFETY REQUIREMENTS and INFECTION CONTROL FOR CONSTRUCTION & RENOVATION.
- D. Hot work such as welding or soldering is not anticipated to occur inside the Bartlett regional Hospital and all of this work will need to occur offsite, or in an approved location. All other work that would be classified as hot work such as grinding and saw cutting must be preapproved by BRH management and may not occur without a hot work permit.

3.4 Testing and Training

- A. The general contractor shall be responsible for sealing and securing the protected space(s) against agent loss and/or leakage during at least the ten (10) minute hold time. Passing the room integrity test in accordance with Appendix C of NFPA 2001 or equal shall validate room integrity. Fan test utilizing a temporary blower to pressurize the space and an air measuring system to determine the leakage is the responsibility of this installer. This test will occur with the automatic dampers in a closed position. If for any reason the fan test should fail, the installer will assist any related General Contractors to repair the room and retest as necessary until the room passes the test.
- B. Include 12 hours of training for the Owner's and Owner's personnel on site on the operation and maintenance of the system. Deliver Operation and Maintenance Manuals at this time along with record drawings.

3.5 Inspections

A. The distributor/installer shall provide two (2) inspections as part of this contract during the one-year maintenance period directly after substantial completion. One at 6 months and one at 12 months after installation. Written reports, documenting these inspections, shall be provided to Marc Walker, BRH Director of Facilities.

END OF SECTION 212200

SECTION 233300 – AIR DUCT ACCESSORIES

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
 - A. Automatic Dampers
 - B. Damper Actuators
 - C. Duct Access Door
- 1.2 RELATED REQUIREMENTS
 - A. Section 211300 Fire-Suppression Sprinkler Systems: Piping Materials
 - B. Section 280513 Conductors and Cables for Electronic Safety and Security
 - C. Section 280528 Pathways for Electronic Safety and Security
 - D. Section 284621.11 Addressable Fire Alarm System

1.3 REFERENCE STANDARDS

- A. NFPA 90A Standard for the Installation of Air-Conditioning and Ventilating Systems; National Fire Protection Association; 2009.
- B. NFPA 92A Standard for Smoke-Control Systems Utilizing Barriers and Pressure Differences; 2009.
- C. SMACNA (DCS) HVAC Duct Construction Standards Metal and Flexible; Sheet Metal and Air Conditioning Contractors' National Association; 2005.
- D. UL 555 Standard for Fire Dampers; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.1.4 SUBMITTALS
- A. See Division 1 Submittal Procedures.
- B. Product Data: Provide for shop fabricated assemblies including volume control dampers. Include electrical characteristics and connection requirements.
- C. Project Record Drawings: Record actual locations of access doors and test holes.
- D. Maintenance Materials: Furnish the following for OWNER's use in maintenance of project.
 - 1. See Division 1 Product Requirements, for additional provisions.

SECTION 233300 – AIR DUCT ACCESSORIES

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
- B. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect dampers from damage to operating linkages and blades.

PART 2 - PRODUCTS

2.1 AUTOMATIC DAMPERS

A. Manufacturers:

- 1. Ruskin Model CD60
- 2. Air Balance.
- 3. Johnson Control.
- B. Dampers: 14 gage galvanized steel air foil shaped dampers with vinyl bulb or neoprene edging and flexible metal compression edge seals in 16 gage galvanized steel hat channel frame. Bearings shall be corrosion resistant, permanently lubricated, stainless steel sleeve type. Axles shall be plated steel type positively locked in damper blade. Damper blades positioned across short air opening dimension. Parallel blades for positive.
- C. Low leakage type with maximum 2 percent leakage at 4 inch wg differential pressure when sized for 2000 fpm face velocity.

2.2 DAMPER ACTUATOR

A. Manufacturers:

- 1. Belimo
- 2. Johnson Control
- 3. Greenheck
- B. Provide smooth proportional control with sufficient power for air velocities 20 percent greater than maximum design velocity and to provide tight seal against maximum system pressures. Provide spring return for two position control and for fail safe operation.
- C. Electric damper actuators shall be direct shaft mounted and use a V-bolt and toothed V-clamp causing a cold weld effect for positive gripping. Single bolt or setscrew type fasteners are not acceptable.

SECTION 233300 – AIR DUCT ACCESSORIES

2.3 DUCT ACCESS DOORS

A. Manufacturers:

- 1. Air Balance
- 2. Durodyne
- 3. Ventlock
- 4. Ruskin Company
- B. Fabricate in accordance with SMACNA HVAC Duct Construction Standards Metal and Flexible, and as indicated. Submittal is required.
- C. Fabrication: Rigid and close fitting of reinforced galvanized steel with closed cell neoprene sponge rubber sealing gaskets and quick fastening locking devices. For insulated ductwork, install minimum 1 inch thick insulation with sheet metal cover.
 - 1. Less Than 12 inches square, secure with sash locks.
 - 2. Sash Lock: Similar to Ventlock Model 90.
 - 3. Hinge: to be zinc plated steel, minimum 2 x 1-1/2 inches wide or 1-1/2 inch wide piano hinge. Similar to Ventlock Model 150, 157 or 167, 250.
 - 4. Access panels with sheet metal screw fasteners are not acceptable.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Verify that electric power is available and of the correct characteristics.
- B. Verify ducts and equipment installations are ready for accessories.

3.2 INSTALLATION

- A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMACNA HVAC Duct Construction Standards Metal and Flexible.
- B. Provide duct access doors for inspection and cleaning before and after automatic dampers, at fire dampers, combination fire and smoke dampers, and elsewhere as indicated. Provide minimum 6 x 6 inch size for access. Review locations prior to fabrication.

END OF SECTION 233300

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Steel slotted support systems.
- 2. Conduit and cable support devices.
- 3. Mounting, anchoring, and attachment components, including powder-actuated fasteners, mechanical expansion anchors, concrete inserts, clamps, through bolts, toggle bolts, and hanger rods.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:
 - a. Slotted support systems, hardware, and accessories.
 - b. Clamps.
 - c. Hangers.
 - d. Fasteners.
 - e. Anchors.
 - f. Saddles.
 - g. Brackets.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame Rating: Class 1.
 - 2. Self-extinguishing according to ASTM D 635.

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32-inch-(10-mm-) diameter holes at a maximum of 8 inches (200 mm) o.c. in at least one surface.
 - 1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 - 2. Material for Channel, Fittings, and Accessories: Plain steel.
 - 3. Channel Width: Selected for applicable load criteria.
 - 4. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-
- B. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- C. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
 - 1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - 2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - 3. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
 - 4. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
 - 5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
 - 6. Toggle Bolts: All-steel springhead type.
 - 7. Hanger Rods: Threaded steel.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with the following standards for application and installation requirements of hangers and supports, except where requirements on Drawings or in this Section are stricter:
 - 1. NECA 1.
 - 2. NECA 101
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceways: Space supports for EMT as required by NFPA 70. Minimum rod size shall be 1/4 inch (6 mm) in diameter.
- C. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch (38-mm) and smaller raceways serving branch circuits and communication systems above suspended ceilings, and for fastening raceways to trapeze supports.

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, according to NFPA 70.
- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 3. To Existing Concrete: Expansion anchor fasteners.
 - 4. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches (100 mm) thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches (100 mm) thick.
 - 5. To Steel: Spring-tension clamps.
 - 6. To Light Steel: Sheet metal screws.
 - 7. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.
- E. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils (0.05 mm).

END OF SECTION 260529

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. UTP cabling.
 - 2. Fire alarm wire and cable.
 - 3. Identification products.

1.3 DEFINITIONS

- A. EMI: Electromagnetic interference.
- B. IDC: Insulation displacement connector.
- C. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control and signaling power-limited circuits.
- D. Open Cabling: Passing telecommunications cabling through open space (e.g., between the studs of a wall cavity).
- E. RCDD: Registered Communications Distribution Designer.

1.4 ADMINISTRATIVEREQUIREMENTS

A. Coordinate layout and installation of electronic safety cabling with Owner's telecommunications and LAN equipment and service suppliers.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.6 INFORMATIONAL SUBMITTALS

- A. Source quality-control reports.
- B. Field quality-control reports.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 50 or less.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 UTP CABLE

- A. Description: 100-ohm, four-pair UTP, covered with a blue thermoplastic jacket.
 - 1. Comply with ICEA S-90-661 for mechanical properties.
 - 2. Comply with TIA-568-C.1 for performance specifications.
 - 3. Comply with TIA-568-C.2, Category 5e.
 - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, General Purpose: Type CM or Type CMG.
 - b. Communications, Plenum Rated: Type CMP, complying with NFPA 262.
 - c. Multipurpose: Type MP or Type MPG.
 - d. Multipurpose, Plenum Rated: Type MPP, complying with NFPA 262.

2.3 UTP CABLE HARDWARE

- A. UTP Cable Connecting Hardware: IDC type, using modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of the same category or higher.
- B. Connecting Blocks: 110-style for Category 5e.
 - 1. packages.

2.4 FIRE ALARM WIRE AND CABLE

- A. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.
- B. Signaling Line Circuits: Twisted, shielded pair, not less than No. 18 AWG or size as recommended by system manufacturer.
 - 1. Circuit Integrity Cable: Twisted shielded pair, NFPA 70, Article 760, Classification CI, for power-limited fire alarm signal service Type FPL. NRTL listed and labeled as complying with UL 1424 and UL 2196 for a two-hour rating.

- C. Non-Power-Limited Circuits: Solid-copper conductors with 600-V rated, 75 deg C, color-coded insulation, and complying with requirements in UL 2196 for a two-hour rating.
 - 1. Low-Voltage Circuits: No. 16 AWG, minimum, in pathway.
 - 2. Line-Voltage Circuits: No. 12 AWG, minimum, in pathway.

2.5 IDENTIFICATION PRODUCTS

A. Comply with TIA-606-B and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

PART 3 - EXECUTION

3.1 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for installation of supports for cables.

3.2 WIRING METHOD

- A. Install wiring in metal pathways and wireways.
 - 1. Minimum conduit size shall be 1/2 inch, (14 mm). Control and data-transmission wiring shall not share conduits with other building wiring systems.
 - 2. Comply with requirements in Section 280528 "Pathways for Electronic Safety and Security."
- B. Install cable, concealed in accessible ceilings, walls, and floors when possible.
- C. Wiring within Enclosures:
 - 1. Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM's "Cabling Termination Practices" chapter. Cable ties shall not be excessively tightened such that the transmission characteristics of the cable are altered.
 - 2. Install lacing bars and distribution spools.
 - 3. Separate power-limited and non-power-limited conductors as recommended in writing by manufacturer.
 - 4. Install conductors parallel with or at right angles to sides and back of enclosure.
 - 5. Connect conductors associated with intrusion system that are terminated, spliced, or interrupted in any enclosure onto terminal blocks.
 - 6. Mark each terminal according to system's wiring diagrams.
 - 7. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Comply with NECA 1 and NFPA 70.
- B. Conductors: Size according to system manufacturer's written instructions unless otherwise indicated.
- C. Do not install conductors and cables that are wet, moisture damaged, or mold damaged.
- D. General Requirements for Cabling:
 - 1. Comply with TIA-568-C.1.
 - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
 - 3. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, and cross-connect and patch panels. Leave a minimum of 6 inches (150 mm) of slack at outlet terminations and coil loosely into box after termination on outlet fitting.
 - 4. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches (760 mm) and not more than 6 inches (150 mm) from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
 - 5. Maintain minimum cable bending radius during installation and termination of cables.
 - 6. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
 - 7. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions. Do not exceed manufacturer's rated cable-pulling tension.
- E. UTP Cable Installation: Install using techniques, practices, and methods that are consistent with Category 5e rating of components and that ensure Category 5e performance of completed and linked signal paths, end to end.
 - 1. Comply with TIA-568-C.2.
 - 2. Install 110-style IDC termination hardware unless otherwise indicated.
 - 3. Do not untwist UTP cables more than 1/2 inch (12 mm) from point of termination to maintain cable geometry.

F. Separation from EMI Sources:

- 1. Comply with BICSI TDMM and TIA-569-C recommendations for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
- 2. Separation between cables in grounded metallic pathways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches (75 mm).
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches (150 mm).

- 3. Separation between Cables and Electrical Motors and Transformers, 5 kVA or hp and Larger: A minimum of 48 inches (1200 mm).
- 4. Separation between Cables and Fluorescent Fixtures: A minimum of 5 inches (127 mm).

3.4 FIRE ALARM WIRING INSTALLATION

- A. Comply with NECA 1 and NFPA 72.
- B. Wiring Method: Install wiring in metal pathway according to Section 280528 "Pathways for Electronic Safety and Security."
 - 1. Install plenum cable in environmental air spaces, including plenum ceilings.
 - 2. Fire alarm circuits and equipment control wiring associated with the fire alarm system shall be installed in a dedicated pathway system. This system shall not be used for any other wire or cable.

C. Wiring Method:

- 1. Cables and pathways used for fire alarm circuits, and equipment control wiring associated with the fire alarm system, may not contain any other wire or cable.
- D. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- E. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes, cabinets, or equipment enclosures where circuit connections are made.
- F. Color Coding: Color code fire alarm conductors differently from the normal building power wiring. Use one color code for alarm circuit wiring and another for supervisory circuits. Color code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Match the existing circuits. Paint fire alarm system junction boxes and covers red.

3.5 POWER AND CONTROL-CIRCUIT CONDUCTORS

- A. 120-V Power Wiring: Install according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables" unless otherwise indicated.
- B. Minimum Conductor Sizes:
 - 1. Class 1 remote-control and signal circuits, No. 14 AWG.
 - 2. Class 2 low-energy, remote-control and signal circuits, No. 16 AWG.
 - 3. Class 3 low-energy, remote-control, alarm and signal circuits, No. 12 AWG.

3.6 CONNECTIONS

A. Comply with requirements in Section 283111 "Digital, Addressable Fire-Alarm System" for connecting, terminating, and identifying wires and cables.

3.7 FIRESTOPPING

- A. Comply with TIA-569-C, "Firestopping" Annex A.
- B. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.8 GROUNDING

A. For communication wiring, comply with J-STD-607-A and with BICSI TDMM's "Grounding, Bonding, and Electrical Protection" chapter.

3.9 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Visually inspect UTP cable jacket materials for NRTL certification markings. Inspect cabling terminations to confirm color coding for pin assignments, and inspect cabling connections to confirm compliance with TIA-568-C.1.
 - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
 - 3. Test UTP cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross connection.
 - a. Test instruments shall comply with or exceed applicable requirements in TIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- B. Document data for each measurement. Print data for submittals in a summary report that is formatted using Table 10.1 in BICSI TDMM as a guide, or transfer the data from the instrument to the computer, save as text files, print, and submit.
- C. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION 280513

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal conduits, tubing, and fittings.
 - 2. Boxes, enclosures, and cabinets.

1.3 DEFINITIONS

- A. GRC: Galvanized rigid steel conduit.
- B. IMC: Intermediate metal conduit.

PART 2 - PRODUCTS

2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. General Requirements for Metal Conduits and Fittings:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.
- B. EMT: Comply with ANSI C80.3 and UL 797.
- C. FMC: Comply with UL 1; zinc-coated steel or aluminum.
- D. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
 - 1. Fittings for EMT:
 - a. Material: Steel.
 - b. Type: Setscrew or compression.

2.2 BOXES, ENCLOSURES, AND CABINETS

- A. General Requirements for Boxes, Enclosures, and Cabinets:
 - 1. Comply with TIA-569-B.
 - 2. Boxes, enclosures and cabinets installed in wet locations shall be listed for use in wet locations.
- B. Sheet-Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- C. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- D. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- E. Device Box Dimensions: 4-inches square by 2-1/8 inches deep (100 mm square by 60 mm deep)
- F. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, **Type 1**.
 - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 - 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- G. Cabinets:
 - 1. NEMA 250, Type 1, galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.

PART 3 - EXECUTION

3.1 PATHWAY APPLICATION

- A. Indoors: Apply pathway products as specified below unless otherwise indicated:
 - 1. Exposed, Not Subject to Physical Damage: EMT.
 - 2. Exposed, Not Subject to Severe Physical Damage: EMT.
 - 3. Concealed in Ceilings and Interior Walls and Partitions: EMT.
 - 4. Pathways for Concealed General Purpose Distribution of Communications Cable: EMT.
 - 5. Boxes and Enclosures: NEMA 250, Type 1.
- B. Minimum Pathway Size: 1/2-inch (16-mm) trade size.
- C. Pathway Fittings: Compatible with pathways and suitable for use and location.
 - 1. EMT: Use setscrew or compression, steel fittings. Comply with NEMA FB 2.10.
 - 2. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.

3.2 INSTALLATION

- A. Comply with NECA 1, NECA 101, and TIA-569-B for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NFPA 70 limitations for types of pathways allowed in specific occupancies and number of floors.
- B. Keep pathways at least 6 inches (150 mm) away from parallel runs of flues and steam or hotwater pipes. Install horizontal pathway runs above water and steam piping.
- C. Complete pathway installation before starting conductor installation.
- D. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Install no more than the equivalent of three 90-degree bends in any conduit run except for communications wiring conduits for which only two 90-degree bends are allowed. Support within 12 inches (300 mm) of changes in direction.
- F. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- G. Support conduit within 12 inches (300 mm) of enclosures to which attached.
- H. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install insulated bushings on conduits terminated with locknuts.
- I. Install pathways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- J. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to conduit assembly to assure a continuous ground path.
- K. Cut conduit perpendicular to the length.
- L. Install pull wires in empty pathways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire. Cap underground pathways designated as spare above grade alongside pathways in use.
- M. Pathways for Communications Cable: Install pathways, metal, rigid and flexible, as follows:
 - 1. 3/4-Inch (21-mm) Trade Size and Smaller: Install pathways in maximum lengths of 50 feet (15 m).
 - 2. 1-Inch (27-mm) Trade Size and Larger: Install pathways in maximum lengths of 75 feet (23 m).
 - 3. Install with a maximum of two 90-degree bends or equivalent for each length of pathway unless Drawings show stricter requirements. Separate lengths with pull or junction boxes or terminations at distribution frames or cabinets where necessary to comply with these requirements.

- N. Flexible Conduit Connections: Comply with NEMA RV 3. Use maximum of 72 inches (1830 mm) of flexible conduit for equipment subject to vibration, noise transmission, or movement.
- O. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
- P. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.

3.3 FIRESTOPPING

A. Install fire stopping at penetrations of fire-rated floor and wall assemblies.

3.4 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.

END OF SECTION 280528

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Manual fire-alarm boxes.
 - 2. System smoke detectors.
 - 3. Notification appliances.
 - 4. Addressable interface device.
 - 5. Network communications.

B. Related Requirements:

- 1. Section 212200 "Clean Agent Fire Extinguishing System" for the extinguishing system.
- 2. Section 280513 "Conductors and Cables for Electronic Safety and Security " for cables and conductors for fire-alarm systems.

1.3 DEFINITIONS

- A. EMT: Electrical Metallic Tubing.
- B. FACP: Fire Alarm Control Panel.
- C. HLI: High Level Interface.
- D. NICET: National Institute for Certification in Engineering Technologies.
- E. PC: Personal computer.
- F. VESDA: Very Early Smoke-Detection Apparatus.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product, including furnished options and accessories.
 - 1. Include construction details, material descriptions, dimensions, profiles, and finishes.
 - 2. Include rated capacities, operating characteristics, and electrical characteristics.
- B. Shop Drawings: For fire-alarm system.

- 1. Comply with recommendations and requirements in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
- 2. Include plans, elevations, sections, details, and attachments to other work.
- 3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations. Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.
- 4. Detail assembly and support requirements.
- 5. Include voltage drop calculations for notification-appliance circuits.
- 6. Include battery-size calculations.
- 7. Include input/output matrix.
- 8. Include statement from manufacturer that all equipment and components have been tested as a system and meet all requirements in this Specification and in NFPA 72.
- 9. Include performance parameters and installation details for each detector.
- 10. Include floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits and point-to-point wiring diagrams.
- 11. Incorporate system modifications and additions to the present asbuilt drawings, illustrating the entire system.

C. General Submittal Requirements:

- 1. Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect.
- 2. Shop Drawings shall be prepared by persons with the following qualifications:
 - a. Trained and certified by manufacturer in fire-alarm system design.
 - b. NICET-certified, fire-alarm technician; Level IV minimum.
 - c. Licensed or certified by authorities having jurisdiction.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Field quality-control reports.
- 1.6 Sample Warranty: For special warranty.

1.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals.
 - 1. Include the following:
 - a. Comply with the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.

- b. Provide "Fire Alarm and Emergency Communications System Record of Completion Documents" according to the "Completion Documents" Article in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
- c. Complete wiring diagrams showing connections between all devices and equipment. Each conductor shall be numbered at every junction point with indication of origination and termination points.
- d. Riser diagram.
- e. Device addresses.
- f. Record copy of site-specific software.
- g. Provide "Inspection and Testing Form" according to the "Inspection, Testing and Maintenance" chapter in NFPA 72, and include the following:
 - 1) Equipment tested.
 - 2) Frequency of testing of installed components.
 - 3) Frequency of inspection of installed components.
 - 4) Requirements and recommendations related to results of maintenance.
 - 5) Manufacturer's user training manuals.
- h. Manufacturer's required maintenance related to system warranty requirements.
- i. Abbreviated operating instructions for mounting at fire-alarm control unit and each annunciator unit.
- B. Software and Firmware Operational Documentation:
 - 1. Software operating and upgrade manuals.
 - 2. Program Software Backup: On magnetic media or compact disk, complete with data files.
 - 3. Device address list.
 - 4. Printout of software application and graphic screens.

1.8 QUALITY ASSURANCE

A. Installer Qualifications: Installation shall be by personnel certified by NICET as fire-alarm Level II technician.

1.9 PROJECT CONDITIONS

- A. Perform a full test of the existing system prior to starting work. Document any equipment or components not functioning as designed.
- B. Interruption of Existing Fire-Alarm Service: Do not interrupt fire-alarm service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary guard service according to requirements indicated:
 - 1. Notify Construction Manager no fewer than seven days in advance of proposed interruption of fire-alarm service.
 - 2. Do not proceed with interruption of fire-alarm service without Construction Manager's written permission.

C. Use of Devices during Construction: Protect devices during construction unless devices are placed in service to protect the facility during construction.

1.10 SEQUENCING AND SCHEDULING

- A. Existing Fire-Alarm Equipment: Maintain existing equipment fully operational until new equipment has been tested and accepted. As new equipment is installed, label it "NOT IN SERVICE" until it is accepted. Remove labels from new equipment when put into service, and label existing fire-alarm equipment "NOT IN SERVICE" until removed from the building.
- B. Equipment Removal: After acceptance of new fire-alarm system, remove existing disconnected fire-alarm equipment and wiring.

1.11 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace fire-alarm system equipment and components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Extent: All equipment and components not covered in the Maintenance Service Agreement.
 - 2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- A. Source Limitations for Fire-Alarm System and Components: Components shall be compatible with, and operate as an extension of the existing system. Provide system manufacturer's certification that all components provided have been tested as, and will operate as, a system.
- B. Noncoded, UL-certified addressable system, with multiplexed signal transmission and voice and horn/strobe evacuation.
- C. Automatic sensitivity control of certain smoke detectors.
- D. All components provided shall be listed for use with the selected system.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 SYSTEMS OPERATIONAL DESCRIPTION (Supplemental to the Existing System)

- A. Fire-alarm signal initiation shall be by one or more of the following devices and systems:
 - 1. Manual stations.
 - 2. Smoke detectors.

- 3. Fire-extinguishing system operation.
- B. Fire-alarm signal shall initiate the following actions:
 - 1. Continuously operate alarm notification appliances.
 - 2. Identify alarm and specific initiating device at fire-alarm control unit, connected network control panels, and remote annunciators.
 - 3. Transmit an alarm signal to the remote alarm receiving station.
 - 4. Switch heating, ventilating, and air-conditioning equipment controls to fire-alarm mode.
 - 5. Close smoke dampers in air ducts of designated air-conditioning duct systems.
 - 6. Record events in the system memory.
 - 7. Record events by the system printer.
 - 8. Indicate device in alarm on the graphic annunciator.
- C. Supervisory signal initiation shall be by one or more of the following devices and actions:
 - 1. Valve supervisory switch.
 - 2. Independent fire-detection and -suppression systems.
 - 3. User disabling of zones or individual devices.
 - 4. Loss of communication with any panel on the network.
- D. System trouble signal initiation shall be by one or more of the following devices and actions:
 - 1. Open circuits, shorts, and grounds in designated circuits.
 - 2. Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
 - 3. Loss of communication with any addressable sensor, input module, relay, control module, remote annunciator, printer interface, or Ethernet module.
 - 4. Loss of primary power at fire-alarm control unit.
 - 5. Ground or a single break in internal circuits of fire-alarm control unit.
 - 6. Abnormal ac voltage at fire-alarm control unit.
 - 7. Break in standby battery circuitry.
 - 8. Failure of battery charging.
 - 9. Abnormal position of any switch at fire-alarm control unit or annunciator.
- E. System Supervisory Signal Actions:
 - 1. Initiate notification appliances.
 - 2. Identify specific device initiating the event at fire-alarm control unit, connected network control panels, and remote annunciators.
 - 3. Record the event on system printer.
 - 4. After a time delay, transmit a trouble or supervisory signal to the remote alarm receiving station.
 - 5. Display system status on graphic annunciator.

2.3 MANUAL FIRE-ALARM BOXES

A. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes shall be finished in red with molded, raised-letter operating instructions in contrasting color; shall show

visible indication of operation; and shall be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.

- 1. Double-action mechanism requiring two actions to initiate an alarm, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to fire-alarm control unit.
- 2. Station Reset: Key- or wrench-operated switch.
- 3. Indoor Protective Shield: Factory-fabricated, clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm. Lifting the cover actuates an integral battery-powered audible horn intended to discourage false-alarm operation.

2.4 SYSTEM SMOKE DETECTORS

A. General Requirements for System Smoke Detectors:

- 1. Comply with UL 268; operating at 24-V dc, nominal.
- 2. Detectors shall be two-wire type.
- 3. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.
- 4. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
- 5. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
- 6. Integral Visual-Indicating Light: LED type, indicating detector has operated.
- 7. Remote Control: Unless otherwise indicated, detectors shall be digital-addressable type, individually monitored at fire-alarm control unit for calibration, sensitivity, and alarm condition.

B. Photoelectric Smoke Detectors:

- 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).

C. Ionization Smoke Detector:

- 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:

- a. Primary status.
- b. Device type.
- c. Present average value.
- d. Present sensitivity selected.
- e. Sensor range (normal, dirty, etc.).

2.5 NOTIFICATION APPLIANCES

- A. General Requirements for Notification Appliances: Individually addressed, connected to a signaling-line circuit, equipped for mounting as indicated, and with screw terminals for system connections.
- B. Horns: Electric-vibrating-polarized type, 24-V dc; with provision for housing the operating mechanism behind a grille. Comply with UL 464. Horns shall produce a sound-pressure level of 90 dBA, measured 10 feet (3 m) from the horn, using the coded signal prescribed in UL 464 test protocol.
- C. Visible Notification Appliances: Xenon strobe lights complying with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.
 - 1. Rated Light Output:
 - a. 15/30/75/110 cd, selectable in the field.
 - 2. Mounting: Wall mounted unless otherwise indicated.
 - 3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
 - 4. Flashing shall be in a temporal pattern, synchronized with other units.
 - 5. Strobe Leads: Factory connected to screw terminals.
 - 6. Mounting Faceplate: Factory finished, red.

2.6 ADDRESSABLE INTERFACE DEVICE

A. General:

- 1. Include address-setting means on the module.
- 2. Store an internal identifying code for control panel use to identify the module type.
- B. Monitor Module: Microelectronic module providing a system address for alarm-initiating devices for wired applications with normally open contacts.
- C. Integral Relay: Capable of providing a direct signal.
 - 1. Allow the control panel to switch the relay contacts on command.
 - 2. Have a minimum of two normally open and two normally closed contacts available for field wiring.

D. Control Module:

- 1. Operate notification devices.
- 2. Operate solenoids for use in fire extinguisher system.

2.7 NETWORK COMMUNICATIONS

- A. Provide network communications for fire-alarm system according to fire-alarm manufacturer's written requirements.
- B. Provide network communications pathway per manufacturer's written requirements and requirements in NFPA 72 and NFPA 70.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements for ventilation, temperature, humidity, and other conditions affecting performance of the Work.
 - 1. Verify that manufacturer's written instructions for environmental conditions have been permanently established in spaces where equipment and wiring are installed, before installation begins.
- B. Examine roughing-in for electrical connections to verify actual locations of connections before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72, NFPA 101, and requirements of authorities having jurisdiction for installation and testing of fire-alarm equipment. Install all electrical wiring to comply with requirements in NFPA 70 including, but not limited to, Article 760, "Fire Alarm Systems."
 - 1. Devices placed in service before all other trades have completed cleanup shall be replaced.
 - 2. Devices installed but not yet placed in service shall be protected from construction dust, debris, dirt, moisture, and damage according to manufacturer's written storage instructions.
- B. Connecting to Existing Equipment: Verify that existing fire-alarm system is operational before making changes or connections.
 - 1. Connect new equipment to existing control panel in existing part of the building.
 - 2. Connect new equipment to existing monitoring equipment at the supervising station.

- 3. Expand, modify, and supplement existing **control** and **monitoring** equipment as necessary to extend existing **control** and **monitoring** functions to the new points. New components shall be capable of merging with existing configuration without degrading the performance of either system.
- C. Install wall-mounted equipment, with tops of cabinets not more than 78 inches (1980 mm) above the finished floor.

D. Manual Fire-Alarm Boxes:

- 1. Install manual fire-alarm box in the normal path of egress within 60 inches (1520 mm) of the exit doorway.
- 2. Mount manual fire-alarm box on a background of a contrasting color.
- 3. The operable part of manual fire-alarm box shall be between 42 inches (1060 mm) and 48 inches (1220 mm) above floor level. All devices shall be mounted at the same height unless otherwise indicated.
- E. Install a cover on each smoke detector that is not placed in service during construction. Cover shall remain in place except during system testing. Remove cover prior to system turnover.
- F. Remote Status and Alarm Indicators: Install in a visible location near each smoke detector, sprinkler water-flow switch, and valve-tamper switch that is not readily visible from normal viewing position.
- G. Audible Alarm-Indicating Devices: Install not less than 6 inches (150 mm) below the ceiling. Install bells and horns on flush-mounted back boxes with the device-operating mechanism concealed behind a grille. Install all devices at the same height unless otherwise indicated.
- H. Visible Alarm-Indicating Devices: Install adjacent to each alarm bell or alarm horn and at least 6 inches (150 mm) below the ceiling. Install all devices at the same height unless otherwise indicated.

3.3 PATHWAYS

- A. Pathways above recessed ceilings and in nonaccessible locations may be routed exposed.
- B. Pathways shall be installed in EMT.
- C. Exposed EMT shall be painted red enamel.

3.4 CONNECTIONS

- A. Make addressable connections with a supervised interface device to the following devices and systems. Install the interface device less than 36 inches (910 mm) from the device controlled. Make an addressable confirmation connection when such feedback is available at the device or system being controlled.
 - 1. Smoke dampers in air ducts of designated HVAC duct systems.

2. Supervisory connections at fire-extinguisher locations.

3.5 IDENTIFICATION

A. Install framed instructions in a location visible from fire-alarm control unit.

3.6 GROUNDING

A. Ground shielded cables at the control panel location only. Insulate shield at device location.

3.7 FIELD QUALITY CONTROL

- A. Field tests shall be witnessed by authorities having jurisdiction.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections.
- D. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 - 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection shall be based on completed record Drawings and system documentation that is required by the "Completion Documents, Preparation" table in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
 - b. Comply with the "Visual Inspection Frequencies" table in the "Inspection" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
 - 2. System Testing: Comply with the "Test Methods" table in the "Testing" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
 - 4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
 - 5. Test visible appliances for the public operating mode according to manufacturer's written instructions.
 - 6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" section of the "Fundamentals" chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
- E. Reacceptance Testing: Perform reacceptance testing to verify the proper operation of added or replaced devices and appliances.

- F. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- I. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.8 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

END OF SECTION 284621.11