
SHEET NO.
1 OF 8
2 OF 8
3 OF 8
4 OF 8
5 OF 8
6 OF 8
7 OF 8
8 OF 8

# JDWWTP AERATION BASIN FLOOR OVERLAYS

CONTRACT NO. BE18-229







PLANS DEVELOPED BY: DOWL 5368 COMMERCIAL BOULEVARD JUNEAU, ALASKA 99801 907-780-3533 AECL848

\_\_\_\_

WHERE CONDITIONS ARE ENCOUNTERED WHICH APPEAR DIFFERENT FROM THOSE INDICATED ON THE PLANS OR IN THE SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY THE

ENGINEER PRIOR TO THE PERFORMANCE OF WORK. ALL WORK AND MATERIALS NOT INCLUDED IN THE PROJECT SPECIFICATIONS SHALL CONFORM TO THE CITY AND BOROUGH OF JUNEAU STANDARD SPECIFICATIONS FOR CIVIL ENGINEERING PROJECTS AND SUBDIVISION IMPROVEMENTS DECEMBER 2003 EDITION INCLUDING ERRATA AND MODIFICATIONS THERETO. IN CASE OF A CONFLICT BETWEEN

REGULATORY OR STANDARD SPECIFICATIONS, THE MORE STRINGENT REQUIREMENT WILL PREVAIL.

CONSTRUCTION SAFETY AND SANITATION FACILITIES FOR WORKERS SHALL BE PROVIDED BY THE CONTRACTOR AND MAINTAINED PER THE REQUIREMENTS OF AUTHORITIES HAVING

THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ANY AND ALL WORK IN THE AREA WITH THE PROJECT ENGINEER AND CBJ STAFF PRIOR TO BEGINNING ANY WORK ON

THIS PROJECT. THE CONTRACTOR SHALL COORDINATE WITH CBJ STAFF FOR LOCKOUT AND TAG OUT AND OPERATION OF EXISTING VALVES AND PUMPS AND ON OPERATIONAL ASPECTS OF PLANT

THE CONTRACTOR IS TO COMPLY WITH ALL PERMIT CONDITIONS AND RESTRICTIONS.

CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL, USING WATER OR OTHER METHODS APPROVED BY THE REPRESENTATIVE.

CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A SAFE SITE DURING BOTH WORKING & NON-WORKING HOURS.

REFER TO THE PROJECT SPECIFICATION (SECTION 01100) FOR EXISTING FACILITY SHUT DOWN ALLOWANCES AND CONSTRUCTION CONSTRAINTS.

CONTRACTOR SHALL ABIDE BY CBJ WWTP HOURS AND SECURITY ARRANGEMENTS AND SHALL GIVE 72 HOURS NOTICE IF WORK WILL OCCUR OUTSIDE NORMAL HOURS OF OPERATION

PROJECT DEADLINES AND SEQUENCING					
PERIOD	COMPLETION DATE	REQUIREMENTS			
SUBSTANTIAL COMPLETION	NOV 30, 2018	THE SOUTH SUMP, AUXILLARY SUMP, AND BASIN FLOOR OVERLAY FOR BOTH BASINS SHALL BE READY FOR THEIR INTENDED USE (INCLUSIVE OF A 7-DAY CURING PERIOD FOR ALL CONCRETE).			
FINAL	DEC 15, 2018	ALL WORK SHALL BE COMPLETE.			
ADDITIONAL OFFICIAND NOTES AND DECUMPRISTS					

#### ADDITIONAL SEQUENCING NOTES AND REQUIREMENTS:

- A WORK ON AERATION BASIN TWO SHALL BE COMPLETED BEFORE WORK ON AERATION BASIN ONE.
- B THE EVACUATION OF WASTEWATER AND CLEANING OF AERATION BASINS ONE AND TWO WILL BE PERFORMED BY CBJ WASTEWATER PERSONNEL. BASIN TWO IS CURRENTLY EMPTY AND WILL REMAIN EMPTY UNTIL MAY 10, 2018. THE BASIN WILL BE FLOODED FOR THE SUMMER AND RE-EVACUATED BY OCTOBER 1, 2018.
- C CBJ WASTEWATER PERSONNEL SHALL BE ALLOTTED 10 DAYS AFTER A 7-DAY CURING PERIOD FOR THE BASIN TWO OVERLAY TO FLOOD BASIN TWO AND CLEAN BASIN ONE BEFORE WORK MAY COMMENCE ON BASIN ONE.

## SECURITY GATE (SEE NOTE 11) SECURITY GATE **WWTP CLARIFIER** BASIN DISINFECTION DIGESTER CONTRACTOR **ACCESS ROUTE** 80'X80' STAGING AREA TO BE-USED FOR BOTH BASINS. **SOLIDS** HANDLING

#### **GENERAL PROJECT LEGEND**

#### **EXISTING ITEMS NEW ITEMS** EXISTING LIGHT POLE PROPOSED EQUIPMENT & PIPING EXISTING CONTOUR (0.01' INTERVAL) EXISTING EDGE OF ASPHALT EXISTING ELECTRIC METER PROPOSED DISCHARGE PIPE EXISTING EDGE OF GRAVEL **EXISTING JUNCTION BOX** --- SAWCUT LINE **EXISTING FENCE-BARBWIRE** EXISTING STORM CULVERT -GB---GRADE BREAK **EXISTING PROPERTY LINE** EXISTING SANITARY SEWER MAIN --- STORM DRAIN EXISTING SANITARY SEWER MANHOLE EXISTING EASEMENT EXISTING RAILROAD R.O.W. EXISTING WATER MAIN EXISTING STORM DRAIN EXISTING GATE VALVE EXISTING SIGN EXISTING FIRE HYDRANT **EXISTING GAS LINE** EXISTING PIPE EXISTING FIBER OPTICS LINE EXISTING EQUIPMENT TO BE REMOVED EXISTING TELE/COMMUNICATION LINE EXISTING EQUIPMENT TO BE RELOCATED **EXISTING PEDESTAL** DEMOLITION LIMITS EXISTING OVERHEAD POWER **EXISTING BURIED POWER** EXISTING UTILITY POLE

### PROJECT AREA MAP

CBJ STAFF CONTACT INFORMATION: NAME: RANDY BROWN PHONE: (907) 321-3827

ENGINEER CONTACT INFORMATION: NAME: JOHN SCOTT PHONE: (907) 780-3533

#### **ABBREVIATIONS**

B.O.C. C.B.J.	CITY AND BOROUGH OF JUNEAU		MANHOLE MINIMUM
CL		MS	
CONC.		MTE	
CTR	CORRUGATED POLYETHYLENE PIPE CONTACTOR		
D.I.		OL OP	OVERLOAD OVERELOW DIDE
DIA	DIAMETER	OP DED	
DP		PFD PLC	
EA		PLC	CONTROLLER
	ELEVATION	PV	
F.C.A.			POLYVINYL CHLORIDE PIPE
FIG		RGS	
FL	FLANGE	S=	
FT	FEET	SEQ.	
GRV	GROOVED	SBR	
GND	GROUND	TBC	
IC	INFLUENT CHANNEL	T.O.C.	TOP OF CONCRETE
I.E.	INVERT ELEVATION	T.O.S.	TOP OF SLAB
IP	SBR INFLUENT PIPE	TP	TOP OF PAVEMENT
INV.	INVERI	TSP	TWISTED SHIELD PAIR
LF	LINEAL FEET	(TYP)	TYPICAL
LT	LEVEL TRANSDUCER	VIC	VICTAULIC
	MOTOR CONTROL CENTER	WC	
MECH	MECHANICAL	WWM	
		WWTP	WASTEWATER TREATMENT PLANT





JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF

EXISTING UTILITY ANCHOR

PLANS DEVELOPED BY: 5368 COMMERCIAL BOULEVARD JUNEAU, ALASKA 99801 907-780-3533

Consulting Engineers • Land Surveyors • Construction Administration CHECKED BY: STAFF DATE: MAR. 2018




JDWWTP AERATION BASIN FLOOR OVERLAYS CONTRACT NO. BE18-229

LEGEND, ABBREVIATIONS, **GENERAL NOTES AND PROJECT AREA**  SHEET NO.

2 01

8



749th ★ mR Holls



PLANS DEVELOPED BY: DOWL 5368 COMMERCIAL BOULEVARD JUNEAU, ALASKA 99801 907-780-3483

Consulting Engineers • Land Surveyors • Construction Administration JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF CHECKED BY: STAFF DATE: MAR. 2018




JDWWTP AERATION BASIN FLOOR OVERLAYS CONTRACT NO. BE18-229

**AS-BUILT BASINS** 


3 of

8



JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF

CHECKED BY: STAFF DATE: MAR. 2018




CONTRACT NO. BE18-229

8

Consulting Engineers • Land Surveyors • Construction Administration

CHECKED BY: STAFF DATE: MAR. 2018

JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF



FLOOR OVERLAYS

CONTRACT NO. BE18-229

of


8

AND GENERAL DETAILS

Consulting Engineers • Land Surveyors • Construction Administration

CHECKED BY: STAFF DATE: MAR. 2018

JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF





JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF

CHECKED BY: STAFF DATE: MAR. 2018

CONTRACT NO. BE18-229

8





AUXILLARY PUMP SUMP - PLAN ENLARGEMENT

SUMP MAY BE PRE-CAST OR CAST-IN-PLACE.
ALL JOINTS BETWEEN NEW AND OLD CONCRETE OR SEPARATE POURS OF NEW
CONCRETE SHALL HAVE HYDROPHILIC WATER STOP. SEE DETAIL A, SHEET 6.





TWO VERTICAL WALLS)

PLANS DEVELOPED BY: DOWL 5368 COMMERCIAL BOULEVARD JUNEAU, ALASKA 99801 907-780-3533

Consulting Engineers • Land Surveyors • Construction Administration JOB No. J70926.02 DRAWN BY: STAFF DESIGNED BY: STAFF CHECKED BY: STAFF DATE: MAR. 2018

SECTION



JDWWTP AERATION BASIN FLOOR OVERLAYS CONTRACT NO. BE18-229

**AUXILIARY PUMP SUMP DETAILS** 

SHEET NO. 8

of 8