

INFORMATION TO BIDDERS

for the

RAINFOREST RECOVERY CENTER DETOX ADDITION

Contract No. BE19-173

ISSUED BY:

City and Borough of Juneau ENGINEERING DEPARTMENT 155 South Seward Street Juneau, Alaska 99801

Date Issued: April 25, 2019

The following information is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php. This is *not* an addendum.

CLARIFICATIONS:

Question: "012300 Alternates 3.1 B. Alternate No. 2: OFFICE RENOVATION

1. Perform selective demolition and improvements to south offices and Activity 140 as detailed in the construction documents...

A004 Finish Schedule Additive Alternate 2 does not list any finishes being done in Activity 140.

Drawing A202 shows this area and calls it out detailed on 2/A403.

1/A403 shows no casework in Activity 140.

2/A403 shows casework in Activity A140...encompassed in the Alternate 2 work area.

It appears the casework is being added?...but there is not an elevation of what the casework is to be. Is this information that can be provided?"

Response:

New casework and countertop exists under the new sink and will be similar to the sink and cabinet shown on 1/A501 with the elimination of cabinets and countertop to the left of the sink and no upper cabinets.

