



ADDENDUM TO THE CONTRACT

for the

**Downtown Waterfront Improvements Phase I
Contract No. DH19-014**

ADDENDUM NO.: Three

CURRENT DEADLINE FOR BIDS:
July 2, 2019

PREVIOUS ADDENDA: Two

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED:

June 21, 2019

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: <http://www.juneau.org/engineering ftp/contracts/Contracts.php>

PROJECT MANUAL:

Item No. 1 SECTION 00310 Bid Schedule
DELETE in its entirety and ***REPLACE*** with SECTION 00310 Bid Schedule labeled Addendum 3 that is attached.

By: 
Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 5

SECTION 00310 – BID SCHEDULE

BASE BID

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
1505.1	Mobilization	LS	All Req'd	Lump	Sum	\$	
1510.1	Field Office	LS	All Req'd	Lump	Sum	\$	
1520.1	Temporary Security Fencing	LF	1,000			\$	
1550.1	Site Access and Traffic Control	LS	All Req'd	Lump	Sum	\$	
1570.1	Erosion and Sediment Control	LS	All Req'd	Lump	Sum	\$	
2060.1	Demolition, Salvage and Disposal	LS	All Req'd	Lump	Sum	\$	
2201.1	Clearing and Grubbing	LS	All Req'd	Lump	Sum	\$	
2202.1	Mining Area Restoration and Road Cleaning Guarantee	CS	All Req'd	Cont	Sum	\$10,000	00
2202.2	Unusable Excavation	CY	1,000			\$	
2202.3	Usable Excavation	CY	3,000			\$	
2202.4	Class A Shot Rock Borrow	TON	7,000			\$	
2204.1	Roadway Base Course	CY	300			\$	
2205.1	Place Salvaged Armor Rock	CY	500			\$	
2205.2	Class III Armor Rock	TON	2,000			\$	
2350.1	Reconfigure HDPE Utilities at ADA Approach Ramp	LS	All Req'd	Lump	Sum	\$	
2401.1	HDPE Gravity Sewer Pipe – Buried and Suspended	LS	All Req'd	Lump	Sum	\$	
2401.2	HDPE Pressure Sewer Pipe and Connection to Existing	LS	All Req'd	Lump	Sum	\$	
2402.1	Utility Access Manhole, Type I	EA	2			\$	
2410.1	Sewer Lift Station	LS	All Req'd	Lump	Sum	\$	
2501.1	6-Inch PVC Storm Drain Pipe	LF	54			\$	
2501.2	18-Inch CPP Storm Drain Pipe	LF	82			\$	
2501.3	24-Inch CPP Storm Drain Pipe	LF	20			\$	

BIDDER: _____

SECTION 00310 – BID SCHEDULE

2501.4	Temporary Drainage Bypass System	LS	All Req'd	Lump	Sum	\$	
2502.1	Storm Drain Manhole, Type I	EA	1			\$	
2502.2	Oil Water Separator Manhole	EA	1			\$	
2502.3	Inlet Box, Curb Inlet Frame and Grate	EA	1			\$	
2502.4	Trench Drain	LS	All Req'd	Lump	Sum	\$	
2502.5	Deck or Planter Drain	EA	24			\$	
2502.6	Floor Drain	EA	2			\$	
2601.1	HDPE Water Pipe – Buried and Suspended With Connection to Existing	LS	All Req'd	Lump	Sum	\$	
2603.1	Fire Hydrant	EA	1			\$	
2607.1	Pipe Insulation	BD	20			\$	
2702.1	Construction Surveying	LS	All Req'd	Lump	Sum	\$	
2718.1	Sign Assemblies	LS	All Req'd	Lump	Sum	\$	
2720.1	Painted Traffic Markings	LS	All Req'd	Lump	Sum	\$	
2726.1	Structural Deck System – Steel Pile Caps and Timber Stringers	LS	All Req'd	Lump	Sum	\$	
2726.2	4X Timber Decking	SF	2,400			\$	
2726.3	6X Timber Decking	SF	14,100			\$	
2726.4	Seawalk Timber Deck Modifications	LS	All Req'd	Lump	Sum	\$	
2726.5	Overdeck Stage and Stairway With Decking	LS	All Req'd	Lump	Sum	\$	
2726.6	Lightweight Structural Fill	LS	All Req'd	Lump	Sum	\$	
2727.1	Timber Planters	LS	All Req'd	Lump	Sum	\$	
2810.1	AC Pavement Patch, 4 Inch Thick	LS	All Req'd	Lump	Sum	\$	
2882.1	Contingent Work - Pile Obstruction Removal	CS	As Req'd	Cont	Sum	\$100,000	00
2896.1	Furnish Steel Pipe Pile, 16" Dia. X 0.500" Thick	LF	2,580			\$	
2896.2	Furnish Steel Pipe Pile, 18" Dia. X 0.500" Thick	LF	3,660			\$	
2896.3	Install 16" Dia. Vertical Pile	EA	18			\$	

BIDDER: _____

SECTION 00310 – BID SCHEDULE

2896.4	Install 16" Dia. Batter Pile	EA	15			\$	
2896.5	Install 18" Dia. Vertical Pile	EA	33			\$	
2896.6	Install 18" Dia. Batter Pile	EA	7			\$	
2896.7	Install 24" Dia. Vertical Pile	EA	36			\$	
2896.8	Pile Splice, 16", 18" and 24" Dia.	EA	15			\$	
2896.9	Marine Mammal Work Suspension - Pile Activity	HR	40			\$	
2996.1	Furnish & Install Pile Anode	EA	80			\$	
2996.2	Anodes Continuity Testing and Potential Readings	LS	All Reqd	Lump	Sum	\$	
3301.1	Concrete Retaining Walls	LS	All Reqd	Lump	Sum	\$	
3301.2	Concrete Structural Deck, 6" Thick	SY	1,950			\$	
3301.3	Concrete Structural Deck at Future Building, 6.5" Thick	SY	360			\$	
3301.4	Concrete Pigments and Additives	LS	All Reqd	Lump	Sum	\$	
3301.5	Concrete Curb on Structural Deck, 6"x6"	LS	All Reqd	Lump	Sum	\$	
3301.6	Concrete Curb With Scuppers on Structural Deck, 6"x18"	LS	All Reqd	Lump	Sum	\$	
3301.7	Concrete Planter and Loading Ramp Walls	LS	All Reqd	Lump	Sum	\$	
3301.8	Concrete Paving On Grade, 4" Thick	SY	50			\$	
3301.9	Concrete Paving On Grade, 8" Thick With Thickened Edges	SY	780			\$	
3302.1	Precast Concrete Bumper Curb	EA	12			\$	
3302.2	Concrete Light Pole Base	EA	4			\$	
3302.3	Concrete Electrical Equipment Rack Foundation	LS	All Reqd	Lump	Sum	\$	
3303.1	Vertical Curb	LF	150			\$	
3303.2	Driveway Curb and Gutter, All Types	LF	60			\$	
5120.1	Guardrails	LS	All Reqd	Lump	Sum	\$	
5120.2	Swing Gate and Access Platform	LS	All Reqd	Lump	Sum	\$	
5120.3	Transition Plates	LS	All Reqd	Lump	Sum	\$	

BIDDER: _____

SECTION 00310 – BID SCHEDULE

5120.4	Manway Hatch in Concrete Deck	LS	All Req'd	Lump	Sum	\$	
5120.5	Welded Steel Light Pole Bases	LS	All Req'd	Lump	Sum	\$	
5120.6	Welded Steel Electrical Equipment Racks and Attachment Bases	LS	All Req'd	Lump	Sum	\$	
8800.1	Glass Panels Attached to Guardrails and Gate	LS	All Req'd	Lump	Sum	\$	
13130.1	Parking Canopy	LS	All Req'd	Lump	Sum	\$	
16000.1	Electrical Power and Lighting	LS	All Req'd	Lump	Sum	\$	

TOTAL BID AMOUNT IN FIGURES: \$ _____

TOTAL BID AMOUNT IN WORDS: _____

BIDDER: _____

END OF SECTION