ENGINEERING DEPARTMENT

ADDENDUM TO THE CONTRACT

for the

ASPEN AVENUE IMPROVEMENTS-
MENDNEHALL BLVD TO TAKU BLVD

Contract No. BE20-142

ADDENDUM NO.: ONE

CURRENT DEADLINE FOR BIDS:
March 3, 2020

PREVIOUS ADDENDA: NONE

ISSUED BY: City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

Previous Deadline for Bids:
March 3, 2020

DATE ADDENDUM ISSUED: February 26, 2020

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering ftp/contracts/Contracts.php

CLARIFICATION:

Item No. 1 **Question:** Will the existing 6x6x6 ductile iron tee at the Taku Boulevard and Aspen Avenue be removed during construction?

Response: Yes, the existing 6x6x6 ductile iron tee at the Taku Boulevard and Aspen Avenue intersection will be removed in order to provide room to install the new 6x8x6 ductile iron tee.

PROJECT MANUAL:

Item No. 1 SECTION 00310 – BID SCHEDULE; Pay Item 2502.5, Pay Item Description, before the word "Grade" ***add*** "Adjust Existing Storm Drain Manhole to Finish"

DRAWINGS:

Item No. 1 SHEET C004, SUMMARY TABLES, SIGN ASSEMBLY TABLE, ***Delete*** "SPEED LIMIT 20 MPH" (20"X30") for both sign No. 1 & 2 and ***Replace*** with "SPEED LIMIT 20 MPH" (24"X30") ***Delete*** REMOVE AND REPLACE EXISTING "STOP" SIGN and ***Replace*** with REMOVE AND REPLACE EXISING "STOP" SIGN (30"X30")

Item No. 2 SHEET C100, TYPICAL SECTION, Mail Box Call, ***Delete*** NEW MAILBOX PER CBJ STANDARDS, SEE SUMMARY ON SHEET C004 and ***Replace*** with REINSTALL EXISTING MAILBOX AND NEWSPAPER RECEPTACLES TO NEW CANTILEVER ARM WITH NEW CONNECTING HARDWARE, SEE SUMMARY ON SHEET C004.

By:_____

Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 2