CITY AND BOROUGH OF JUNEAU
ALASKA'S CAPITAL CITY

ADDENDUM TO THE CONTRACT

for the

HOUSEHOLD HAZARDOUS WASTE FACILITY
Contract No. BE20-024

ADDENDUM NO.: **TWO**

CURRENT DEADLINE FOR BIDS:
January 28, 2020

PREVIOUS ADDENDA: **ONE**

ISSUED BY:
City and Borough of Juneau
ENGINEERING DEPARTMENT
155 South Seward Street
Juneau, Alaska 99801

DATE ADDENDUM ISSUED: **January 22, 2020**

The following items of the contract are modified as herein indicated. All other items remain the same. This addendum has been issued and is posted online. Please refer to the CBJ Engineering Contracts Division webpage at: http://www.juneau.org/engineering_ftp/contracts/Contracts.php

CLARIFICATIONS:

Question: "Where will the contractor's staging area be located?"

Response: Waste Management will make two areas available for the Contractor's use as staging areas for the duration of construction: 50-ft x 150-ft gravel surfaced area west of the Quonset hut, and 65-ft x 80-ft paved area east of the Quonset hut. Contractor to coordinate use of these areas with the Waste Management Landfill Manager, Eric Vance.

Question: "Would the owner entertain a wireless network in place of telecom hardlines? This could alleviate some amount of site work and coordination with public access."

Response: We need phone and internet capability at the office trailer.

Question: "Is the CBJ's Lemon Creek pit available for producing rock for this project?"

Response: The CBJ's North Lemon Creek Material Source (NLCMS) may be suitable as a source of rock for use in the Household Hazardous Waste Building project. Bidders interested in utilizing this material source are invited to contact the CBJ Material Sources Manager, Michael Eich (phone 586-0874, email Michael.Eich@juneau.org), to discuss their needs and get information on NLCMS site and the current conditions of use.

PROJECT MANUAL:

Item No. 1 SECTION 00310 – BID SCHEDULE
Replace with the attached SECTION 00310 – BID SCHEDULE.

Item No. 2 SPECIAL PROVISIONS - SECTION 01550 – SITE ACCESS AND STORAGE, PART 1 – GENERAL, Article 1.3, MAINTENANCE OF TRAFFIC, ***add*** the following paragraph:

"U. Vehicular access to the landfill weigh scale and the Recycle Center must be maintained during Landfill operating hours, 7:00AM-5:00PM Mon-Fri and 8:30AM-5:00PM Sat. Prior to commencing utility trenching in scale vicinity, the Contractor shall present a trenching and vehicle detour plan to the Engineer for approval. The plan must provide for uninterrupted vehicular access to/from scale and Recycle Center, and for temporary trench patching if permanent patching is unable to be placed within five days of the date the trench is first opened."

By: _____
Greg Smith,
Contract Administrator

Total number of pages contained within this Addendum: 3

SECTION 00310 - BID SCHEDULE

PAY ITEM NO.	PAY ITEM DESCRIPTION	PAY UNIT	APPROX. QUANTITY	UNIT PRICE		AMOUNT	
				DOLLARS	CENTS	DOLLARS	CENTS
1505.1	Mobilization	Lump Sum	All Req'd	Lump	Sum		
1570.1	Erosion and Sediment Control	Lump Sum	All Req'd	Lump	Sum		
2201.1	Clearing and Grubbing	Lump Sum	All Req'd	Lump	Sum		
2202.1	Excavation	CY	3,338				
2202.2	Shot Rock Borrow	CY	2,854				
2202.3	Sideslopes and Ditch Grading	Lump Sum	All Req'd	Lump	Sum		
2202.4	Mining area restoration and Road Cleaning Guarantee	Contingent Sum	All Req'd	Contingent	Sum	$5,000	00
2204.1	2-inch Minus Shot Rock with Base Course	CY	246				
2204.2	Base Course Grading D-1	Ton	246				
2401.1	Service Connection and Laterals	Each	1				
2401.2	Locate Sanitary Sewar Service	Lump Sum	All Req'd	Lump	Sum		
2401.3	Relocate Existing 4" PVC Sewer Service	Each	1				
2501.1	12-inch Pipe Culvert	LF	245				
2501.2	18-inch Pipe Culvert	LF	96				
2502.1	Storm Drain Manhole, Type 1	Each	1				
2502.2	Catch Basin, Type III	Each	2				
2605.1	1-inch Poly Water Service	Each	1				
2605.2	Locate Water Service	Lump Sum	All Req'd	Lump	Sum		
2605.3	Relocate Existing 1" Poly Water Service	Each	1				
2607.1	Pipe Insulation	Board	30				
2702.1	Construction Surveying	Lump Sum	All Req'd	Lump	Sum		
2707.1	Remove and Replace Chain Link Fence	LF	195				
2716.1	Storm Drain Pipe and Structure Removeal	Lump Sum	All Req'd	Lump	Sum		
2801.1	A.C. Pavement, Type II-A, Class B	Ton	113				
2806.1	Remove Existing Asphalt Surfacing	SY	1,128				
2901.1	Gas Infilitration Prevention System	Lump Sum	All Req'd	Lump	Sum		
3303.1	Concrete Pad, 4" Thick	SY	3				
3303.2	Concrete Pad, 6" Thick	SY	9				
16000.1	Electrical	Lump Sum	All Req'd	Lump	Sum		
133419.1	Household Hazardous Waste Building	Lump Sum	All Req'd	Lump	Sum		
133420.1	Modular Office Building	Lump Sum	All Req'd	Lump	Sum		

TOTAL BID _____

COMPANY NAME: _____